Project Report

FIELD INVESTIGATION OF VALVED SOFFIT VENTS IN POUCH COVE NL: IN SITU HOUSEHOLD VSV PERFORMANCE APRIL-JULY 2006

Submitted to:

Stormfirma Inc. c/o R. E. Platts, P.Eng Ottawa, Ontario

Submitted by:

S. Bruneau on behalf of Industrial Outreach Group Faculty of Engineering and Applied Science Memorial University of Newfoundland



PR. CM2006_01 Industrial Outreach Group November 30, 2006 St. John's, Nf. Can

Proprietary Notice

Please Note that all information, discussions, concepts, ideas and recommendations contained in this document are proprietary to the client and the author. No part of this document may be communicated to any individual other that the intended recipient without prior permission from the author.

Ð

Page

CONTENTS

1. Ba	ackground	3
2. Pr	oject Execution	3
	Scope and Plan Data Acquisition Equipment 1- Meteorological Station: 2- Pressure Transducers and Data logging Equipment Local Weather Records and Files Demobilization Data Reduction	3 4 5 8 9
3.0	Results and Analysis	10
	Observations: Uncertainty Analysis and Mitigation	12 12
4.0	Project Contacts	15
5.0	Deliverables	15
6.0	Commitment	15
Appe Appe Appe	endix A Client Draft Work Plan endix B Proposal Work Scope endix C Proposal Schedule endix D Pressure Transducer Specifications endix E Wind Environment	16 19 21 23 26



1.0 Background

Typical vulnerabilities of houses constructed prior to modern standards in the tropics include insufficient anchorage of the roof sheathing and trusses and an inadequate soffit barrier to wind-driven rain. Stormfirma Inc of Ottawa Ontario is developing products to mitigate hurricane wind and rain damage to these houses. Of particular import, Stormfirma's valved soffit vent product, or VSV, is in the latter stages of development and requires some measure of full-scale performance evaluation in an existing house prior to field trials in a hurricane-prone region later in 2006.

Prior experience of the client led to their search for a suitable test site in Newfoundland and in March 2006, a test house in Pouch Cove, near St. John's was secured. Industry contacts further directed Bob Platts of Stormfirma to contact Memorial University's Industrial Outreach Group (IOG) for the express purpose of carrying out the proposed field trials in a timely manner. A contract between Memorial's IOG and Stormfirma was finalized in April 2006 with the work to begin immediately. This document outlines the execution and results of these field trials as performed by The Industrial Outreach Group of Memorial's Faculty of Engineering for Stormfirma Inc.

2.0 **Project Execution**

Scope and Plan

The client's introductory work scope was drafted prior to the commencement of the program and is presented in Appendix A "Draft Work Plan". This plan was used as a basis for the development of a work scope developed by IOG and formally presented in the project proposal and contract document. The work scope for the contract is thus presented in Appendix B. In broad terms the program involved three phases: planning, field work and synthesis/reporting. For each phase, subtasks were identified and described and a 10-week schedule was developed as presented in Appendix C.

Though the project followed the proposed schedule in principle, deviation from the schedule dates occurred in three instances: during the planning phase where longer delivery time for a DA board pushed dates ahead by 3 weeks, in the testing phase where longer testing and VSV installations pushed the schedule ahead by an additional two weeks, and, in the analysis phase where longer and more time-consuming data processing pushed the schedule by an additional week. In total, five extra weeks were required to complete the work. The timeline below illustrates the activities and durations for the project as performed:

April 17 - May 31 st	June 1st - 12th	12th-17th	June 17th - 28th	June 28th - July 10th	July 10th - July 31st
	no VSVs				
		installation		_	
			VSVs active		
				VSVs fixed open	
PLANNING PHASE	FIE	LD TEST PH	ASE		REPORTING PHASE

PROJECT TIMELINE



Data acquisition equipment was sourced, tested and installed through May with onsite operations beginning June 1st. Weather data were recorded continuously beginning June 1st through to the conclusion of tests July 10th. Pressure data from six transducers was collected from June 2nd to July 10th with the exception of the week of June 12th to June 17th during which time the client installed the VSV units. During the field trials data were recorded for three household venting conditions:

- 1. Somewhat-normally (and poorly) vented condition prior to VSV installation
- 2. Venting via active VSV operation.
- 3. Venting with VSVs fixed in the open position

Data Acquisition Equipment

The data acquisition equipment was comprised of two semi-independent systems, the first being the *meteorological station* with associated display and recording unit, and the second, a computer-based *pressure data acquisition system*.

1- Meteorological Station:

The met station utilized for the study was a DAVIS Vantage Pro 2 System – a high-end private-use kit often used for low-end commercial applications. It was an inexpensive in-stock item that had a high degree of flexibility and reliability in non-extreme weather environments like that expected at the Pouch Cove test site during summer months. The unit shown below is essentially comprised of two parts: an indoor display and recording unit, and an array of instruments and sensors for placement outdoors.





Meteorological Station Components Left = Weather Instruments Above = Data Display and Logging Unit




The sensors and instruments of the met station measured wind speed, direction, duration, temperature, humidity, barometric pressure, solar radiation and precipitation. The Davis logging unit communicated with the instruments via wireless radio transmission and displays instantaneous conditions while recording peaks and averages on a 10 minute interval basis.

This unit was also linked to a dedicated laptop computer for periodic downloads. Downloads were required occasionally during the field test program due to the limited memory storage on the dedicated DAVIS logger. Although the DAVIS logger is designed to operate either independently, or, as part of a computer-based display/logging system, the simultaneous computer-based operation of the DAVIS unit and the pressure data acquisition system resulted in corrupted operations. Thus best efforts were made to sync the clocks on both units and then the met station was allowed to run independently for the test duration. The field station was positioned 25 meters NNW of the house in a clear open field setting on top of a rigid, 3 meter support structure (anemometer was 3m above ground level).

2- Pressure Transducers and Data logging Equipment


To expedite mobilization and to minimize costs, pressure data were acquired using equipment sourced in the retail market. This was comprised of a 16 channel, USB connected, external DA board purchased from US suppliers in-stock. Transducers were simple differential measuring devices (Setra Corp Model 265s - Appendix D) that had a range of plus-minus 5 inches of water pressure at 24 VDC excitation with 0-5VDC output. Six units were purchased to provide for two internal (attic space) pressure measurements and four external (outside) measurements at the soffit level, midway along each of the four sides of the rectangular house.

The sketch below indicates the position of the house, met station and prevailing winds:





The positions of the pressure measurement locations within and around the house are identified below:



The six transducer units have electronic terminals for power supply and output, plus a high and low pressure pneumatic connector. From each connector 3/16" vinyl tubing is run to the desired measurement location (high) and to pressure datum (low), respectively. The manufacturer stated that tubes extending less than 50 feet would in no way adversely affect readings thus allowing the installation of all transducers at a convenient central location with tubes radiating outwards towards the desired pressure points. The photo below shows the bank of transducers as-installed in the attic space:





The low pressure datum where all six tubes terminated inside the house was in an open bedroom/closet space isolated from the attic and open to the main and lower levels of the bungalow. The transducers were electronically connected to the external USB DA board (Data Foundry, 16 ch. unit) via cables running through the main level ceiling and floor into the basement of the test house where the terminal was stored.



Local Weather

A detailed discussion of the wind environment at the nearby International Airport is Provided in Appendix E. During the six week window of operation wind strengths were equal to, or above, seasonal in persistence and magnitude, direction was as expected.



Source: Dept of Geography, Memorial University of Newfoundland



Though winds were weak in the first days of testing, conditions changed to the point where peak winds exceeding 50 kph were experienced for over half of the 40 days of recording. In addition, strong summer breezes over 60 kph occurred bi-weekly allowing for the thorough testing of all three venting arrangements in a six week window.

Records and Files

Weather data were stored on the DAVIS logger and downloaded weekly onto the laptop hard drive in both **DAVIS** proprietary, and, ASCII data file formats. Likewise pressure data were recorded and stored on the laptop hard drive in both **Measure Foundry** proprietary and ASCII formats. The **Measure Foundry** software was permanently fixed at 50 Hz sampling rate and thus required a manual download/store operation every seven hours of active record taking. This also required a resetting of the acquisition software. Home owner and project assistant Cyril Snook diligently carried out this procedure on a regular basis during the six week period resulting in 84 record sessions averaging 7 hours each with complete coverage of key events. The figure below is indicative of the file listing on the accompanying data DVD.

pressure_4-21-47 PM.txt	19,573 KB Text Document	6/2/2006 11:06 AM	pressure_12-29-53 AM.txt	17,917 KB Text Document	6/23/2006 8:19 AM
pressure_11-30-02 AM.txt	21,215 KB Text Document	6/2/2006 8:28 PM	pressure_8-20-11 AM.txt	18,721 KB Text Document	6/23/2006 7:35 PM
pressure_8-29-06 PM.txt	17,206 KB Text Document	6/3/2006 9:04 AM	pressure_7-36-19 PM.txt	11,010 KB Text Document	6/23/2006 11:50 PM
pressure_9-04-37 AM.txt	19,429 KB Text Document	6/3/2006 7:23 PM	pressure_11-51-18 PM.txt	19,113 KB Text Document	6/24/2006 7:21 AM
pressure_7-23-32 PM.txt	19,637 KB Text Document	6/4/2006 4:41 AM	pressure_7-24-40 AM.txt	19,252 KB Text Document	6/24/2006 4:08 PM
pressure_4-41-33 AM.txt	19,900 KB Text Document	6/4/2006 12:20 PM	pressure_4-09-31 PM.txt	18,250 KB Text Document	6/24/2006 11:16 PM
pressure_12-22-41 PM.txt	18,387 KB Text Document	6/4/2006 7:25 PM	pressure_11-17-17 PM.txt	19,036 KB Text Document	6/25/2006 6:49 AM
pressure_7-26-35 PM.txt	14,227 KB Text Document	6/5/2006 12:49 AM	pressure_6-50-59 AM.txt	18,558 KB Text Document	6/25/2006 3:50 PM
pressure_12-49-42 AM.txt	19,769 KB Text Document	6/5/2006 8:22 AM	pressure_3-50-46 PM.txt	18,784 KB Text Document	6/25/2006 11:13 PM
pressure_8-24-08 AM.txt	20,893 KB Text Document	6/5/2006 4:16 PM	pressure_11-14-01 PM.txt	18,172 KB Text Document	6/26/2006 8:10 AM
pressure_4-17-35 PM.txt	19,754 KB Text Document	6/6/2006 12:26 AM	pressure_8-11-31 AM.txt	18,926 KB Text Document	6/26/2006 5:42 PM
pressure_12-27-11 AM.txt	19,357 KB Text Document	6/6/2006 8:12 AM	pressure_6-09-21 PM.txt	14,250 KB Text Document	6/26/2006 11:37 PM
pressure_8-13-45 AM.txt	19,932 KB Text Document	6/6/2006 4:17 PM	pressure_11-42-49 PM.txt	19,138 KB Text Document	6/27/2006 7:54 AM
pressure_4-18-40 PM.txt	20,634 KB Text Document	6/7/2006 12:16 AM	pressure_7-55-51 AM.txt	13,551 KB Text Document	6/27/2006 1:04 PM
pressure_12-17-34 AM.txt	19,322 KB Text Document	6/7/2006 8:13 AM	pressure_1-43-24 PM.txt	17,837 KB Text Document	6/27/2006 8:50 PM
pressure_8-14-54 AM.txt	19,465 KB Text Document	6/7/2006 5:34 PM	pressure_8-51-50 PM.txt	5,783 KB Text Document	6/27/2006 11:08 PM
pressure_5-35-43 PM.txt	18,627 KB Text Document	6/8/2006 12:43 AM	pressure_11-08-42 PM.txt	19,123 KB Text Document	6/28/2006 8:04 AM
pressure_12-44-35 AM.txt	20,194 KB Text Document	6/8/2006 8:30 AM	pressure_8-05-23 AM.txt	10,944 KB Text Document	6/28/2006 12:14 PM
pressure_8-30-56 AM.txt	19,652 KB Text Document	6/8/2006 4:15 PM	pressure_12-14-36 PM.txt	17,732 KB Text Document	7/3/2006 3:17 PM
pressure_4-16-50 PM.txt	20,122 KB Text Document	6/9/2006 12:57 AM	pressure_3-19-25 PM.txt	19,480 KB Text Document	7/3/2006 10:56 PM
pressure_12-58-21 AM.txt	19,242 KB Text Document	6/9/2006 8:19 AM	pressure_10-57-21 PM.txt	18,664 KB Text Document	7/4/2006 7:08 AM
pressure_8-20-43 AM.txt	18,883 KB Text Document	6/9/2006 5:58 PM	pressure_7-10-00 AM.txt	11,314 KB Text Document	7/4/2006 11:25 AM
pressure_5-59-17 PM.txt	19,346 KB Text Document	6/10/2006 1:14 AM	pressure_11-26-32 AM.txt	18,341 KB Text Document	7/4/2006 6:30 PM
pressure_1-14-49 AM.txt	18,770 KB Text Document	6/10/2006 8:22 AM	pressure_6-31-37 PM.txt	15,793 KB Text Document	7/5/2006 12:38 AM
pressure_8-23-59 AM.txt	13,713 KB Text Document	6/10/2006 1:31 PM	pressure_12-39-06 AM.txt	19,016 KB Text Document	7/5/2006 8:18 AM
pressure_1-32-45 PM.txt	20,017 KB Text Document	6/10/2006 9:06 PM	pressure_8-23-49 AM.txt	18,490 KB Text Document	7/5/2006 3:33 PM
pressure_9-07-02 PM.txt	10,158 KB Text Document	6/11/2006 12:55 AM	pressure_3-34-31 PM.txt	19,237 KB Text Document	7/5/2006 11:02 PM
pressure_12-56-22 AM.txt	20,973 KB Text Document	6/11/2006 12:09 PM	pressure_11-02-57 PM.txt	18,200 KB Text Document	7/6/2006 8:04 AM
pressure_12-10-01 PM.txt	13,093 KB Text Document	6/11/2006 5:05 PM	pressure_8-05-05 AM.txt	19,153 KB Text Document	7/6/2006 3:55 PM
pressure_6-56-51 AM.txt	18,277 KB Text Document	6/19/2006 3:43 PM	pressure 3-56-08 PM.txt	18.847 KB Text Document	7/6/2006 11:36 PM
pressure_3-48-05 PM.txt	20,181 KB Text Document	6/20/2006 12:30 AM	pressure_3-56-08 PM.txt	18,847 KB Text Document	7/6/2006 11:36 PM
pressure_12-31-48 AM.txt	19,564 KB Text Document	6/20/2006 8:21 AM	pressure_11-37-27 PM.txt	19,043 KB Text Document	7/7/2006 7:28 AM
pressure_8-23-54 AM.txt	19,699 KB Text Document	6/20/2006 6:39 PM	pressure_7-29-12 AM.txt	8,563 KB Text Document	7/7/2006 10:42 AM
pressure_6-40-09 PM.txt	14,784 KB Text Document	6/21/2006 12:21 AM	pressure_10-43-19 AM.txt	19,257 KB Text Document	7/8/2006 11:41 AM
pressure_12-22-08 AM.txt	18,290 KB Text Document	6/21/2006 7:26 AM	pressure_1-25-11 PM.txt	18,854 KB Text Document	7/8/2006 9:35 PM
pressure 7-27-50 AM.txt	18,288 KB Text Document	6/21/2006 4:36 PM	pressure_9-35-40 PM.txt	8,939 KB Text Document	7/9/2006 1:02 AM
pressure_4-37-29 PM.txt	18,284 KB Text Document	6/22/2006 2:01 AM	pressure_1-03-12 AM.txt	18,528 KB Text Document	7/9/2006 9:06 AM
pressure_2-02-03 AM.txt	19,948 KB Text Document	6/22/2006 9:45 AM	pressure_9-09-02 AM.txt	18,008 KB Text Document	7/9/2006 8:55 PM
pressure_9-57-04 AM.txt	18,859 KB Text Document	6/22/2006 5:19 PM	pressure_8-56-24 PM.txt	11,580 KB Text Document	7/10/2006 1:22 AM
pressure_5-20-30 PM.txt	18,432 KB Text Document	6/23/2006 12:29 AM	pressure_1-23-32 AM.txt	19,960 KB Text Document	7/10/2006 9:35 AM
pressure_12-29-53 AM.txt	17,917 KB Text Document	6/23/2006 8:19 AM	pressure_9-36-34 AM.txt	5,688 KB Text Document	7/10/2006 11:47 AM
· · · · · · · · · · · · · · · · · · ·					

Demobilization

Once it was judged that significant wind events had been experienced for all three house venting conditions the equipment was demobilized. The met station, and data




logging equipment were removed from the house/property and brought to the University for data uploading and processing on July 10th.

Data Reduction

Raw ASCII data files have been used for all analysis carried out in this report. Future work may chose to use proprietary software or other means for additional analysis but this was not required for first-order synthesis. Calibrated meteorological data for peak and sustained wind speeds were plotted for the six week program so that significant wind events could be identified within the three test scenarios.

After scrutinizing the data sets it was found that three independent but similar wind events occurred for each house venting condition. These occurred on June 5th, June 21st and July 3rd - in all three instances sustained winds of 37 kph and peak winds of 61 kph from the SW quadrant were recorded over a ten minute interval.






The pressure data files for these periods were sourced and truncated so that uploading into Excel could be accommodated. Once uploaded, the data sets were zeroed based on initial no-load tests run June 1st (@ baro=1013.4 or 4.068 inches of water) prior to the installation of pressure tubes, and then, the files were calibrated using the factory-provided unit factors as shown below. Subsequently, the three data sets, each with six transducer outputs were plotted on same-scale axes for review. Below is a sample view of the calibration file used for data processing


	Pressu	ure Trai	nsduce	er Zeroi	ng Test	ts			Pressure Transduce	r Calibrat	ion Facto	r:		
	#1	2.491023	2.511343	2.520981	2.497484	2.502751	2.477654		plus and minus five inche	es of water				
	#2	0.000000	2 544452	2 640700	2 400420	2 504770	2.472642		' far earr to Earrie DO at :			D		
		0.036399	2.511452	2.519798	2.496138	2.501776	2.472612		for zero to 5 volts DC at :	24 VDC ext	citation (inte	ernai)		
	#3	0.040497	2.510712	2.51889	2.495941	2.502258	2.471436							
	avg(avg)	2.491023	2.511169	2.51989	2.496521	2.502261	2.473901	[inches water per volt	pascals				
								l	2	498.1778				
Data File	#1								Data File	#2				
	Calibration	2-33-49PM. File g the pressu		cers prior ti	o upper tubi	e install				Calibration		txt ure transdu	cers prior to	o upper
Time	Clock	Ch. 0	Ch. 1	Ch. 2	Ch. 3	Ch. 4	Ch. 5		Time	Clock	Ch. 0	Ch. 1	Ch. 2	Ch. 3
6/1/06 2:33 PM	38869.61	2.495117	2.504883	2.519531	2.504883	2.495117	2.480469		6/1/06 3:34 PM	38869.65	0.03418	2.509766	2.524414	2.4951
6/1/06 2:33 PM	38869.61	2.495117	2.514648	2.524414	2.485352	2.504883	2.475586		6/1/06 3:34 PM	38869.65	0.039063	2.514648	2.519531	2.4951
6/1/06 2:33 PM	38869.61	2.490234	2.509766	2.524414	2.485352	2.5			6/1/06 3:34 PM	38869.65	0.039063		2.514648	
6/1/06 2:33 PM	38869.61	2.490234	2.519531	2.519531	2.490234	2.5	2.480469							2.4951
									6/1/06 3:34 PM		0.03418		2.524414	
6/1/06 2:33 PM	38869.61	2.5			2.5		2.480469		6/1/06 3:34 PM	38869.65	0.03418	2.509766	2.509766	
6/1/06 2:33 PM 6/1/06 2:33 PM	38869.61 38869.61	2.5 2.485352	2.504883	2.519531	2.5	2.5	2.475586		6/1/06 3:34 PM 6/1/06 3:34 PM	38869.65 38869.65	0.03418	2.509766 2.514648	2.509766 2.524414	2.4902
6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM	38869.61 38869.61 38869.61	2.5 2.485352 2.485352	2.504883 2.504883	2.519531 2.529297	2.5 2.504883	2.5 2.5	2.475586 2.480469		6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM	38869.65 38869.65 38869.65	0.03418 0.039063 0.029297	2.509766 2.514648 2.514648	2.509766 2.524414 2.524414	2.4902
6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM	38869.61 38869.61 38869.61 38869.61	2.5 2.485352 2.485352 2.495117	2.504883 2.504883 2.514648	2.519531 2.529297 2.514648	2.5 2.504883 2.490234	2.5 2.5 2.504883	2.475586 2.480469 2.480469		6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM	38869.65 38869.65 38869.65 38869.65	0.03418 0.039063 0.029297 0.039063	2.509766 2.514648 2.514648 2.509766	2.509766 2.524414 2.524414 2.519531	2.4902 2.4853 2.4951
6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM	38869.61 38869.61 38869.61 38869.61 38869.61	2.5 2.485352 2.485352 2.495117 2.490234	2.504883 2.504883 2.514648 2.519531	2.519531 2.529297 2.514648 2.519531	2.5 2.504883 2.490234 2.5	2.5 2.5 2.504883 2.514648	2.475586 2.480469 2.480469 2.475586		6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM	38869.65 38869.65 38869.65 38869.65 38869.65	0.03418 0.039063 0.029297 0.039063 0.03418	2.509766 2.514648 2.514648 2.509766 2.504883	2.509766 2.524414 2.524414 2.519531 2.514648	2.4902 2.4853 2.4951 2.4902
6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM	38869.61 38869.61 38869.61 38869.61 38869.61 38869.61	2.5 2.485352 2.485352 2.495117 2.490234 2.490234	2.504883 2.504883 2.514648 2.519531 2.519531	2.519531 2.529297 2.514648 2.519531 2.524414	2.5 2.504883 2.490234 2.5 2.495117	2.5 2.5 2.504883 2.514648 2.504883	2.475586 2.480469 2.480469 2.475586 2.470703		6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM	38869.65 38869.65 38869.65 38869.65 38869.65 38869.65	0.03418 0.039063 0.029297 0.039063 0.03418 0.03418	2.509766 2.514648 2.514648 2.509766 2.504883 2.509766	2.509766 2.524414 2.524414 2.519531 2.514648 2.514648	2.4902 2.4853 2.4951 2.4902 2.4902
6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM 6/1/06 2:33 PM	38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61	2.5 2.485352 2.485352 2.495117 2.490234 2.490234 2.485352	2.504883 2.504883 2.514648 2.519531 2.519531 2.509766	2.519531 2.529297 2.514648 2.519531 2.524414 2.524414	2.5 2.504883 2.490234 2.5 2.495117 2.509766	2.5 2.5 2.504883 2.514648 2.504883 2.509766	2.475586 2.480469 2.480469 2.475586 2.470703 2.475586		6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM	38869.65 38869.65 38869.65 38869.65 38869.65 38869.65 38869.65	0.03418 0.039063 0.029297 0.039063 0.03418 0.03418 0.03418	2.509766 2.514648 2.514648 2.509766 2.504883 2.509766 2.504883	2.509766 2.524414 2.524414 2.519531 2.514648 2.514648 2.519531	2.4902 2.4853 2.4951 2.4902 2.4902 2.4902 2.4951
6/1/06 2:33 PM 6/1/06 2:33 PM	38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61	2.5 2.485352 2.485352 2.495117 2.490234 2.490234 2.485352 2.485352	2.504883 2.504883 2.514648 2.519531 2.519531 2.509766 2.519531	2.519531 2.529297 2.514648 2.519531 2.524414 2.524414 2.524414	2.5 2.504883 2.490234 2.5 2.495117 2.509766 2.490234	2.5 2.504883 2.514648 2.504883 2.509766 2.504883	2.475586 2.480469 2.480469 2.475586 2.475586 2.470703 2.475586 2.480469		6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM 6/1/06 3:34 PM	38869.65 38869.65 38869.65 38869.65 38869.65 38869.65 38869.65 38869.65	0.03418 0.039063 0.029297 0.039063 0.03418 0.03418 0.03418 0.03418 0.03429297	2.509766 2.514648 2.509766 2.504883 2.509766 2.504883 2.509766 2.504883 2.514648	2.509766 2.524414 2.524414 2.519531 2.514648 2.514648 2.519531 2.524414	2.4902 2.4853 2.4951 2.4902 2.4902 2.4902 2.4951
6/1/06 2:33 PM 6/1/06 2:33 PM	38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61	2.5 2.485352 2.485352 2.495117 2.490234 2.490234 2.485352 2.485352 2.485352 2.490234	2.504883 2.504883 2.514648 2.519531 2.519531 2.509766 2.519531 2.519531	2.519531 2.529297 2.514648 2.519531 2.524414 2.524414 2.524414 2.524414	2.5 2.504883 2.490234 2.5 2.495117 2.509766 2.490234 2.490234 2.495117	2.5 2.504883 2.514648 2.504883 2.509766 2.504883 2.5	2.475586 2.480469 2.480469 2.475586 2.470703 2.475586 2.480469 2.480469		6/1/06 3:34 PM 6/1/06 3:34 PM	38869.65 38869.65 38869.65 38869.65 38869.65 38869.65 38869.65 38869.65 38869.65	0.03418 0.039063 0.029297 0.039063 0.03418 0.03418 0.03418 0.03418 0.029297 0.03418	2.509766 2.514648 2.514648 2.509766 2.504883 2.509766 2.504883 2.504883 2.514648 2.514648	2.509766 2.524414 2.524414 2.519531 2.514648 2.514648 2.519531 2.524414 2.519531	2.4902 2.4853 2.4951 2.4902 2.4902 2.4902 2.4951
6/1/06 2:33 PM 6/1/06 2:33 PM	38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61	2.5 2.485352 2.485352 2.495117 2.490234 2.490234 2.485352 2.485352 2.485352 2.490234 2.490234	2.504883 2.504883 2.514648 2.519531 2.519531 2.509766 2.519531 2.519531 2.519531 2.514648	2.519531 2.529297 2.514648 2.519531 2.524414 2.524414 2.524414 2.524414 2.524414	2.5 2.504883 2.490234 2.5 2.495117 2.509766 2.490234 2.495117 2.490234	2.5 2.504883 2.514648 2.504883 2.509766 2.504883 2.5 2.504883	2.475586 2.480469 2.480469 2.475586 2.470703 2.475586 2.480469 2.480469 2.480469 2.475586		6/1/06 3:34 PM 6/1/06 3:34 PM	38869,65 38869,65 38869,65 38869,65 38869,65 38869,65 38869,65 38869,65 38869,65	0.03418 0.039063 0.029297 0.039063 0.03418 0.03418 0.03418 0.029297 0.03418 0.039063	2.509766 2.514648 2.514648 2.509766 2.504883 2.509766 2.504883 2.514648 2.514648 2.514648	2.509766 2.524414 2.524414 2.519531 2.514648 2.514648 2.519531 2.524414 2.519531 2.524414	2.4902 2.4853 2.4951 2.4902 2.4902 2.4902 2.4951 2.4951
6/1/06 2:33 PM 6/1/06 2:33 PM	38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61	2.5 2.485352 2.485352 2.495117 2.490234 2.490234 2.485352 2.485352 2.485352 2.490234 2.490234 2.490234	2.504883 2.504883 2.514648 2.519531 2.519531 2.509766 2.519531 2.519531 2.519531 2.514648 2.509766	2.519531 2.529297 2.514648 2.519531 2.524414 2.524414 2.524414 2.524414 2.524414 2.524414 2.524414	2.5 2.504883 2.490234 2.5 2.495117 2.509766 2.490234 2.495117 2.490234 2.495117	2.5 2.504883 2.514648 2.504883 2.509766 2.504883 2.5 2.504883 2.504883 2.504883	2.475586 2.480469 2.480469 2.475586 2.470703 2.475586 2.470586 2.480469 2.480469 2.480469 2.475586 2.480469		6/1/06 3:34 PM 6/1/06 3:34 PM	38869,65 38869,65 38869,65 38869,65 38869,65 38869,65 38869,65 38869,65 38869,65 38869,65	0.03418 0.039063 0.029297 0.039063 0.03418 0.03418 0.03418 0.029297 0.03418 0.039063 0.03418	2.509766 2.514648 2.509766 2.504883 2.509766 2.504883 2.504883 2.514648 2.514648 2.514648 2.514648	2.509766 2.524414 2.524414 2.519531 2.514648 2.514648 2.519531 2.524414 2.519531 2.524414 2.519531 2.524414	2.4902 2.4953 2.4951 2.4902 2.4902 2.4951 2.4951 2.4951
6/1/06 2:33 PM 6/1/06 2:33 PM	38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61 38869.61	2.5 2.485352 2.495352 2.495117 2.490234 2.490234 2.485352 2.485352 2.490234 2.490234 2.490234 2.490234 2.490234	2.504883 2.504883 2.514648 2.519531 2.519531 2.509766 2.519531 2.519531 2.514648 2.509766 2.519531	2.519531 2.529297 2.514648 2.519531 2.524414 2.524414 2.524414 2.524414 2.524414	2.5 2.504883 2.490234 2.5 2.495117 2.509766 2.490234 2.495117 2.490234 2.495117 2.5	2.5 2.504883 2.514648 2.504883 2.509766 2.504883 2.5 2.504883 2.504883 2.504883 2.504883	2.475586 2.480469 2.480469 2.475586 2.470703 2.475586 2.480469 2.480469 2.480469 2.475586		6/1/06 3:34 PM 6/1/06 3:34 PM	38869.65 38869.65 38869.65 38869.65 38869.65 38869.65 38869.65 38869.65 38869.65 38869.65 38869.65 38869.65	0.03418 0.039063 0.029297 0.039063 0.03418 0.03418 0.029297 0.03418 0.029297 0.03418 0.039063 0.03418	2.509766 2.514648 2.514648 2.509766 2.504883 2.509766 2.504883 2.514648 2.514648 2.514648	2.509766 2.524414 2.524414 2.519531 2.514648 2.514648 2.519531 2.524414 2.519531 2.524414 2.519531 2.524414 2.514648 2.519531	2.4902 2.4951 2.4951 2.4902 2.4951 2.4951 2.4951 2.4951 2.4951


3.0 Results and Analysis

A thorough analysis of VSV performance was not within the scope of this project. A quantitative assessment would require some form of power spectral density investigation in which the differential between inside and outside pressures was assessed. In addition this work would be required for various wind approaches to the structure. A sensitivity analysis may also reveal correlations between differential pressure measurements and factors other than soffit venting. These and other analysis techniques may be the focus of future work, however, for this study analysis was limited to a qualitative look at the pressures recorded during three similar weather events . Below are the plots representing these events:



Note that the data sets were zeroed on the basis of no-wind readings on June 1st.







Observations:

The following observations have been made from these plots:

- 1. The pressure state inside the attic (relatively flat black and blue lines in plot background) appears to be further displaced to the positive side from the pressures outside at the soffits in the active VSV state than in either the no-VSV or the fixed open VSV conditions.
- 2. A higher pressure flux is observed in the attic when VSVs are fixed open than in either of the other two conditions.
- 3. Attic space pressures at opposing ends of the structure do not vary or differ significantly.
- 4. Though wind events were similar, subtle changes in direction must occur over short time intervals giving rise to significantly different surface pressure readings around the house perimeter demonstrated by varying dominant pressures on the positive side. Negative pressures on the lea side (Eastern) gable end were greatest in magnitude in all test cases.

The complete dataset provides for analysis opportunities for other wind directions and magnitudes, the choice for that above having been somewhat arbitrary. Results may vary according to these factors and therefore should be considered for follow on work. Video clips of VSVs in operation during high wind conditions record the following: VSVs flap open and shut during operation in windy conditions. The noise and vibration caused by this action requires the attention of the designers to mitigate homeowner/ client discomfort.

Uncertainty Analysis and Mitigation

Many factors affect household venting and not all are understood nor were they carefully controlled during these tests. From the glimpse provided by the three intervals plotted above it cannot be concluded that the VSVs in operation had a remarkable impact on attic space venting. However, it is quite likely that subtle changes in the wind direction and turbulence intensity affect pressure distribution around the house in a significant way. Therefore, no conclusive statement can or should be made about VSV operations until a thorough analysis of the full dataset is performed using power spectral density analyses procedures.


Two concerns were expressed by the client after the initial results were presented: the adverse affects of the pressure high-side tube terminations and in-house depressurization where low-side tubes were terminated. Pressure tube (high side, outside) terminations projected 10cm from each soffit and wall surface with the open tube end pointed downwards for rain avoidance. It was suggested that this was causing significant flapping and trailing leading to lower than normal pressures due to suction. The pressure datum for all six transducers was the ambient pressure inside



the living space of the house – where all six tubes (low side) were bundled and terminated in an open, well-vented room. The status of household windows, chimney and doors were not recorded and it was a concern that gross depressurization within the house may have diminished the value of the data qualitatively and quantitatively.


To alleviate these concerns an additional set of tests were performed with two modifications. High-side pressure tube terminations outside were clipped and carefully flush-mounted to avoid any projection into the air space. A second digital barometric pressure gauge was installed inside the house beside the low-side transducer tube terminations. This indoor gauge was previously calibrated side-by-side against the outside gauge.

Data were recorded over a one-month period during which two post-hurricane tropical depressions passed with 60 nautical miles of the house. The figure below shows that the ambient pressure measured inside the house at the datum for the transducers was equal to the pressure measured outside the house at the met station – at all times. There was no significant or apparent de-pressurization of the home interior during any time interval measured.



To analyze the effect of tube terminations a wind event with the same characteristics as the three previously analyzed events - was identified. An identical analysis procedure was undertaken and the results plotted (below with others). The similarity of this plot with the others indicates that the degree of rapid pressure flux, the relative variation between sensors and the significant negative displacement of the lee-side pressure is a real and robust phenomenon and not an artifact of the experimental procedure or equipment. This result further suggests that the previous body of data for which these changes were not affected - is valid and representative. In summary, definitive and conclusive statements of VSV performance cannot be made given the first-order analysis presented.





17:50:12

17:50:30

17:50:47

17:51:04

17:51:22

17:48:46

17:49:03

17:49:21

17:49:38

17:49:55



4.0 **Project Contacts**

The Client:	Bob Platts, P.Eng, of Stormfirma Inc. Ottawa bobplatts@yahoo.com>
Project Manager:	Steve Bruneau, PhD, P.Eng of Memorial University in St. John's Newfoundland, 709 737 2119 sbruneau@engr.mun.ca
Contract Manager:	Andy Fisher, PhD, P.Eng Memorial University of Newfoundland, 709 737-6180 adfisher@mun.ca
Technical Support:	Karl Tuff, C-CORE, St. John's Newfoundland 709 737-8367 karl.tuff@c-core.ca
House Location host:	Cyril Snook, MUN Physics, cyril@physics.mun.ca

5.0 Deliverables

Deliverable included with this final report are:

(a) Meteorological and Pressure Transducer Data

Time sequenced data series on DVD format with index of file names and ID information.

(b) Written Report

3 hard copies, 1 digital of final report.

6.0 Commitment

It should be understood that the nature of research work in the field is complex and it is difficult to predict the exact nature of a given result until the process has been completed. Within the context of this uncertainty, the Industrial Outreach Group has done its best to execute the proposed work and to provide a clear summary of the results and observations.

For more information please contact Steve Bruneau at 709 737-2119.



APPENDIX A

Stormfirma Inc. Draft work Plan and Instrumentation Proposals



Stormfirma Inc. R.E. Platts, P.Eng. bobplatts@yahoo.com Ottawa, 3rd April 2006

WORK PLAN - draft -

for the project TESTING THE PERFORMANCE OF VALVED SOFFIT VENTS IN DEPRESSURIZING ROOF SPACES DURING WINDSTORMS

The Job: To determine the effect of Valved Soffit Vents in reducing uplift on roof sheathing, equip the test house with Valved Soffit Vents and monitor its roof space pressures vs. wind speeds and directions during strong windstorms, alternating between normal soffit venting and VSV venting, and varying the roof space-to-indoor air-leakiness as well.

Tasks: (Tasks 1-4 begin now and proceed in parallel)

- 1. <u>Refine the Project Design</u>: Review the 'Instrumentation Options' document, suggest any improvements and recommend the minimum level of set-up and testing, all to ensure this job can be accomplished fully.
- Primarily MUN, by April 15th approx \$2000
 2. <u>Describe the test house and site</u>: House type, configuration, external dimensions, features/obtrusions, roof type and slopes, roof framing and spacing, overhangs, soffits, roof space-soffit space continuity... Site sketch, house orientation, elevation (above sea level), 'wind fetch' from house looking NSEW photos.

• Primarily CS (separate budget) by April 15th

3. Select, source and install instrumentation

• **Primarily MUN**, by April 30-May 15th, approx \$5000 (Stormfirma buys instrumentation or leases from MUN, internal funding)

- 4. <u>Prepare and install VSVs</u>: Fabricate prototypical VSVs specifically for these field tests, using lightweight plastic valves -so that VSV performance can be demonstrated even in winds of less than gale force. Devise and install "de-activators" on each VSV for these tests, to allow on-off "control" runs (see 5). Valve or seal off any other vents such as gable vents. Air seal the ceiling and soffits. Install an operable opening in the attic hatch to allow determination of air leakage effects on VSV performance. "Road test" all in strong winds, and report.
 - Primarily Stormfirma (internal funds) with MUN,
 - with air seal specialist (up to \$4000)
 - and CS (sep. budget), by April 30th-May 15th
- 5. <u>Monitor VSV performance during windstorms</u>: Switch on instrumentation as gales come in, and run alternating on-off cycles of the VSVs through the worst hours. Open the defined 'air leak' during certain cycles. From the outside, video-record the valve action of windward and leeward VSVs concurrently with wind and pressure recordings, during gales from for at least two cardinal directions.

• Primarily CS (sep. budget),

• with MUN/Stormfirma \$2000

by May 15th-30th


6. <u>Analyze and Report in full</u>: Determine the efficacy of VSVs in depressurizing the roof space with winds/gusts from various directions; the effect of normal venting likewise, in pressurizing as well as depressurizing; the effects of air leakage, roughly; the calculated reductions/increases in uplift forces on the sheathing.

• Primarily MUN, up to \$7000,

by May 30th-June 15th



Stormfirma Inc. R. E. Platts, P.Eng. bobplatts@yahoo.com



Favoured for first field trial: Level 3; Level 2 okay. Does MUN prefer 4 or 5 for better research? REP, 15 Mar 06 revised 31 Mar 06



APPENDIX B

Proposal Work Scope and Sub Tasks



Work Scope and Sub Tasks:

Task A - PLAN

- 1. Develop understanding of project request and the purpose of the proposed device, review and refine client *draft work plan (Appendix A)*.
- 2. Establish and manage the project schedule and budget, incl. communications between all stakeholders
- 3. Evaluate the characteristics and configuration of the proposed test house in Pouch Cove (Cyril Snook, homeowner, directly contracted to client).
- 4. Design an instrumentation and data acquisition system to meet the technical and scheduling needs of the client.
- 5. Source the DA equipment, configure it for the test program and perform lab test.

Task B - FIELD

- 6. Mobilize kit into the field by setting up the met station and installing pressure transducers while minimizing household disturbances with the positioning of the tubing, wires, and D.A. test base station.
- 7. Perform brief field trial for troubleshooting.
- 8. Begin monitoring
- 9. VSV installation and house HVDC modifications performed by others on an ASAP basis either before or after system monitoring begins.
- 10. Check ongoing system performance and perform routine data downloads.
- 11. Host a client site visit and accommodate specific performance tests over a few day period for a few hours each day.
- 12. Perform pressure measurement tests with, and without, the VSV's in operational mode during gusty conditions.
- 13. End data acquisition program after approximately 4-6 weeks of operation. Demobilize the equipment back to Memorial University.

Task C - REPORT

- 14. Download, backup, calibrate, label and package digital data in DVD format.
- 15. Perform first order review of pressure activity during one or more key meteorological events and provide plotted results.
- 16. Write a report that provides an overview of the test program, describes the data acquisition, lists the data, provides brief analysis of key event(s) and lists salient observations of, and recommendations for, the tested VSV product.
- 17. Courier digital and three hard copies of the draft final report and data DVD(s) to the client on or before June 15th, 2006.
- 18. Receive and consider the draft report review by client and incorporate into final report issue.



APPENDIX C

Proposal Schedule

SCHEDULE	SCHEDULE WINDOW FOR EACH TASK											
		Schedule	Week 1 Week 2		Week 3	Week 4	Week 5	Week 6	Week 7	Week 8	Week 9 \	Week 10
TASK A - PLAN		Start date	16-Apr-06	23-Apr-06	30-Apr-06	7-May-06	14-May-06	21-May-06	28-May-06	4-Jun-06	11-Jun-06 18-Jun-06	18-Jun-06
~	Review and refine project parameters	17-Apr										
2	2 Develop budget, schedule, project team											
m	3 Evaluate Pouch Cove house											
4	4 Design D.A. System											
S	5 Source D.A. and perform Lab tests											
TASK B - FIELD												
9	6 Mobilization of equipment											
2	7 Field trial troubleshooting											
	8 Commence monitoring											
6	9 VSV installation, HVAC mods.											
0	10 Routine maintenance data downloads											
ŧ	11 Client site visit											
12	12 Perform control tests											
10	13 Demobilization											
TASK C - REPORT												
14	14 Data storage and handling											
15	15 First-order analysis											
16	16 Write report											
17	17 Send draft report											
9	18 Finalize report											





APPENDIX D

Pressure Transducer Specifications

<u>m</u>
Ā
ш
~
8
ō
Ĕ.
ŝ
F.
Ú
Δ
ō
ž
ā
10
¥
≤
Z
2
5
F
ш
8
0
6.0

returning unit for repair to review information relative to your application. Many times only minor field adjustments may be necessary. When returning a product to Setra, the Please contact a Setra application engineer (800-257-3872, 978-263-1400) before material should be carefully packaged and shipped prepaid to:

Boxborough, MA 01719-1304 Attn: Repair Department 159 Swanson Road Setra Systems, Inc.

To assure prompt handling, please supply the following information and include it inside the package or returned material:

- Name and phone number of person to contact.
 - Shipping and billing instructions.
- Full description of the malfunction. - ~ ~ *
- Identify any hazardous material used with product.

Notes: Please remove any pressure fittings and plumbing that you have installed and enclose any required mating electrical connectors and wiring diagrams Allow approximately 3 weeks after receipt at Setra for the repair and return of the unit. Non-warranty repairs will not be made without customer approval and a purchase order to cover repair charges.

Calibration Services

Setra maintains a complete calibration facility that is traceable to the National Institute Setra pressure transducers or transmitters, please call our Repair Department at 800of Standards & Technology (NIST). If you would like to recalibrate or recertify your 257-3872 (978-263-1400) for scheduling.

7.0 WARRANTY AND LIMITATION OF LIABILITY

Without charge, SETRA will repair or replace products found to have manufacturing defects within the warranty SETRA warrants its Model 265 Transducer products to the original consumer purchaser against defects for a period of one year from the date of sale by SETRA, as shown in its shipping documents.

SETRA must be notified in advance of any returns; any products returned to SETRA must be transportation The serial number or date code must not have been removed, defaced or otherwise changed. period.

The foregoing warranty is in lieu of all warranties, express, implied or statutory, including but not limited to, any orepaid.

mplied warranty of merchantability for a particular purpose.

SETRAS liability for breach of warranty is limited to repair or replacement, or if the goods cannot be repaired or replaced to a refund of the purchase price. SETRAS liability for all other breaches is limited to a refund of the ourchase price. In no instance shall SETRA be liable for incidental or consequential damages arising from a preach of warranty, or from the use or installation of its products.

No representative or person is authorized to give any warranty other than as set out above or to assume for SETRA any other liability in connection with the sale of its products.

Tel: 800-257-3872/978-263-1400 159 Swanson Road, Boxborough, MA 01719-1304



Differential Pressure Transducer Installation Guide Setra Systems Model 265

GENERAL INFORMATION 0.1

Every Model 265 has been tested and calibrated before shipment. Specific performance specifications are shown on page 3 of this Guide

analog output for both unidirectional and bidirectional pressure ranges. The pressure and convert this pressure difference to a proportional high level Setra Systems 265 pressure transducers sense differential or gage (static) Model 265 is available in the following excitation and output versions:

Output	0-5 VDC	0-5 VDC	0-10 VDC	4-20 mA
 EXCITATION	9-30 VDC	9-30 VAC	12-30 VAC	9-30 VDC (measured between the + and - terminals)

Check the label on the unit to confirm the excitation and ouput. 6

MECHANICAL INSTALLATION 2.0

Model 265 transducers are designed to be used with air or nonconducting gases. Use with liquids or corrosive gases will damage the unit. 2.1 Media Compatibility

2.2 Environment

The operating and compensated temperature limits of the 265 are 0°F to +150°F (-18°C to +65°C).

2.3 Pressure Fittings

suggested for tubing lengths up to 100 feet long, 1/4"I.D. for tubing lengths up push-on tubing. Both the positive (high) pressure port and the reference (low) pressure port are located on the front of the unit, labeled "HIGH" and "LOW" fittings for the pressure signal connection and typically installed with 1/4" respectively. For best results (shortest response times), 3/16"I.D. tubing is The Model 265 is supplied with two factory installed 1/4" O.D. pressure to 300 feet, and 3/8" I.D. for tubing lengths up to 900 feet.

ELECTRICAL INSTALLATION 3.0

If the Model 265 is supplied with the optional Conduit Enclosure, access the electrical terminations by removing the cover.

3.1 Voltage Output Units

SS2009 Rev.F 08/08/01

can operate from 9-30 VDC or 9-30 VAC excitation with 0-5 VDC output, or 12-30 The Model 265 voltage output is a 3-wire circuit, with three terminals available Diagram 1). [Note: The - designation above COM and the + designation above Output are commoned on the circuit (see Diagram 2). The 265 voltage output EXC are designations for the current output terminals.] The -Excitation and for wiring. These terminals have the designation COM, OUT and EXC (see VAC excitation with 0-10 VDC output.



are 0.0VDC (\pm 50mV) for unidirectional pressure ranges and 2.5VDC (\pm 50mV) for bidirectional pressure ranges. Optional outputs are set at the same $\pm 1\%$ ocation of zero adjustment.) For 0-5 VDC output units, the factory settings actory setting.

Voltage Output Span Adjustment (Complete the zero adjustment before setting span.)

Model 265

OUT

+ EXC

COM

atmosphere), the span may be adjusted by turning the SPAN adjustment screw. (See Diagram 1 for location of the SPAN adjustment.) For 0-5 VDC output units accurate pressure standard (electronic manometer, digital pressure gage, etc.). with at least comparable accuracy to the 265 transducer (<±1% FS). With full Span or full scale output adjustments should only be performed by using an the factory settings are 5.0 VDC (±50mV) for unidirectional and bidirectional range pressure applied to the high pressure port (reference port open to ranges. Optional outputs are set at the same $\pm 1\%$ factory setting.

4.3 Current Output Zero Adjustment


factory settings are 4mA (0.16mA) for unidirectional pressure ranges and 12mA pressure ports open to atmosphere, the zero may be adjusted by turning the While monitoring the current output between +EXC and OUT, and with both zero adjustment screw. (See Diagram 1 for location of zero adjustment.) The (0.16mA) for bidirectional ranges.

4.4 Current Output Span Adjustment

(See Diagram 1 for location of SPAN adjustment.) The factory settings are 20mA atmosphere), the span may be adjusted by turning the SPAN adjustment screw. accurate pressure standard (electronic manometer, digital pressure gage, etc.) with at least comparable accuracy to the 265 transducer (<±1% FS). With full Span or full scale output adjustments should only be performed by using an range pressure applied to the high pressure port (reference port open to (0.16mA) for unidirectional and bidirectional pressure ranges.


MODEL 265 PERFORMANCE SPECIFICATIONS 5.0

Accuracy RSS [*]	±1.0% FS	Thermal Effects	
(at constant temperature.)	(Compensated Range F(°C)	0 to +150 (-18 to +65)
Non-Linearity, BFSL	±0.98% FS	Zero/Span Shift %FS/F(°C)	0.033 (0.06)
Hysteresis	0.1% FS	Maximum Line Pressure	10 psi
Non-Repeatability	0.05% FS	Overpressure	10 psi in positive or
*RSS of Non-Linearity, Non-Repeatability	n-Repeatability		negative direction
and Hysteresis.	5	Warm-up Shift	±0.1% FS total
Position Effects			
(Unit is factory calibrated at 0g effect in the vertical position)	at 0g effect in the	vertical position)	
Range	Zero Offset (%FS/G)	.2/G)	
0 to 1" WC	22		
0 to 5" WC	.14		
0 to 30" WC	.06		



3.2 Current Output Units

voltage source with a voltage range between 9 and 30 measured between terminal + and - terminals. The unit is calibrated at the factory with a 24 VDC loop supply voltage Diagram 3). The current flows into + terminal and returns back to the power supply through the - terminal (see Diagram 3). The power supply must be a DC The Model 265 is a two-wire loop-powered 4 to 20mA current output unit (see and a 250 ohm load.



CALIBRATION 4.0.

corrected by software adjustment in the user's control system. However, both ment. Generally, the mounting position will have a zero shift effect on ranges zero and span adjustments are accessible either on the front of the unit or by removing the optional conduit enclosure. The 265 transducer is calibrated in The 265 transducer is factory calibrated and should require no field adjustbelow 1"WC. Whenever possible, any zero and/or span offsets should be the vertical position at the factory.

4.1 Voltage Output Zero Adjustment

common (COM), and with both pressure ports open to atmosphere, the zero may be adjusted by turning the zero adjustment screw. (See Diagram 1 for While monitoring the voltage between the positive output (OUT) and

0





APPENDIX E

Torbay International Airport Wind Environment

