

Quality Civil Engineering Consultants

Duckworth Street Retaining Wall Final Report ENGI 8700

Prepared for: Acuren & Dr. Bruneau Prepared by: Erica Soucy, Chantel Nicolle, Qiong Zhang & Chenel Waight



Quality Civil Engineering Consultants Memorial University of Newfoundland St. John's, NL, A1B 3X5

April 3, 2013

Emad Rizk Acuren Group Inc. 112 Forest Rd St. John's, NL, A1A 1E6

Dear Mr. Rizk,

Please see the enclosed document for details on the design and construction of the Duckworth Street temporary retaining wall in St. John's, Newfoundland.

The final project report details the design selection process followed by QCEC to select the most appropriate temporary retaining wall for construction of the Duckworth Street parking garage and condominium complex. The detailed design process is also discussed in depth for the selected retaining wall as well as the drafting and cost estimate. Finally, by request of the client, a construction plan and schedule has been developed and included in the following report.

If there are any questions regarding the project report, please feel free to contact the undersigned.

Sincerely,

Quality Civil Engineering Consultants

Chantel Nicolle

Erica Soucy

Qiong Zhang

Chenel Waight

cc. Dr. Steve Bruneau



Table of Contents

1.0	PROJE	CT DESCRIPTION
2.0	APPRO	DACH2
3.0	LITER	ATURE REVIEW
4.0	SITE C	ONDITIONS
5.0	PRELI	VINARY DESIGN
5.1	SOL	DIER PILE RETAINING WALL
5	.1.1	DESIGN7
5	.1.2	COST
5.2	SOI	L NAIL RETAINING WALL
5	.2.1	DESIGN
5	.2.2	COST
6.0	GENE	RAL DESIGN AND SKETCHING
6.1	GEN	JERAL
6.2	RIG	ID GRAVITY RETAINING WALL
6	.2.1	LOADING14
6.3	FAII	LURE MODES
6	.3.1	TRANSLATIONAL FAILURE
6	.3.2	ROTATIONAL FAILURE
6	.3.3	BEARING FAILURE
6.4	DR/	AINAGE
6.5	SOL	DIER PILE RETAINING WALL
6	.5.1	TIEBACK LAYOUT
6	.5.2	LOADING
6	.5.3	SOLDIER PILE ANALYSIS
6	.5.4	TIEBACK DESIGN
6	.5.5	TIMBER LAGGING DESIGN



6.6	DRAFTING	. 29

7.0	COST ESTIMATE	30
7.1	QUANTITY TAKE-OFF	30
7.2	LABOUR AND MATERIALS	31
8.0	CONSTRUCTION	33
8.1	METHODOLOGY	33
9.0	CONCLUSION	36
10.0	REFERENCES	37

APPENDIX A	- Geotechnical	Report
-------------------	----------------	--------

- **APPENDIX B Drawings Received from Client**
- **APPENDIX C Soil Profile Drawings**
- **APPENDIX D Soldier Pile and Rigid Gravity Retaining Wall Drawings**
- **APPENDIX E Preliminary Soil Nail Retaining Wall Drawings**
- **APPENDIX F S-FRAME and S-STEEL Results**
- **APPENDIX G Design Anchor Capacity Estimates**
- **APPENDIX H Soldier Pile Retaining Wall Design Calculations**
- **APPENDIX I Rigid Gravity Retaining Wall Design Calculations**
- **APPENDIX J Cost Estimate**
- **APPENDIX K Construction Schedule**



1.0 PROJECT DESCRIPTION

Quality Civil Engineering Consultants (QCEC) was contracted by Acuren Group Inc. to design a temporary retaining wall. A new parking garage and condominium complex is in development on Duckworth Street and a temporary retaining wall is required for support along Henry Street to allow for construction of the building (Figure 1.1).




Figure 1.1: Site Location

The retaining wall will have a life of approximately three years then it will be backfilled and the new building will continue to provide long term support.

A geotechnical investigation was completed on the site in 2011 and a topographical survey of the site is also available. The developers of the parking garage also provided architectural drawings.



2.0 APPROACH

Initially, a soil profile of the retaining wall area was developed based on the provided geotechnical investigation. The soil profile includes soil details along the face of the retaining wall location as well as three cross sections along the length. QCEC used the soil profile to assist in selecting an appropriate retaining wall for the soil type on site. Site conditions and the soil profile are discussed in more detail in Section 4.0.

Several retaining wall types were researched in an effort to select the best option for the current site conditions and restraints. Potential solutions that were researched include:

- Mechanically Stabilized Earth (MSE) walls
- Earth backfilling
- Prefabricated modular or rigid gravity walls
- Reinforced concrete cantilever walls
- Soil nailing
- Partially embedded soldier piles
- Continuous sheet pile walls.

These retaining wall types were summarized by advantages and disadvantages then ranked in a decision table based on four criteria: applicability to the project, cost, ease of construction and construction time. Based on the decision table, two options (soldier pile and soil nail retaining wall) were selected for the Duckworth Street retaining wall as detailed in Section 3.0.

A preliminary design and cost estimate for both designs were completed to determine if one option was more cost efficient. Sections 5.1.2 and 5.2.2 outline the cost estimates based on preliminary design of each option.

Upon the completion of the preliminary design, detailed design and drafting was completed for the soldier pile wall (selected design). The cost estimate was then completed using data from RSMeans, local supply stores and unit prices provided by the client. At the request of the client, Acuren, QCEC also developed a construction plan and schedule. The construction plan is outlined in Section 8.0 and includes the required actions to construct the soldier pile retaining wall as well as a schedule (Appendix K) that details approximate time required to complete each task.



3.0 LITERATURE REVIEW

Potential solutions for the temporary Duckworth Street retaining wall are outlined below in Table 3.1.

Wall Type	Advantages	Disadvantages
Mechanically Stabilized Earth (MSE) Walls	 Easy to install Quick construction time Low labour costs 	 Height limited to 8.5m Wide base (~70% of retaining wall height)
Earth Backfilling	 Low cost (only equipment and labour costs since method uses existing soil) Easy to construct 	 Not suitable for high walls and large loads/pressure Wide base
Prefabricated modular or rigid gravity walls	 Can be used for depths >8.5m Reduced construction time due to prefabrication Potentially high cost 	 Wide base (~50-70% of the retaining wall height) Costly if not prefabricated with concrete or timber cribs/bins Can be difficult to construct depending on the design
Reinforced Concrete Cantilever Wall	 Can be used for depths >8.5m Smaller than a concrete gravity wall 	 Economical up to ~7.5m Wide base (~50-60% of retaining wall height)
Soil Nailing	 Economical alternative to traditional retaining walls Can be used for narrow spaces 	Not applicable for loose soil.
Partially Embedded Soldier Piles	 Narrow base Less labour required Lower labour costs Can be used for building pits and areas with underground facilities 	 Increased costs if concrete or steel panel lagging is used A tie back system may be required to support increased heights and loading
Continuous Sheet Pile Walls	• Narrow base	 Ideal height <6m A tie back system may be required to support increased heights (up to ~24m)

Table 3.1: Wall Type Comparison



Based on the advantages and disadvantages outlined above, it was evident that some options will not be feasible for the location. The limited space for the retaining wall due to the construction of the parking garage and condominium is a major factor in choosing a retaining wall. The critical height to be used in the design of the retaining wall is approximately 8.5 meters. Therefore, options with a wide base (50%-70% of wall height) such as MSE walls, gravity walls and reinforced concrete cantilever walls will not be applicable. Also, the earth backfilling would not be suitable for the height required of the retaining wall. However, a decision table based on weighted factors was developed to determine the best option for the site's criteria (Table 3.2).

Wall Type	Applicability	Cost	Ease of Construction	Construction Time	Total	Rank
Weighting Factor	70%	15%	10%	5%	100%	-
Mechanically Stabilized Earth (MSE) Walls	3	2	2	2	2.7	5
Earth Backfilling	3	1	2	2	2.6	4
Prefabricated modular or rigid gravity walls	3	2	2	2	2.7	5
Reinforced Concrete Cantilever Wall	3	3	2	3	2.9	7
Soil Nailing	1	2	2	2	1.3	2
Partially Embedded Soldier Piles	1	1	2	2	1.2	1
Continuous Sheet Pile Walls	2	2	3	2	2.1	3

Applicability		Ease of	Construction
(based on height & space)	Cost	Construction	Time
1-Most Applicable	1-Low	1-Easy	1-Relatively Short
2-Possibly Applicable	2-Medium	2-Easy to Difficult	2-Short to Long
3-Least Applicable	3-High	3-Difficult	3-Relatively Long



QCEC determined four factors to be considered when choosing the retaining wall: applicability, cost, ease of construction and construction time. These factors were weighted based on QCEC's understanding of the client's needs with regards to the chosen retaining wall. The retaining wall's applicability to the site conditions (e.g. limited space for the base of the wall) was weighted with a factor of 70%. This factor was particularly high because if the base of the retaining wall is not narrow enough it cannot be considered an option. Cost was given a factor of 15% because if two options were considered equal in all regards the most cost efficient option would be chosen. Ease of construction and construction time were ranked the lowest with 10% and 5% respectively. Ease of construction was ranked slightly higher because the retaining wall is in a residential area, therefore minimal interruptions and noise due to construction methods would be ideal.

Based on the results of Table 3.2, a soldier pile wall would be the best option for the Duckworth Street temporary retaining wall and soil nailing could be a second possible alternative.

4.0 SITE CONDITIONS

In 2011, exp Services Inc. conducted a geotechnical subsurface investigation including a total 13 test pits and seven boreholes. Four boreholes (BH02, BH04, BH05 and BH06) and three test pits (TP08, TP12 and TP13) were located in the vicinity of the proposed retaining wall (Figure 03 of Appendix C). The report detailing the investigation was provided to QCEC by Acuren Group Inc. for reference throughout the design of the retaining wall (Appendix A).

QCEC analyzed the borehole and test pit records to create a soil profile for the benefit of the design process (Appendix C). Four cross sections were developed by linear interpolation of these records as shown in Figures 01 to 04 of Appendix C. The soil on site consists mainly of granular fill and till which extends from 0.3 to 8.41 meters below ground surface. The report describes the fill as greyish brown or dark grey to black gravelly sand with some silt and occasional cobbles and boulders. The till is described as brownish-grey to grey gravelly sand to a sand and gravel with traces of some silt and occasional cobbles and boulders. Bedrock is classified as very severely fractured to fractured medium grey sandstone.

Based on the geotechnical analysis, exp Services Inc. recommended soil parameters for design which are outlined below in Table 4.1. These are the parameters used by QCEC throughout the design of the retaining wall.



From Table 2 of the Geotechnical Report (Appendix A)				
Proposed Parking Garage				
Duckworth Stre	et at Bell Street			
St. John's, Newfoundland and Labrador				
Parameter Compacted Engineered Fill				
Total Unit Weight, KN/m3 20.5				
Buoyant Unit Weight, KN/m3	10.5			
Effective Friction Angle, degrees	36			
Coefficient of Active Earth Pressure, K _a 0.26				
Coefficient of Passive Earth Pressure, K _p 3.8				
Coefficient of Earth Pressure at Rest, K _o 0.41				

Table 4.1: Recommended Geotechnical Parameters

As requested by the client, a one meter space must be maintained between the retaining wall and the building construction line to ensure accessibility for construction. This request placed size restrictions on the type of retaining wall that can be implemented in the limited space. However, based on the retaining wall location in Figure 05 of Appendix C, the space between the retaining wall and construction line is 5.09 meters on the south end (soil height of 2.78 meters) and 4.4 meters on the north end (soil height of 7.33 meters).

In addition, soil will be removed for the construction of the retaining wall and the bedrock will be excavated in steps to provide a level construction surface (Figure 02 of Appendix D).



5.0 PRELIMINARY DESIGN

Based on the literature review and the site conditions, two potential options were explored by QCEC. The top two ranked options in Table 3.2 were soldier pile wall and soil nailing wall. QCEC developed a preliminary design and cost estimate of each option to determine which option would be more efficient for the Duckworth Street Retaining Wall.

5.1 SOLDIER PILE RETAINING WALL

5.1.1 DESIGN

The preliminary design of the soldier pile retaining wall includes HP piles and timber lagging along the 65 meter length of the proposed retaining wall location. Typical values were found through literature review and communication with the client and used to complete the preliminary design. The piles are spaced at 3 meters, therefore, the number of piles required was determined by dividing the length of the wall by the spacing plus an additional pile at the end. The number of steel piles required using this design method is 22. The timber lagging placed between the steel piles have an assumed typical dimension 100x250 millimeters. The amount of timber required for the design was determined based on an assumed retaining wall height of 7 meters. The holes for placing the piles are drilled and and based on a typical diameter of 550 mm (steel casing) and will need to be done for each pile (assumed embedment depth of 2 meters). Tiebacks are also required if the wall exceeds a height of 4.5m [1], therefore, the preliminary design assumes that at least one tieback will be required for each pile. Tiebacks include steel rods, grouting and drilling which has also been considered in the preliminary design. Typical assumed lengths for grouting are 4.5 meters with a diameter of 168 millimeters (Appendix G) therefore QCEC assumed a total tieback length of 8 meter for each pile.






Figure 5.2: Soldier Pile Retaining Wall

5.1.2 COST

The soldier pile wall has typical components as determined in the preliminary design that must be considered for the cost estimate. The steel sections, timber, labour and equipment are the main factors to be considered for the initial cost estimate. Based on the preliminary drawings and design for the soldier pile retaining wall, 22 pile are required. The piles are placed by drilling holes into the ground, therefore equipment and labour is taken into account for this as well. The client has provided QCEC with some typical cost values that can be used for steel (kg), concrete (m³), drilling in soil and bedrock (m) and grout (m³), which include the materials, equipment, labour (Table 5.1). The holes are based on a 550 millimeter diameter for steel casing and the cost is determined using lineal meters of drilling required for both soil and bedrock. The concrete is required for the embedment of the piles and a volume can be determined based on the hole diameter and assumed embedment depth. Considering the height of the wall, QCEC implemented an estimate of one tieback per soldier pile. The tieback cost includes the anchor (steel – kg), the grouting (m³) and the drilling (m).



Item	Unit	Unit Price
Excavation (Soil)	m3	\$15.70
Excavation (Rock)	m3	\$39.25
Steel	m3	\$3.50
Concrete	m3	\$650.00
Grout	m3	\$400.00
Drilling (Soil)	m	\$180.00
Drilling (Rock)	m	\$550.00

The timber that is placed between each steel section is 250x100 millimeters and 3 meters long. Based on these timber dimensions and an average wall height of approximately 7 meters, QCEC calculated the quantity of timber required for the design. The cost of timber and labour required (two labourers) can be calculated with data from RSMeans.

The preliminary cost estimate for the soldier pile retaining wall is outlined below in Table 5.2.

SOLDIER PILE WALL					
ITEM	UNIT PRICE	TOTAL			
PILES:					
STEEL	24200	kg	\$3.50	\$84,700.00	
CONCRETE @ BASE	10.454	m3	\$650.00	\$6,794.87	
DRILLING (SOIL) (550mm diam)	176	m	\$180.00	\$31,680.00	
DRILLING (ROCK) (550mm diam)	44	m	\$550.00	\$24,200.00	
TIMBER LAGGING (RS Means)	588.9	ea	N/A	\$27,326.87	
TIE-BACKS:					
RODS	1126.4	kg	\$3.50	\$3,942.40	
GROUT	2.1945	m3	\$400.00	\$877.82	
DRILLING (168mm diam)	176	m	\$65.45	\$11,520.00	
TOTAL:				\$191,041.96	



5.2 SOIL NAIL RETAINING WALL

Soil nail retaining walls consist of soil nails installed and grouted into the soil then sprayed with shotcrete and connected to a concrete face (cast-in-place) along the soil to be retained [2]. In Figure 5.2-a below, two soil nails are already installed and sprayed with shotcrete and a third soil nail is in the process of installation. In Figure 5.2-b, the layer of shotcrete is sprayed on the third soil nail. Figure 5.2-c, all three soil nails are installed with their layer of shotcrete.




Figure 5.2: Soil Nail Retaining Wall [3]

The soil nails are composed of steel bars that are drilled and grouted at a specified angle to the horizontal [2]. These retaining walls require a "prequalified Anchored Wall Contractor" for construction which is unavailable in Newfoundland, therefore a contractor would have to relocate to Newfoundland for the duration of construction.

5.2.1 DESIGN

The preliminary design is based on standard design dimensions [2]. Shotcrete should be a minimum of 4 inches thick and the concrete facing should be a minimum of 8 inches thick. The concrete face should also extend 6 inches above the soil grade. Drain strips are also placed a maximum of 10 feet horizontally [2]. Typically, soil nails are installed with a drill hole diameter of 6 to 8 inches at an angle of 20 degrees to the horizontal. Preliminary drawings for the soil nail retaining wall are in Appendix E.



5.2.2 COST

Soil nail retaining wall quantity take-offs include the soil nails (anchors), shipping of the anchors, grouting, shotcrete and steel mesh. The cost of these items were provided by the client based on typical values used for cost estimates (Table 5.1). The preliminary design includes approximately 149 nails which is the main factor when completing the cost estimate. However, the material for the soil nails must be shipped from out of province. The exact location is unclear but QCEC assumed Toronto, Ontario for the preliminary estimate. RSMeans supplies a cost per kilometer for shipping; therefore using the travel distance from Toronto to St. John's (3075 kilometers) QCEC determined an approximate shipping cost.

The preliminary cost estimate for the soil nail retaining wall is outlined in Table 5.3 below.

SOIL NAILING								
ITEM QUANTITY UNIT UNIT PRICE TOTAL								
Nails								
STEEL	5523.90	kg	\$3.50	\$19,333.66				
SHIPPING (RS Means)	3075	km	\$1.26	\$3,874.50				
GROUT	28.0044	m3	\$400.00	\$11,201.75				
DRILLING	863.11	m	\$65.45	\$56,494.46				
STEEL MESH/Concrete	332.3	m2	\$430.60	\$143,071.84				
TOTAL:				\$ <mark>233,976.21</mark>				

Table 5.3: Preliminary Cost Estimate for Soil Nail Retaining Wall

In addition, due to the fact that a contractor experienced with soil nail retaining walls is not located in Newfoundland, additional costs would incur to relocate a contractor for the duration of the project. These costs were not calculated because the soil nail retaining wall (Table 5.3) is already considerably more expensive than the soldier pile retaining wall option (Table 5.2). For that reason, QCEC elected to design a soldier pile retaining wall for the construction of the Duckworth Street parking garage and condominium complex.



6.0 GENERAL DESIGN AND SKETCHING

6.1 GENERAL

Based on the preliminary design and cost estimate for the soil nail and soldier pile retaining wall, the soldier pile wall is the most feasible and economical option.

However, as discussed in Section 4.0, the south end of the proposed retaining wall location has an available space of approximately 5 meters to the construction line. In this area it is not necessary to have a retaining wall with a narrow base. Therefore, combining a rigid gravity retaining wall with a soldier pile wall is a cost saving alternative. Rigid gravity walls are constructed of unreinforced concrete which is readily available in Newfoundland. Conversely, steel H-pile sections are uncommon in Newfoundland and must be delivered from the Nova Scotia. This adds additional shipping expenses (included in unit prices in Table 5.1) which will be reduced by implementing a concrete rigid gravity retaining wall.

6.2 RIGID GRAVITY RETAINING WALL

Rigid gravity walls are suitable to retain up to 8.5 meters of soil with a base width of approximately 60-70% of the wall height. Although its large dimensions make it an unsuitable choice for the entire retaining wall due to limited available space, the south end of the retaining wall has approximately 5 meters available to the construction line and 3 meters of soil to retain. This available space makes the rigid gravity wall a good alternative to the soldier pile wall due to its lower cost. Therefore, QCEC proposed to construct a 15 meter long rigid gravity wall starting from the south end of the retaining wall location.

As shown in Figure 6.1-a below, the final design of the rigid gravity wall includes a width of 0.5 meters at the top, 2 meters at the bottom, and height of 4 meters. The retaining wall is designed to run parallel to the construction line of the proposed parking garage and maintain a distance of 1 meter to the construction line.






Figure 6.1 - Rigid Gravity Retaining Wall

Due to the excavation of the bedrock (Figure 02 of Appendix D), the design height for the rigid gravity wall is 6 meters. The retaining wall is designed for a strength of 24 MPa cast-in-place concrete. Other assumptions for the rigid gravity wall design include:

- Natural backfill (excavated soil is used as backfill)
- Backfill slope of 1:1
- Groundwater level is below the base of the rigid gravity retaining wall
- Wall friction is zero
- Effective friction angle, ϕ' , is used as both the critical state friction angle ϕ'_{cs} and peak friction angle ϕ'_{p} .
- 12 KPa design surcharge load



(Equation 6.2-1)

6.2.1 LOADING

The rigid gravity wall must be designed to resist three types of failure: translational failure, rotational failure, and bearing failure. The initial step is to determine the lateral forces applied on the wall by the retained soil. The active soil pressure from the retained soil is calculated by using Rankine's Method:

$$P_{asoil} = \frac{1}{2} K_a \gamma H_o^2$$

where:

K_a = the active earth pressure coefficient

 γ = total unit weight of the soil (kN/m³)

 H_o = height of the wall

The active pressure created by the design surcharge load must also be calculated using:

$$P_{asurcharge} = K_a q H_o \tag{Equation 6.2-2}$$

Due to the sloped backfill, the concentrated active load caused by the retained soil is acts at one third of the wall height at the same angle as the backfill slope (1:1). The concentrated active load caused by the surcharge acts horizontally at one half of the wall height. In an effort to simplify the calculations, the active loads applied on the retaining wall can be transformed into horizontal and vertical components with the following equations:

$P_{ah} = P_{asoil} \times \frac{b}{c} + P_{asurcharge}$	(Equation 6.2-3)
$P_{av} = P_{asoil} \times \frac{a}{c}$	(Equation 6.2-4)

where:

a = 1 unit meter horizontal distance of backfill

b = 1 unit meter vertical distance of backfill

c = inclined distance of backfill for 1:1 slope



6.3 FAILURE MODES

The design of the gravity retaining wall should resist all three modes of failure: translational failure, rotational failure and bearing failure.

6.3.1 TRANSLATIONAL FAILURE

For the retaining wall to resist translational failure, the base should sufficiently resist the lateral forces applied to the wall by the retained soil. The typical factor of safety used for translation is 1.5.

In an effort to simplify calculations, QCEC divided the retaining wall into a triangular and rectangular shape based on its geometry (Figure 6.1-b). The weight of each components are calculated using:

$W_1 = \frac{1}{2} \times b_1 \times H_o \times \gamma_c$	(Equation 6.3-1)
$W_2 = b_2 \times H_o \times \gamma_c$	(Equation 6.3-2)
$W = W_1 + W_2$	(Equation 6.3-3)

where:

 b_1 , b_2 = Dimension of each component

H_o = Height of the retaining wall

 γ_c = Unit weight of concrete

W = Total weight of retaining wall

The total moment on the retaining wall is calculated from Equation 6.3-4 below using dimensions shown in Figure 6.1-b:

$$M_o = W_1 \times x_1 + W_2 \times x_2 + P_{av} \times B - (P_{ah} - P_{asurcharge}) \times Z_a - P_{asurcharge} \times Z_b$$



The location of the vertical resultant force at the base of the retaining wall can be calculated with:

$$\bar{x} = \frac{M_o}{R_z}$$
 (Equation 6.3-5)

where:

M_o = Total moment on retaining wall

 R_z = Resultant vertical force (W+P_{av})

The base resistance can then be calculated:

$$T = R_z \times \tan(\phi'_b)$$
 (Equation 6.3-6)

where:

R_z = Vertical resultant force

 ϕ'_{b} = Base resistance factor

The factor of safety for translation is determined by:

$(FS)_T = \frac{T}{P_{ah}}$	(Equation 6.3-7)
-----------------------------	------------------

where:

T = Horizontal resistance of the base

P_{ah} = Horizontal force from active soil pressure

As shown in Appendix I, the final design has a factor of safety against translation of 1.568, which is greater than the minimum value of 1.5. Therefore, the design is safe against translational failure.



6.3.2 ROTATIONAL FAILURE

The rigid gravity wall must also resist rotational failure. If the vertical resultant force, R_z , is located between one third and two thirds of the base width, the wall is considered safe. The eccentricity of R_z is calculated with:

 $e = \left| \frac{B}{2} - \bar{x} \right|$

(Equation 6.3-8)

where:

B = Width of the base

 \bar{x} = Location of vertical resultant force

If the eccentricity is less than B/6 (0.333 meters), the wall is considered safe against rotation. The final design has an eccentricity of 0.007 meters, therefore the design is safe against rotational failure.

6.3.3 BEARING FAILURE

Finally, the rigid gravity wall must also resist bearing failure which means the allowable soil bearing capacity should be greater than the maximum pressure caused by the gravity wall on the soil. Since the wall is safe against rotational failure, no tensile forces will develop in the soil. The maximum stress occurs at point A in Figure 6.1-c and can be calculated from:

$$\sigma_{max} = \frac{R_z}{A} \times (1 + 6 \times \frac{e}{B})$$

(Equation 6.3-9)

where:

R_z = Vertical resultant force

A = Area of base

e = Eccentricity

B = Width of the base



The vertical resultant force, Rz, is inclined to the vertical and eccentric (Figure 6.1-c). Therefore, a bearing capacity equation considering the inclined load should be used:

$$\omega = \tan^{-1} \frac{H}{V_n}$$
 (Equation 6.3-10)
where:
H = P_a

 $V_n = R_z$

The base of the retaining wall can be treated as a strip footing; therefore the B/L is approaching zero. The allowable soil capacity can be calculated using the following equation:

$$q_{u} = 0.5\gamma B' N_{\gamma} i_{\gamma}$$
(Equation 6.3-11)
where:

$$B' = B - 2e$$

$$N_{\gamma} = 0.1054e^{(9.6\phi_{\gamma}p)}$$

$$i_{\gamma} = (1 - \frac{H}{V_{n}})$$

The factor of safety against bearing can be calculated by:

$$(FS)_B = \frac{q_u}{\sigma_{max}}$$
 (Equation 6.3-12)

Typically, a factor of safety of 3 for bearing is considered safe. In the final design of the rigid gravity wall, a factor of safety of 4.29 was obtained which shows that the design is sufficient against bearing failure (Appendix I).



6.4 DRAINAGE

Precipitation may increase the groundwater level and subsequently increase the water content of the backfilled soil. This can decrease the stability of the retaining wall and cause it to fail. Weep holes have been implemented into the design to provide drainage for excess water. As shown in Figure 04 of Appendix D, weep holes with a 75 millimeter diameter were used in the concrete retaining wall with a horizontal and vertical spacing of 1.5 meters.

6.5 SOLDIER PILE RETAINING WALL

Prior to detailed design of the soldier pile retaining wall, an excavation plan was developed for the reshaping of the bedrock in the location of the retaining wall (Figure 02 of Appendix B). Based on the drawing, three different retaining wall heights were determined based on each 'step.' The critical section (8.41 meters) is located on the lowest step and will have a retaining wall height of 8.5 meters. Other sections of the soldier pile retaining wall will have a height of 7.5 meters or 6.5 meters based on the excavation plan.

In general, soldier pile walls exceeding 4.5 meters in height require the use of tiebacks [1]. When the soldier pile wall heights were finalized, it was evident that at least one or two tiebacks would be required at each height. In an effort to determine the number of tiebacks required, three retaining wall models were developed: cantilever soldier piles, soldier piles with one tieback and soldier piles with two tiebacks.

6.5.1 TIEBACK LAYOUT

Typically tiebacks are installed at a slight angle (15°) from the horizontal [1] to limit additional axial forces on the soldier piles. However, for the Duckworth Street retaining wall, underground obstructions had to be considered when designing the tiebacks. According to the client, underground sewer facilities are located approximately 2 meters below the surface of Henry Street along the length of the retaining wall location. For this reason, the first tiebacks are located 2 meters below the top of the soldier piles. This placement combined with the angle of the tiebacks proves sufficient for avoiding the underground sewer facilities. Based on suggested guidelines, the second anchor will be installed 3 meters below the first anchor [4]. In addition, residential housing is located across Henry Street, therefore the horizontal distance of the tiebacks cannot exceed the width of the street (approximately 8.5 meters) to avoid conflicts with housing. Subsequent to an evaluation of several tieback angles, an angle of 30° to the horizontal was selected to avoid the housing across Henry Street. The final layout of the soldier pile and tieback system is shown in Figure 6.2 below.






Figure 6.2: Layout of the Selected Tieback System

6.5.2 LOADING

The retaining wall was designed to resist the lateral earth pressure of the soil and a uniform surcharge load (q) applied along the surface of the retained soil (Figure 6.3). In the case of the Duckworth Street retaining wall, it is assumed that the water table is not encountered and sufficient drainage is provided in the design, therefore water pressure is neglected.




Figure 6.3: Lateral Earth Pressures for Retaining Wall Design



The active earth pressure (p2) acts along the height of the wall:

$$p2 = K_a \gamma H$$

where:

K_a = the active earth pressure coefficient

 γ = Total unit weight of the soil (kN/m³)

H = Height of the wall

The surcharge load creates a uniform load along the length of the retaining wall (p1) which is calculated with Equation 6.3-2 shown below. Typically for design purposes, the surcharge load is taken as 12kPa [5].

 $p1 = K_a q$

where:

K_a = Active earth pressure coefficient

q = Uniform surcharge load (12kPa)

6.5.3 SOLDIER PILE ANALYSIS

Soldier piles are usually H-pile sections due to their equivalent dimensions and typically spaced at 2-3 meters. In an effort to reduce the number of piles required along the length of the wall, QCEC utilized a spacing of 3 meters in the design of the soldier pile retaining wall. S-FRAME models were developed for the three soldier pile design cases at 8.5 meters, 7.5 meters, and 6.5 meters. The pile loads were determined by multiplying p1 and p2 (Figure 6.3) by the tributary area (3 meters) and can be reviewed in Appendix F.

When the models were run through S-STEEL, the program suggested a HP310x79 section for the 8.5 meter soldier piles with two tiebacks. However, in the interest of safety, QCEC chose to use the slightly larger section of HP310x110 for the soldier piles. This section was evaluated using S-STEEL for all S-FRAME models and a summary of its results are detailed below in Table 6.1. Based on the section checks from the S-STEEL analysis, two tiebacks are required for the 8.5 meter soldier piles and one tieback could potentially be sufficient for the 7.5 and 6.5 meter piles.

(Equation 6.5-1)

(Equation 6.5-2)



Wall Type	N _f (KN)	V _f (KN)	M _f (KN)	Code Check Results	Comment
8.5 m Cantilever	0	657	1975	> 1.0	Not OK
8.5 m Anchored -1 Tieback	132	429	490	> 1.0	Not OK
8.5 m Anchored -2 Tiebacks	238	246	155	0.575	ОК
7.5 m Cantilever	0	520	1388	> 1.0	Not OK
7.5 m Anchored -1 Tieback	113	325	313	0.726	ОК
7.5 m Anchored -2 Tiebacks	209	159	78	0.507	ОК
6.5 m Cantilever	0	399	930	> 1.0	Not OK
6.5 m Anchored -1 Tieback	96	233	183	0.44	ОК
6.5 m Anchored -2 Tiebacks	181	107	40	0.44	ОК

Table 6.1: HP310X110 Section Check Summary Table

Each wall height has a maximum allowable deflection of 0.005H based on guidelines outlined by the US Army Corps of Engineers. Table 6.2 below summarizes the maximum deflection of each soldier pile model and the maximum allowable deflection for comparison. The implementation of tiebacks reduces the maximum deflections at each height to an acceptable value.



Wall Type	Δ _{max} (mm)	Δ _{Allow} (mm)	Comment
8.5 m Cantilever	633.19	42.5	Not OK
8.5 m Anchored -1 Tieback	18.38	42.5	ОК
8.5 m Anchored -2 Tiebacks	2.19	42.5	ОК
7.5 m Cantilever	348.74	37.5	Not OK
7.5 m Anchored -1 Tieback	8.73	37.5	ОК
7.5 m Anchored -2 Tiebacks	1.27	37.5	ОК
6.5 m Cantilever	177.08	32.5	Not OK
6.5 m Anchored -1 Tieback	3.62	32.5	ОК
6.5 m Anchored -2 Tiebacks	1.27	32.5	ОК

Table 6.2: Deflection Check Summary Table

The embedment depth of the soldier piles is based on the shear force at the base of the critical section (8.5 meter height). As shown in Table 6.1 above, the shear force for the 8.5 meter pile with two tiebacks is 246 kN. In an effort to reduce the required embedment depth, the shear force at the base of the 7.5 and 6.5 meter piles must be less than 246 kN. Therefore, one tieback for the 7.5 meter soldier piles will not be sufficient (325 kN) and for that reason, two tiebacks have been implemented. However, one tieback is sufficient for the 6.5 meter soldier piles (233kN).

The required depth of the soldier pile is calculated based on the Wang-Reese equations for ultimate passive resistance of cohesionless soils [6]. The passive force, F_p , resists the shear force that is created at the base of the wall (Figure 6.4).






Figure 6.4 - Passive Force and Shear Force on Soldier Pile

 F_p is calculated from **Equation 6.5-3** [6] below:

$$F_{p} = \gamma d^{2} \left[\frac{K_{0} tan\varphi' sin\beta}{tan(\beta - \varphi') cos\alpha} + \frac{tan\beta}{tan(\beta - \varphi')} \left(\frac{b}{2} + \frac{d}{3} tan\beta tan \propto \right) + \frac{K_{0} d tan\beta}{3} (tan\varphi' sin\beta - tan\alpha) \right]$$
Where:
 $\gamma = \text{total unit weight of the soil (kN/m^{3})}$
 $d = \text{embedment depth}$
 $K_{0} = \text{at-rest pressure coefficient}$
 $\beta = 45 + \varphi'/2$
 $\alpha = \varphi' (\text{dense sands})$
 $b = \text{diameter of soldier pile}$

 ϕ ' = drained friction angle of soil

After the embedment depth is determined from Equation 6.5-3 it is multiplied by a factor of safety of 1.5. This results in a safe embedment depth of 3.0 meters which is implemented for all soldier piles.



6.5.4 TIEBACK DESIGN

Tiebacks have to be designed to sustain the axial forces of the tie members from the S-FRAME analysis (Table 6.3).

Wall Height (m)	Tieback	Axial Tensile Force (kN)
8.5	Upper Tieback	146
0.5	Lower Tieback	330
7 5	Upper Tieback	157
7.5	Lower Tieback	261
6.5	Upper Tieback	192

Table 6.3: Axial Tensile Forces in Tiebacks

Based on the S-FRAME results, the tiebacks must be designed for 330 kN. The capacities of various tie rod diameters were established from DYWIDAG product information [7]. A diameter of 32 millimeters will provide a yield load of 402 kN which is sufficient for the maximum tensile force in the tiebacks. The tiebacks are also designed in two other portions: the unbonded length and the bonded length.

The unbonded length must extend a distance of H/5 or 1.5 meters beyond the soil's failure plane [6]. The failure plane is located at an angle of $45^{\circ} - \frac{\varphi}{2}$ from the base of the retaining wall (Figure 6.5).




Figure 6.5: Theoretical Failure Plane



The interception points for the tiebacks and the theoretical failure plane were determined by plotting the failure plane and both tiebacks for each wall height (Appendix D). The top tieback of the 8.5 meter section governs the unbonded length design with a length of 4.5 meters.

The bonded length of the tiebacks is determined from the Design Anchor Capacity Estimates table provided to QCEC by the client (Appendix G). Based on the geotechnical report, QCEC determined the anchors would be bonded in either severely fractured bedrock or fractured sandstone bedrock. The provided table shows that severely fractured bedrock provides lower anchor capacities. Therefore, bond length was determined based on the criteria provided for the anchors bonded in severely fractured bedrock. Based on the load tested capacities, a bond length of 4.5 meters will provide 475 kN which will be sufficient to resist the maximum tensile force in the anchors.

The final tieback design includes a 32 millimeter diameter rod and a total length of 9 meters with a bonded length of 4.5 meters.

6.5.5 TIMBER LAGGING DESIGN

The lagging used for the soldier pile wall is untreated timber with a service life of three years. Since the retaining wall is temporary, all timber lagging will be untreated. The initial design of the timber lagging is based on the recommended thicknesses from the US Army Corps of Engineers [6].

The soil is considered to be a 'competent' soil with a clear span of 3 meters and a critical height of 8.5 meters. Based on these criteria, a thickness of 100 millimeters is recommended up to approximately 7.5 meters and a 125 millimeter thickness for timber deeper than 7.5 meters. The client informed QCEC that typical sizes of timber available have dimensions of 250x75 and 250x100 millimeters. Therefore, based on these recommendations, QCEC would suggest to use 250x100 millimeter sized timber for the retaining wall up to a depth of 7.5 meters then doubling the same sized timber for the deeper sections.

This design was verified by the wood design manual from the Canadian Wood Council. First, the factored load applied to the timber by the retained soil is calculated for different depths. The critical design depth used is 8.5 meters and the pressure is established every 0.5 meters. Assumptions relating to the calculations included:

- Untreated saw timber
- Members are intended to support permanent loads
- Wet service condition
- Timber is Spruce-Pine-Fir (S-P-F) Grade No.1
- Members are treated as simply support beams with uniform loading
- Timber is not notched
- No live load



The factored load which the soil applied to the timber can be calculated use equation:

$$w = K_a \times \gamma \times \left(H - \frac{b}{2}\right) + K_a \times q) \times b \times 0.6 \times 1.25$$
 (Equation 6.5-4)

where:

- w = Normally distributed load on the timber lagging
- K_a = Active earth pressure coefficient

 γ = Total unit weight of soil

- H = Depth measured from the ground surface
- b = Width of the timber lagging
- q = Uniform surcharge load (12KPa)
- 0.6 = Factor used to compensate for soil arching behind lagging
- 1.25 = Dead load safety factor

The maximum moment is then calculated:

$$M = \frac{w \times l^2}{8}$$
 (Equation 6.5-5)

where:

w = Normally distributed load on the timber lagging

I = clear span of the timber lagging



The section modulus of each section is calculated:

$$S = \frac{b \times d^2}{6}$$

where:

- b = Width of the timber lagging
- d = Thickness of the timber lagging

The bending stress is calculated:

$$\sigma = \frac{M}{S}$$

where:

- M Maximum bending moment
- S Section modulus

Based on the Wood Design Manual, 2005, the bending strength at the extreme fibre of S-P-F Grade No. 1 is 11.0 MPa. This number is reduced by a factor of 0.77 because the load is applied to the wider face of the timber. The calculated bending stress can then be compared to the bending strength. If the bending stress is less than the bending strength then the time section is considered adequate.

Based on the calculations (Appendix H), QCEC recommends 250x100 mm S-P-F Grade No. 1 timber for the first 2.5 meters then double the 250x100 mm timber for the remaining depth (i.e. 250x200mm).

This final timber lagging design differs from the initial design outlined by the US Army Corps of engineers because S-P-F is a relatively weaker timber species.

In addition, the timber members are spaced 25 millimeters to allow for drainage.

(Equation 6.5-6)

(Equation 6.5-7)



6.6 DRAFTING

There are three sets of AutoCAD drawings prepared for Duckworth Retaining Wall: Soil Profile, Construction Drawings for Soldier Pile and Rigid Gravity Retaining Wall, and Preliminary Drawings for Soil Nailing Retaining Wall. These drawings are outlined in Table 6.4 below.

Appendix	Drawing Number	Sheet	Description		
	Figure 01	S01	Borehole and test pit locations relevant to developing the soil profile		
с	Figure 02	S02	Locations of four cross sections		
C	Figure 03	S03	Cross section 1-1'		
	Figure 04	S04 Cross sections 2-2', 3-3' and 4-4'			
	Figure 05		Proposed retaining wall location		
	Figure 01	A01	Layout of the retaining wall site		
	Figure 02	A02	Stepped excavation profile for retaining wall		
D	D Figure 02		Plan and elevation view of soldier pile and rigid gravity		
	Figure 03	A03	retaining wall		
	Figure 04	A04	Soldier pile and rigid gravity retaining wall details		
Е	Figure 01	A01	Plan and elevation view of soil nailing retaining wall		
	Figure 02	A02	Side view of soil nailing retaining wall		

Table 6.4: List of Drawings

The soil profile drawings in Appendix C are intended to show type and depths of soil in the retaining wall location. The geotechnical information in these drawings were linearly interpolated from the provided geotechnical report (Appendix A).

The construction drawings in Appendix D show the layout and detailed design of the soldier pile and rigid gravity (south end) retaining wall (Figure 03). Drawings include the plan and elevation view of the retaining wall and details of the timber and tieback design (Figure 04). The bedrock in the location of the retaining wall is sloped 12 degrees on the south side and 4 degrees on the north side of the critical depth (8.41 meters). The excavation profile (Figure 02) was developed in 0.5 to 1.0 meter steps to provide a level soil foundation for construction of the retaining wall.

Appendix E contains preliminary design drawings for the soil nailing retaining wall option. Drawings illustrate the plan, elevation and side view of the retaining wall. All dimensions used in this drawing are based on typical soil nailing designs.



7.0 COST ESTIMATE

7.1 QUANTITY TAKE-OFF

Based on the construction drawings for the rigid gravity and soldier pile retaining wall (Appendix D), QCEC performed a quantity take off for final cost estimate. Table 7.1 shows the various items that have been taken-off to complete the cost estimate. The quantity take-offs were initially completed by calculating the amount of each material required and then converted into a weight or volume based on dimensions. For example, steel was evaluated as a total mass in kilograms due to the provided unit prices (Table 5.1). Other quantities use simple calculations to determine the number of items required (ie. timber).

Quantity Take-Off						
ITEM	ITEM DESCRIPTION					
Steel	Hp Beams - 310x310 - 11 Each	13255	kg			
Concrete	At pile embedment depths	7.84	m3			
Steel Casings	Used for drilling into soil - 11 Each - Rented	44826	kg			
Timber Lagging	Placed between piles	524	each			
Timber Blocking	To brace timber between steel flange - 2x4x8 Lumber	221	pieces			
Tie-Back Rods	19 Each	1094.4	kg			
Grout	Used for grouted length of tie-backs	2.68	m3			
L-angles	Used to support tie-backs at steel flange	4.57	kg			
Misc Steel	Used to brace steel and timber	4.39	kg			
Concrete	Concrete for rigid gravity wall	75	m3			
Formwork	Plywood	134.08	m2			
PVC Pipe	Used to form the weep holes in the rigid gravity wall - 3" diameter - approximately 1.5 m length	6	pieces			

Table 7.1 – Quantity Take Off



7.2 LABOUR AND MATERIALS

SOLDIER PILE WALL						
ITEM	QUANTITY	UNIT	UNIT PRICE	TOTAL		
EXCAVATION (SOIL)	21741.00	m3	\$15.70	\$341,333.72		
EXCAVATION (ROCK) (@concrete wall)	46.14	m3	\$39.25	\$1,811.00		
PILES:						
STEEL	13255	kg	\$3.50	\$46,392.50		
CONCRETE @ BASE	7.840	m3	\$650.00	\$5,096.15		
DRILLING (SOIL) (550mm diam)	86.73	m	\$180.00	\$15,611.40		
DRILLING (ROCK) (550mm diam)	39.25	m	\$550.00	\$21,587.50		
CASING (Rented-10% of New Cost)	44826	kg	\$3.50	\$15,689.10		
TIMBER LAGGING	523.5	ea	N/A	\$31,266.20		
BLOCKING (LUMBER)	221	рс	\$2.79	\$617.01		
TIE-BACKS:						
RODS	1094.4	kg	\$3.50	\$3,830.40		
GROUT	2.6861	m3	\$400.00	\$1,074.42		
DRILLING (200mm diam)	171	m	\$65.45	\$11,192.73		
L-ANGLE	4.5725	kg	\$3.50	\$16.00		
MISC STEEL	4.3912	kg	\$3.50	\$15.37		
CONCRETE WALL:						
CONCRETE	75.0	m3	\$650.00	\$48,750.00		
FORMWORK	134.08	m2	N/A	\$5,420.71		
WEEP HOLES (PVC pipe)	6.00	ea	\$13.49	\$80.94		
TOTAL				\$549,785.15		
10% extra-misc items				\$54,978.52		
TOTAL:				\$604,763.67		
TOTAL W/ MARK UP (10%)				\$665,240.03		

Table 7.2 - Cost Summary – Soldier Pile Wall



The cost estimate for the soldier pile retaining wall was calculated based on prices from RSMeans, local building suppliers (Kent Building Supplies), and typical unit prices supplied by the client. Items that used costs supplied by the client included:

- Excavation (both in soil and bedrock)
- Steel
- Drilling (both in soil and bedrock)
- Concrete/Grout

The prices for these items used standard costs that were provided by the client (Table 5.1), these prices include the material, equipment and labour. The prices are provided as per unit costs; therefore the quantities that are taken off are multiplied by per unit cost to give the total.

RSMeans was also used to complete the cost estimate of the timber lagging and formwork for the concrete rigid gravity wall. The timber lagging design requires the timber to double at a specific depth (greater than 2.5m), therefore each section would have a height varying timber thickness. The timber section used in the design is 250x100 millimeters and its cost was determined from RSMeans. The daily output, bare material cost, and crew from RSMeans were used to develop a cost for materials and labour. A crew of two labourers was used for the installation of the timber at a cost of \$283.60 per day per labourer. The quantity take-off for timber (Table 7.2) is multiplied by a bare material rate of \$451.20/m³ from RSMeans. The per unit price for timber lagging is not shown in Table 7.2 as it includes both labour and materials and were calculated in another spreadsheet located in Appendix J.

The formwork for the rigid gravity wall is calculated using a price for plywood from RSMeans. The bare material price, \$22.38/m², is multiplied by the total area required to complete the formwork (Table 7.1). The labour used to complete this was taken as three labourers and one carpenter at a rate of \$283.60/labourer/day and \$359.20/carpenter/day. The time to complete this work should be a maximum of two days. The cost shown in Table 7.2 has been calculated in a separate spreadsheet as it includes the labour and material, similar to the timber lagging.

While most costs were found using typical per unit values or RSMeans, some smaller costs were found using local building supply stores. The blocking for the timber lagging and the weep holes located in the rigid gravity wall have are based on costs from Kent Building Supplies. The blocking for the timber requires four blocks (2x4 lumber) located between the steel flange and the timber lagging. The length required for all blocking was calculated and divided by 8 feet (length of lumber) then multiplied by the cost for each piece. The price found from a local supplier (Kent Building Supplies) was found at \$2.79/piece.



Similarly, the cost of the weep hole prices were determined by using PVC pipe as the material and a cost from Kent Building Supplies. Approximately 6 PVC pipes are required at a material cost of \$13.49/piece and a total cost of \$80.94.

After the cost estimate was completed, the final amount was increased by 10% to accommodate any additional costs (client recommended). In addition, the cost was increased by another 10% as a profit mark up.

8.0 CONSTRUCTION

8.1 METHODOLOGY

For the Duckworth Street Retaining Wall, QCEC designed a soldier pile wall with a 15 meter rigid gravity wall located on the south end (Figure 03 of Appendix D). The construction of the retaining wall is expected to be completed within 52 days (Appendix K).

The equipment for the soldier piles are first mobilized to site and set up to begin construction of the soldier pile wall. The equipment includes drilling equipment, a crane, and an excavator. The following steps explain how to construct the soldier pile wall with timber lagging

Soldier Piles and Lagging

- Holes are drilled into the soil using 550 millimeter casing to ensure the soil does not collapse (Figure 8.1). The holes are drilled at different depths, the most critical depth being 8.5 meters.
- 2. The HP piles are then placed in the hole and held there while the concrete is poured. After the concrete is poured the casings are removed.
- 3. When all piles have been installed across the length of the wall, excavation will begin in order to install the timber lagging. The excavation is done in one meter increments.
- 4. At each one meter increment, the timber lagging is placed behind the H-beams and braced with lumber blocking (Figure 8.2)
- 5. The soldier piles are also designed with tiebacks to prevent high deflections. Each soldier pile will have a minimum of one tieback with most of them having two. The tiebacks are installed as the excavation occurs, the first one at a 2 meter depth and the second 3 meters below the first.





Figure 8.1: Drilling of Steel Casing for Installation of HP Sections



Figure 8.2: Bracing of Timber Lagging



<u>Tiebacks:</u>

The tiebacks are installed using the following procedure:

- a. The holes for the tiebacks must be drilled for the required length and diameter at an angle of 30 degrees to the horizontal. There will be an unbonded length and a bonded length. The unbonded and bonded length will be the same for all tiebacks (4.5 meters). The diameter required for the bonded area of the tieback is 168mm, this will be the diameter for all drilled holes.
- b. The steel bars must be placed in the hole, and then the primary grout is applied.
- c. Performance and proof tests must be carried out on each bar to ensure sufficient installation.
- d. The bars are then stressed and locked off.
- e. Add secondary grout

The steel flange must be cut in order to drill holes and install the tiebacks. When the tiebacks are installed and tested, steel plates are welded back onto the flange for support. An L200x100x13 angle is also attached at the tieback as a steel connection to provide support.

6. As the excavation continues, the timber lagging and tiebacks will continue to be installed until it has reached the final depth.

Gravity Wall:

The gravity wall will begin construction on the south end when the desired depth of excavation is reached. It has a height of four meters and a length of approximately 15 meters. The base of the gravity wall is 2 meters thick and the top is 0.5 meters thick. PVC piping for the weep holes are to be installed within the concrete to allow for drainage.

The bedrock is excavated in order to place the formwork and begin the construction of the gravity wall. The formwork is constructed and placed in the correct location and then the concrete is poured. The piping for the weep holes is installed with the formwork to allow the concrete to form around them without seeping into the pipe. The concrete will take 14 days to cure and set and at that time the formwork can be removed. The soil behind the gravity wall will be sloped at a 45 degree angle to ensure that the soil does not fail.

- 7. Once both the soldier pile wall and gravity wall are complete, the soldier pile wall will be backfilled with the excess soil from the original excavation.
- 8. The final step is the demobilization of the site; all equipment will be removed.



9.0 CONCLUSION

Based on requirements outlined by Acuren, QCEC designed the most cost efficient solution for the Duckworth Street Retaining Wall.

Initially, QCEC determined a soldier pile retaining wall would be the most cost efficient option in comparison to a soil nail retaining wall. After a thorough analysis of the site conditions, it was determined that a rigid gravity wall could be implemented on the south end of the retaining wall location to reduce costs. The rigid gravity wall eliminated approximately 5 required soldier piles (large expense) and replaced them with unreinforced concrete. The materials required for the 15 meter length of the rigid gravity wall are much more cost efficient than 15 meters of additional soldier pile retaining wall.

At the request of the client, QCEC also developed a construction plan and schedule. The construction schedule details the actions required to construct the wall in 52 days. The construction of the rigid gravity and the soldier pile retaining wall have been scheduled to overlap for a period of the construction duration. This allows for efficient use of construction time and will limit the amount of disruption to the surrounding residential area.



10.0 REFERENCES

- [1] Caltrans (1997, July). *Foundation Manual: Chapter 11 Tiebacks, Tiedowns and Soil Nails.* [online]. Available: http://www.studioad.net/tieback.pdf [January 25, 2013].
- [2] State of North Carolina Department of Transportation, Raleigh (2012, May). *Soil Nail Retaining Walls.* [online]. Available: https://connect.ncdot.gov [January 25, 2013].
- [3] Juan Rodriguez (2011, February). "Soil Nailing Process". [online]. Available: http://www.youtube.com/watch?v=cRAEZTOCBm0 [March 6, 2013].
- [4] Fugro Consultants Inc. (2009, December). North Tarrant Express 2E. "Preliminary Geotechnical Recommendations for Drilled Shaft, Soldier Pile and Soil Nail Retaining Walls." [online]. Available: ftp://ftp.dot.state.tx.us/pub/txdot-info/ftw/nte/cda/0311/mdp/16_1_seg2e/nte%202e%20-%20tech%20memo%20%23%203%20-%20cut%20walls.pdf [February 9, 2013].
- [5] New York State Department of Transportation, Geotechnical Engineering Bureau (2007, April). *Geotechnical Design Procedure for Flexible Wall Systems*. [online]. Available: https://www.dot.ny.gov/divisions/engineering/technical-services/technical-servicesrepository/GDP-11b.pdf [January 22, 2013].
- [6] R.W. Strom and R.M. Ebeling (2001, December). "State of Practice in the Design of Tall, Stiff and Flexible Tieback Retaining Walls," US Army Corps of Engineers. [online]. Available: http://www.dtic.mil/cgi-bin/GetTRDoc?AD=ADA405009 [March 11, 2013].
- [7] DYWIDAG-SYSTEMS INTERNATIONAL. DYWIDAG Tie Rods. [online]. Available: http://www.dywidag-systems.com/uploads/media/DSI-DYWIDAG_Tie_Rods_02.pdf [April 4, 2013].

Standards and Codes

- Wood Design Manual, CSA-086-01, 5th ed., Canadian Wood Council, Ottawa, ON, 2005.
- Handbook of Steel Construction, CSA S16-09, 10th ed., Canadian Institute of Steel Construction, Willowdale, ON, 2011.
- Concrete Design Handbook, 3rd ed., Cement Association of Canada, Ottawa, ON, 2006.
- RSMeansOnline version 5.0.1, Reed Construction Data Inc, 2013.

Appendix A

Geotechnical Report

Letter-form Report:

GEOTECHNICAL SUB-SURFACE INVESTIGATION PROPOSED PARKING GARAGE AND CONDOMINIUMS DUCKWORTH STREET AT BELL STREET ST. JOHN'S, NEWFOUNDLAND AND LABRADOR

August 16, 2011

Project No. SJN-00021594-A0



• Henry Bell Development Ltd.

Geotechnical Sub-surface Investigation

Type of Document Letter-form Report

Project Name Proposed Parking Garage and Condominiums Duckworth Street at Bell Street St. John's, Newfoundland and Labrador

Project Number SJN-00021594-A0

Prepared by: William G. Melendy, M.A.Sc., P.Eng.

exp Services Inc. 60 Pippy Place, Suite 200 St. John's, NL A1B 4H7 Canada

Date Submitted August 16, 2011



The new identity of ADI Limited

August 16, 2011

exp File SJN-00021594-A0 (27-6628-001.1)

Henry Bell Development Ltd. 12 Caldwell Place St. John's, Newfoundland Labrador A1E 6A4

Attention: Mr. William Clarke

Dear Sirs:

RE: Geotechnical Sub-surface Investigation *Proposed Parking Garage and Condominiums* Duckworth Street at Bell Street St. John's, Newfoundland and Labrador

Acting on the request of Mr. William Clarke, representing *Henry Bell Development Ltd.*, **exp** Services Inc., the new identity of *ADI Limited*, has completed additional boreholes to supplement the previously-completed geotechnical sub-surface investigation at the Duckworth Street site. Specifically, three additional boreholes were advanced on Henry Street, and one borehole was advanced at the west side of Bell Street. The purpose of the investigation was to determine subsurface conditions, and update previous recommendations for the new parking garage/condominium project, as presented in the previously-completed reports, as follows:

Geotechnical Sub-Surface Investigation, Proposed Parking Garage, Duckworth at Bell Street, St. John's, NF, final report dated February 14, 2011

Geotechnical Sub-Surface Investigation, Proposed Parking Garage, Duckworth at Bell Street, St. John's, NF, letter-form report dated February 14, 2011.

1.0 FIELD PROGRAM

The field work for the additional borehole program was completed during the period July 5 to July 8, 2011, and consisted of four boreholes, advanced using a *CME-55* drill rig operated by *Logan Geotech Inc.* of Dieppe, New Brunswick. The boreholes were located in the field by **exp** in discussion with Henry Bell Development Ltd.. Final borehole locations are shown on *Figure 1: Borehole and Test Pit Location Plan*.



Conditions encountered in the boreholes are described below and on the Borehole Records attached. *Table 1: Summary of Borehole Data* presents the summarized findings of the investigation.

Borehole No.	Ground Surface Elevation (m)	Bottom of Fill Elevation/Top of Till (m)	Top of Bedrock Elevation (m)	End of Borehole Elevation (m)	Ground- water Elevation (m)		
BH01	17.77	16.0	16.0	13.7	16.9		
BH02	21.63	19.7	16.2	12.6	19.2		
BH03	22.76	21.7	21.7	13.0	21.3		
BH04	25.09	19.4	18.4	14.8	-		
BH05	25.71	22.6	17.3	15.6	<u></u>		
BH06	26.68	23.5	22.9	19.3	<u>.</u>		
BH07	19.94	17.6	17.0	13.9	-		

Asphalt

A 50 mm to 100 mm thick asphalt layer was encountered at the surface in BH04 to BH07.

Granular Fill/Fill

A Granular Fill or Fill layer was encountered beneath the asphalt at BH04, BH05, BH06, and BH07. The Granular Fill/Fill layer extended to depth ranging from 2.3 m to 5.7 m below the existing ground surface. The composition of the Fill is variable, but may generally be described as greyish-brown or dark grey to black gravelly Sand with some silt and occasional cobbles and boulders. Note that a 200 mm to 500 mm thick Class A and Class B granular layer was encountered in BH04, BH05, and BH06.



Based on N-values ranging from five to 42, encountered during the performance of Standard Penetration Tests, the Fill may be classified as loose to dense in terms of relative density

Tilll

A Till layer was encountered beneath the Fill in BH04, BH05, BH06, and BH07, at depths ranging from 2.3 m to 5.7 m below the existing ground surface, extending to depths ranging from 2.9 m to 8.4 m below the existing ground surface. The composition of the Till is variable, but may generally be described as brownish-grey to grey gravelly Sand, to a Sand and Gravel, with traces to some silt and occasional cobbles and boulders.

Based on N-values greater than 50, encountered during the performance of Standard Penetration Tests, the Till may be classified as very dense in terms of relative density.

Bedrock

Bedrock was encountered beneath the Till layer at BH04, BH05, BH06, and BH07 at depths ranging from 2.9 m to 8.4 m below the existing ground surface. Boreholes were terminated in the bedrock at depths ranging from 6.0 m to 10.3 m below the existing ground surface.

Bedrock is variable, but may be described as a medium grey sandstone. Rock quality designations (RQD) of retrieved core samples ranged from zero to 76, and on this basis, the bedrock may be classified as very-severely-fractured to fractured. Note that the RQD encountered in BH04, BH05, and BH07 was generally zero, a very-severely-fractured bedrock.

Published geology for the area indicates the bedrock consists of thin lenticular-bedded, dark grey sandstone and minor shale of the Renews Head Formation, St. John's Group.

2.0 DISCUSSION AND RECOMMENDATIONS

The following comments are provided relative to geotechnical aspects of design and construction for the proposed new parking garage/condominium building. It is understood that the proposed structure is intended to be of slab-on-grade construction, with conventional concrete strip footings, column footings, and foundation walls.

2.1 Site Development

Recommendations for site development within the proposed structure footprint, from a geotechnical viewpoint, were presented in the report, Geotechnical Sub-Surface



Investigation, Proposed Parking Garage, Duckworth at Bell Street, St. John's, NL, final report dated February 14, 2011, and will not be further discussed in this submission.

2.2 Building Foundations

Bearing Capacity of Footings

Bedrock encountered at the site, in general, is classified as very-severely-fractured to severely-fractured in terms of rock quality. Based on the bedrock quality, bedrock removal using a hydraulic rock buster may be achieved at the site. Bedrock quality typically encountered in the upper 1.6 m to 3.1 m is considered very-severely-fractured, becoming more sound with depth.

Exp is recommending that all building foundations be founded on bedrock with an RQD >30. For foundations placed on competent bedrock, design loads may be based on a net allowable bearing pressure of 800 kPa. Note that the recommended allowable bearing capacity of 800 kPa is conservative for competent bedrock. Higher bearing capacity values for competent bedrock could be discussed, if required, during detailed structural design. For fractured bedrock, design loads may be based on a net allowable bearing pressure of 400 kPa.

Foundation Preparation

Prior to placement of footings, excavation and removal of Fill, Till, and very-severelyfractured bedrock to required founding elevation, is required.

Floor slabs placed on structural blast-rock fill, compacted as previously outlined, should be cast on a free-draining layer of Department of Transportation and Works Class "A" aggregate at least 125 mm thick. The Class "A" should be compacted to 98 percent of the aggregate's Standard Proctor dry density.

Groundwater/drainage recommendations are presented in the report, Geotechnical Sub-Surface Investigation, Proposed Parking Garage, Duckworth at Bell Street, St. John's, NL, final report dated February 14, 2011, and the letter-form report, Geotechnical Sub-Surface Investigation, Proposed Parking Garage, Duckworth at Bell Street, St. John's, NL, letter-form report dated February 14, 2011, and will not be discussed further in this submission.

It is recommended that founding levels be inspected by a qualified geotechnical engineer/technologist prior to placement of footings, and during sub-slab placement of structural fill and/or blast-rock fill where required, to ensure that specified bearing capacities have been attained.



2.3 Geotechnical Parameters for Design

The recommended geotechnical parameters for design of foundations acting as retaining walls, as provided in the February 2011 geotechnical report, are summarized below in *Table 2: Recommended Geotechnical Parameters*. It should be noted that the following earth pressure coefficients are based on an assumed horizontal engineered backfill, placed and compacted in accordance with the recommendations of the previously submitted report. If inclined backfill or a different type of backfill is to be placed behind walls, the geotechnical engineer should be consulted for the appropriate earth pressure coefficients for design.

Table 2: RECOMMENDED GEOTECHNICAL PARAMETERS Proposed Parking Garage and Condominiums - Duckworth Street at Bell Street St. John's, Newfoundland and Labrador									
Parameter	Compacted Engineered Fill								
Total Unit Weight, kN/m ³	20.5								
Buoyant Unit Weight, kN/m ³	10.5								
Effective Friction Angle, degrees	36°								
Coefficient of Active Earth Pressure, K _a	0.26								
Coefficient of Passive Earth Pressure, K_p	3.8								
Coefficient of Earth Pressure at Rest, $K_{\mbox{\scriptsize o}}$	0.41								

The recommended geotechnical parameters for design of foundations acting as retaining walls for severely-fractured bedrock situations are summarized below in *Table 3: Recommended Geotechnical Parameters*. It should be noted that the following earth pressure coefficients are based on an assumed horizontal engineered backfill, placed and compacted in accordance with the recommendations of the previously-submitted report. Backfill material should consist of a well-graded, angular material with low percentage of fines (maximum 2 percent), such as a 4" minus blast rock. If inclined backfill or a different type of backfill is to be placed behind walls, the geotechnical engineer should be consulted for the appropriate earth pressure coefficients for design.



Table 3: RECOMMENDED GEOTECHNICAL PARAMETERS

Proposed Parking Garage and Condominiums - Duckworth Street at Bell Street St. John's, Newfoundland and Labrador

	Severely Fractured Bedrock
Total Unit Weight, kN/m ³	24.5
Buoyant Unit Weight, kN/m ³	14.5
Effective Friction Angle, degrees	38°
Coefficient of Active Earth Pressure, K _a	0.24
Coefficient of Passive Earth Pressure, K _p	4.20
Coefficient of Earth Pressure at Rest, K _o	0.38

The following parameters may be used for concrete on sound bedrock interface:

- interface friction angle 35°
- friction factor 0.7
- geotechnical resistance factor, sliding 0.8.

2.4 Site Classification for Seismic Site Response

In general, the ground profile at the site within the top 30 m may be considered as rock. Based on this, and per the requirements of the 2010 National Building Code of Canada (NBC 2010), the site classification for seismic site response, per Table 4.1.8.4.A of NBC 2010, Division B, Part 4, Structural Design, the site may be considered a Class "B" site classification.

3.0 CLOSURE

A subsurface investigation is a limited sampling of conditions at a particular site. Should conditions be encountered which differ from those described in this report, we require immediate notification in order to permit a re-evaluation of our recommendations.



We trust this submission meets your current requirements. Should you have any questions or require clarification on any aspect of this report, please do not hesitate to contact our office.

Yours very truly,

exp Services Inc.

William G. Melendy, M.A.Sc., P.Eng. Group Manager, Geotechnical/Environmental Engineering

WGM:dgn


Attachments: Figure 1: Borehole and Test Pit Location Plan

Symbols and Terms Used on Borehole, Test Pit and Monitor Well Records

Borehole Records (4)

Geotechnical Sub-Surface Investigation, Proposed Parking Garage, Duckworth at Bell Street, St. John's, NL, final report dated February 14, 2011, prepared by ADI Limited

Geotechnical Sub-Surface Investigation, Proposed Parking Garage, Duckworth at Bell Street, St. John's, NL, letter-form report dated February 14, 2011, prepared by ADI Limited





O:/#new/#March April May/SJN-00021594-A0/Letter Report August 16, 2011



ATTACHMENTS

Figure 1: Borehole and Test Pit Location Plan





ADI Limited (C) 2011

Symbols and Terms Used on the Borehole, Test Pit and Monitor Well Records



SYMBOLS AND TERMS USED ON THE BOREHOLE, TEST PIT, AND MONITOR WELL RECORDS

SOIL DESCRIPTION

Behavioural properties (i.e. plasticity, permeability) take precedence over particle gradation in describing soils.

Terminology describing soil structure:

Desiccated	-	having visible signs of weathering by oxidation clay minerals, shrinkage, cracks, etc.
Fissured	-	having cracks, and hence a blocky structure
Varved	-	composed of regular alternating layers of silt and clay
Stratified	-	composed of alternating layers of different soil types, e.g. silt and sand or silt and clay
Well-graded	-	having wide range in grain sizes and substantial amounts of all intermediate particle sizes
Uniformly-graded	-	predominantly of one grain size.

Terminology used for describing soil strata based upon proportion of individual particle sizes present:

Trace, or occasional	-	less than 10%
Some	-	10% to 20%
Adjective (e.g. silty or sandy)	-	20% to 35%
And (e.g. silt and sand)	-	35% to 50%

The standard terminology to describe cohesionless soils include the relative density, as determined by laboratory test or by the Standard Penetration Test N-value: the number of blows of 140 pound (64 kg) hammer falling 30 inches (760 mm), required to drive a 2-inch (50.8 mm) O.D. split-spoon sampler 1 foot (305 mm) into the soil. On the records, where complete sampler penetration is not achieved and an N-value cannot be reported, the total number of blows are shown over actual penetration in millimetres (eg. 75/180).

Relative Density	N-value	Relative Density %
Very Loose	<4	<15
Loose	4 - 10	15 - 35
Compact	10 - 30	35 - 65
Dense	30 - 50	65 - 85
Very Dense	>50	>85

The standard terminology to describe cohesive soils include the consistency, which is based on undrained shear strength as measured by in situ vane tests, penetrometer tests, unconfined compression tests, or occasionally by Standard Penetration Tests.

Consistency	Undrained S	N-value	
Consistency	Kips/sq.ft.	kPa	IN-Value
Very Soft	< 0.25	< 12.5	< 2
Soft	0.25 to 0.5	12.5 to 25	2 to 4
Firm	0.5 to 1.0	25 to 50	4 to 8
Stiff	1.0 to 2.0	50 to 100	8 to 15
Very Stiff	2.0 to 4.0	100 to 200	15 to 30
Hard	> 4.0	> 200	> 30

SAMPLES

- SS Split-spoon sample (obtained by performing the Standard Penetration Test)
- AS Auger sample
- ST Shelby tube or thin-wall tube
- PS Piston sample

WS	Wash sample
RC	Rock core
	AXT, BXL, etc.

Bulk sample

Rock core samples obtained with the use of standard diamond drilling bits.

OTHER TESTS

- G Specific Gravity
- H Hydrometer Analysis
- S Sieve Analysis
- MC Moisture Content
- y Unit Weight
- C Consolidation
- CD Consolidated drained triaxial
- CU Consolidated undrained triaxial with pore pressure measurements
- UU Unconsolidated undrained triaxial
- RCC Rock Core Compression

BK

- DS Direct Shear
 - P Field Permeability
 - TPH Total Petroleum Hydrocarbons (ppm)
 - ND Below Detection Limit

ROCK DESCRIPTION

The description of rock is based on the rock quality designation (RQD).


The classification is based on a modified core recovery percentage in which all pieces of sound core over 100 mm long are counted as recovery. The smaller pieces are considered to be due to close shearing, jointing, faulting, or weathering in the rock mass and are not counted. In most cases, RQD is run on NXL core; however, it can be used on different core sizes if the bulk of the fractures caused by drilling stresses are easily distinguishable from normal in situ fractures.

RQD	Rock Quality
90 to 100	excellent quality
75 to 90	good quality
50 to 75	fair quality
25 to 50	poor quality
< 25	very poor quality


CLASSIFICATION OF ROCK WITH REGARD TO STRENGTH

S	RENGTH		
Grade	Classification	FIELD IDENTIFICATION METHOD	COMPRESSIVE STRENGTH (MPa)
RO	Extremely weak	Indented by thumbnail	<1
R1	Very weak	Crumbles under firm blows of geological hammer; can be peeled with a pocket-knife	1 - 5
R2	Weak rock	Can be peeled by a pocket-knife with difficulty; shallow indentations made by a firm blow with point of geological hammer	5 - 25
R3	Medium strong	Cannot be scraped or peeled with a pocket-knife; specimen can be fractured with a single firm blow of geological hammer	25 - 50
R4	Strong	Specimen requires more than one blow of geological hammer to fracture	50 - 100
R5	Very strong	Specimen requires many blows of geological hammer to fracture	100 - 250
R6	Extremely strong	Specimen can be chipped by geological hammer	> 250

STRATA PLOT



WATER LEVEL MEASUREMENT



WELL CONSTRUCTION



Flush-mounted Well-head Enclosure



End/Top Cap



Slotted



Bentonite



Cave-in

Borehole Records (4)

		exp	Э.	E	BOF	۶E	HOL	E F	RECO	ORD												
		JENT _		elopment Ltd.												PRO.	JECT	No. Ş	<u>SJN-2</u>	2159	94-A	<u>.0</u>
			Proposed Parkin		orth S												EHOI			<u>BH</u>		_
ŀ	D/	ATES (dd-	mm-yy): BORING _	07-07-11			VATEF I)7-07-	11					UM .		<u>Geo</u>	letic		
ĺ	(r	_			5	ÆL		- 5	SAMPL	ES			ι	Jndr 20			ar Stro 40		kPa 0	,	30	
	H (n	(B)	DESCR	UPTION	A PL	LE		R	ŝRΥ	Be.	22										4	
	DEPTH (m)	ELEV. (m)	DESCR		STRATA PLOT	WATER LEVEL	TYPE	NUMBER	RECOVERY	N-VALUE OR RQD	OTHER						erberg Test,		,	[₩] р	₩ ' ⊖ ★	₩ı ⊣
-		, ,				-			<u> </u>								Test, I				•)
ł	0 -	25.09 25.0 24.8	ר ASPHALT:						mm				10 = [] :	20	3	0	40 5	50 <u>6</u> ::::		0 8	80 : : :	<u>90</u> 구
	-	$\underline{-24.8}$	<u> GRANULAR FI</u>	LL: Loose	1		SS	01	355	25												E
-	1		brownish grey GF SAND; trace silt (Class "A") and s	[Granular base ub-base (Class																		
-	1		["B") materials]; n FILL: Compact																			Ē
ł	2		brown to brownis	h grey gravelly			SS	02	305	25												
	-		SAND; some silt; cobbles and bould	lers; moist.																		E
	3																					
ſ	3						SS	03	430	42	MC, S			6								
F							55	05		74	S			Ĭ								E
F	4																					
ļ	-									-												
	5 -						RC	04	305	28					٠							-
								<u> </u>														
ľ		19.4	TILL: Very dens	se brownich grey	×																	E
ŀ	6		to grey SAND and	d GRAVEL; trace																		F
ł		18.4	silt; cobbles and t	oulders; moist.			SS	05	355	123	MC, S		þ								>>	ŧ.
ļ	7		BEDROCK: Ve fractured SANDS				RC	06	100%	0												
╞	-		mud seams.		E																	
-	8						RC	07	39%	13												E
	-				E																	
							RC	08	0%	0												
ſ	9																					E
ł					臣																	E
Ę	10 =	14.8																				
20/7/		1.4.0	End of H	Borehole																		E
	11		NOTES: 1) Bedrock encour	ntered at 6.7 m																		E
PJ AI	11		dépth.																			E
1594.0	1																					
GEOTECH 00021594.GPJ ADI.GDT 20/7/11	12 <u>1</u>	[^] ex	exp Services In		Te	chno	ologist:	B. Ca	meron	}	<u> </u>	····	<u>ះះ</u> ហ	:: : 1001	::: fined	l Con	npress.	[: : : :] ion Te	st ::::	::::	1:::	: [-
OTECI	•	EX	O. 60 Pippy Place, St. John's, NL, A	A1B 4H7		ontra	clor: Lo	ogan C	Melendy Seolech I			Ŧ	W	ater	Leve	el at T	Cime o			cava	lion	
۳ <u></u>			I Tel 709.579.20	27 Fax 709.579.7115	Ec	luipn	nent: C	ME-5.	5			Ē				er Lev Test		1	lemoi	ilded		

DATES (III) HI AGO HI AGO III) HI AGO III III III III III III III III III I	IONP (dd-mm-yy (dd-mm-yy 71 5.6 <u>AS</u> 5.1 Bro SA (Cl (Cl ("B" FII	enry Bell Development Ltd. roposed Parking Garage - Ducky DESCRIPTION PHALT: ANULAR FILL: Compact wnish grey GRAVEL and ND; trace silt [Granular base ass "A") and sub-base (Class			WATER	R LEV	EL	<u>0</u> ES	6-07-			_	BOR DAT ed She	EHOL UM	E No.	Geod	BH (letic	
DATES (III) HLABQ 0 25 - 0 27 - 1	(dd-mm-yy 71 5.1 5.1 5.1 5.1 5.1 5.1 5.1 5.1 5.1 5.	DESCRIPTION DESCRIPTION PHALT: ANULAR FILL: Compact wnish grey GRAVEL and ND; trace silt [Granular base			WATE	r lev S	EL	<u>0</u> ES	6-07-			draine	DAT ed She	UM ar Stre	ength, l	Geoc kPa	letic	
- 0 <u>25.</u> - <u>2</u> : - 1	71 5.1 5.1 5.1 5.1 5.1 5.1 5.1 5.	PHALT: ANULAR FILL: Compact wnish grey GRAVEL and ND; trace silt [Granular base	ž l	STRATA PLOT	TYPE												8	:0
- 0 <u>25.</u> - <u>2</u> : - 1	71 5.1 5.1 5.1 5.1 5.1 5.1 5.1 5.	PHALT: ANULAR FILL: Compact wnish grey GRAVEL and ND; trace silt [Granular base	Ĩ	STRATA PLC	TYPE	MBER	ERY	Ро				20		40	6	0	8	so
- 0 <u>25.</u> - <u>2</u> : - 1	71 5.1 5.1 5.1 5.1 5.1 5.1 5.1 5.	PHALT: ANULAR FILL: Compact wnish grey GRAVEL and ND; trace silt [Granular base	Ĩ	STRATA	TYPE	MBE	ΙШ		N			•		•				Ĩ
- 1	$ \begin{array}{c} 5.6\\ 5.1\\ \hline GR\\ 5.1\\ \hline GR$	ANULAR FILL: Compact wnish grey GRAVEL and ND; trace silt [Granular base	Ĩ			5	RECOVERY	N-VALUE OR RQD	OTHER TESTS	Dyn	amic	Penel	ration	Tesł,	Limits blows/ blows/	s 10.3m	Np I	w w _l ⊖
- 1 -	5.1 GR bro SA (Cl "B" FII	ANULAR FILL: Compact wnish grey GRAVEL and ND; trace silt [Granular base	j 🕅				nun								i0 6		0 8	0 90
	bro SA (Cl "B"	wnish grey GRAVEL and ND; trace silt [Granular base		\otimes		0.1	0.00											
- 1 - 2 - 2 - 2 - 2 - 2 - 2 - 2 - 2 - 2		ND; trace silt [Granular base	! Å		SS	01	250	12										
- 2	\"B" <u>FII</u>	a_{00} is function -0 and $(-1$ and -0 and $(-1$ and -0 and $(-1$ and -0 and $(-1$ and -0 and (-1) and $(-$	Į₿	8														
- 2	<u>F11</u> grey) materials]; moist.	Ι₿	്∷														Ē
	6.0	L: Loose to compact dark to black to brown gravelly	×	▓.	SS	02	200	9										Ē
	SAI cob	ND; some silt; occasional bles and boulders; moist.	Ŕ	\bigotimes														Ē
		,	Ŕ	8														Ē
	2.6	L: Dense to very dense wnish grey to grey gravelly		\mathbb{X}	SS	03	430	35					٠					
- 4	SA and	ND; some silt; some cobbles boulders - frequency decreasing			RC	04	50%	0										
	with	n depth; moist.			RC	05	50%	0										
- 5 -					RC	05	50%	0										
			L.						MC,									Ē
				9 4	SS	07	455	201	SÍ									
- 6 -			•		1													
7			ŗ		SS	08	250	111/										<u>>></u>
			ŀ					75										
																		E
8 -	.3																	
		DROCK: Very severely tured SANDSTONE.	-		SS RC	09	0 100%	73/ 25										Ē
- 9 -	Irac	lured SAINDSTONE.	Н					0			<u></u>						:::: :::::	<u></u>
			Б		RC	11	100%	0										E
10 15	.6		Þ		RC	12	100%	0										Ē
		End of Borehole	T	1														
		TES: Bedrock encountered at 8.4 m																Ē
	dept	h.							l									
					1													
																		Ē
	Xp.	exp Services Inc. 60 Pippy Place, Suite 200 St. John's, NL, A1B 4H7		Revie	nologist: wed By:	B. Cai Wm. I	neron			Δ	Unco	nfine	d Con	pressi	on Tee	t		
		Tel 709.579.2027 Fax 709.579.7115					vielendy ieolech li			_					f Drilli		cavali	ัดท

		[*] exp	D.	B	BOF	RE	HOL	.E F	RECC	ORD						
	C	LIENT _	Henry Bell Development			4			funct D	6 Tal	α λ Π		PROJECT N)
			Proposed Parking Garage	<u>- Duckwo</u> 07-11	<u>ortn 8</u>		<u>et at B</u> VATEF				<u>s, nl</u> <u>5-07-</u>		BOREHOLE	NO		-
	2				5	ÆL	-	S	AMPL	ES		Undraine 20	d Shear Streng 40	gth, kPa 60	80	
	DEPTH (m)	ELEV. (m)	DESCRIPTION		STRATA PLOT	WATER LEVEL	ц	BER	/ERY	58	E E E E E E E E E E E E E E E E E E E				w _p w w	4
	DEP	ELEV			STRA	WATE	TYPE	NUMBER	RECOVERY	N-VALUE OR RQD	OTHER TESTS	Water Content Dynamic Penet	ration Test, bl	ows/0.3m		ť
ĺ	- 0 -	26.68						-	mm			Standard Peneti 10 20 2			• 0 80 9	ю
		<u>26.6</u> 26.2	ASPHALT: GRANULAR FILL: Co	mpact,			SS	01	200	17						E
	1		brownish grey GRAVEL at SAND; trace silt [Granular	nd i base i												
			(Class "A") and sub-base ("B") materials]; moist.	Class {												
	2 -		FILL: Compact to dense a brown to brownish grey gra	ivelly			SS	02	510	47						-
			SAND; some silt; occasion cobbles and boulders; mois	al st.												
-	3	23.5							0.05	1.50	MC,					Ē
		22.9	TILL: Very dense browni to grey gravelly SAND; sor	ne silt;	; ; ; ; ;		SS	03	305	153	S	ι.				
	4 -	22.9	occasional cobbles and bou				RC	04	100%	0						-
ŀ	· _		BEDROCK: Very severel fractured to fractured SANDSTONE.	IJ	E											Ē
	5		SHUDDIONE.		臣		RC	05	100%	45						E
-					F											
ļ	6 -				E											
Ī					E		RC	06	100%	76						
Ī	7 -	19.3														
	0		End of Borehole NOTES:	7.0												-
	8		1) Bedrock encountered at 3 depth.	5.8 m												Ē
	9							:								-
	, , ,															
	10															-
20/7/11																E
ADI.GDT	11															E
94.GPJ																
000215	12		exp Services Inc.		 Te	chn/	ologist:	B, Ca	meron			△ Unconfine	d Compression	1 Teet		F
GEOTECH 00021594.GPJ ADI.GDT 20/7/11	•	[#] ex	 60 Pippy Place, Suite 200 St. John's, NL, A1B 4H7 Tel 709.579.2027 Fax 709 	579.7115	Re Co	eview ontra	/ed By:	Wm. xgan G	Melendy Seotech				el at Time of 2		xcavation	
۳ſ							ion. U	-01				Field Van		Remo	ulded	

	.	[*] ex	О. Е	BOF	RE	HOL	E F	RECO	ORD										
	С	LIENT	Henry Bell Development Ltd.		C4.		D-11	Sture at	C4 T-1		17								<u>4-A0</u>
			Proposed Parking Garage - Duckw mm-yy): BORING 08-07-11	<u>orun</u>		WATEI				<u>m s, r</u> 8-07-			_		eehoi Tum		Geo		<u>)/</u>
	(Ŀ	E		5	SAMPL	ES			U		ied Sh	ear Str	ength,	kPa	-	
	I (m	E (E)	DEGODIDUCU	STRATA PLOT	WATER LEVEL		R	RY	ËО				20		40		50 	8	0
	DEPTH (m)	DESCRIPTION				TYPE	NUMBER	RECOVERY	N-VALUE OR RQD	OTHER TESTS	Dy	mami	c Pene	etratio	terberg n Test, n Test,	blows	ts :/0.3m		w w₁ ∋ I ●
	- 0 -	19.94						mm				10						0 8	0 90
	Ĵ	<u> </u>	ASPHALT: FILL: Compact to loose grevish		§	SS	01	75	29										Ē
	- 1 -		FILL: Compact to loose greyish brown to brownish grey gravelly SAND; some silt; occasional																
			cobbles and boulders; moist.			SS	02	75	5		•								
	- 2 -	17.6																	
		17.0	<u>TILL</u>: Very dense brownish grey to grey gravelly SAND; some silt; occasional cobbles and boulders;																
	- 3 -	17.0	\moist.			SS RC	03 04	<u>125</u> 50%	65/ 125										· · · · · · · · · · · · · · · · · · ·
ĺ			BEDROCK: Very severely fractured SANDSTONE; some			RC	05	50%											
Ī	- 4 -		mud seams.			RC	06	50%	0										
ľ	- 5 -			Ħ		RC	07	50%	0										
	· 6 -	13.9																	
	0		End of Borehole NOTES:																
	· 7 -		1) Bedrock encountered at 2.9 m depth.																
	· · ·																		
	8																		
						i													
	9																		
	· · ·																		
	10-																		
16/8/11	. v.									r									
DI.GDT	11																		
GEOTECH 00021594.GPJ ADI.GDT 16/8/11																			
3021594	12	_																	
ECH O		*ex	O. exp Services Inc. 60 Pippy Place, Suite 200 St. John's, NL, A1B 4H7	Re	viev	ved By:	:Wm.	ameron Melendy	y Inc		∆ ¥				mpress Fime o			cavat	ion
GEOT			Tel 709.579.2027 Fax 709.579.7115	Eq	uipr	nent: C	ME-5	Geotech 5	INC.		Ā	Sta	tic Wa	iter Le	vel				
												Fie	d Van	e Test		I I	Remou	Ided	

ADI Limited Final Report:

Geotechnical Sub-surface Investigation Proposed parking Garage Duckworth at Bell Street St. John's, Newfoundland and Labrador Date: February 14, 2011

Final Report: GEOTECHNICAL SUB-SURFACE INVESTIGATION *PROPOSED PARKING GARAGE* DUCKWORTH STREET AT BELL STREET ST. JOHN'S, NEWFOUNDLAND AND LABRADOR Prepared for: Henry Bell Development Ltd.

ADI LIMITED

FILE: 27-6628-001.1 DATE: February 2011



February 14, 2011

Air File 27-6628-001.1

ADI Limited A Trow Global Company

> Henry Bell Development Ltd. 12 Caldwell Place St. John's, Newfoundland and Labrador A1E 6A4

Engineering Consulting Procurement Project Management

Architecture

Attention: Mr. William Clarke

RE:

Dear Sirs:

Enclosed are three copies of our final report containing the findings of our geotechnical sub-surface investigation at the above-noted site, for your perusal.

Geotechnical Sub-surface Investigation

St. John's, Newfoundland and Labrador

Proposed Parking Garage

Duckworth Street at Bell Street

We trust this submission meets your current requirements, and thank you for the opportunity of providing our services.

Yours very truly,

ADI Limited

Blain Domen

Blair D. Cameron, P.Tech. Sr. Geo-Enviromental Tech.

BDC/WGM:dgn

William G. Melendy, M.A.Sc., P.Eng. Group Manager, Geotechnical/Environmental Engineering

60 Pippy Place Suite 200 St. John's, NL A1B 4H7 Canada Telephone: 709.579.2027 Fax: 709.579.7115 Email: nfld@adi.ca

Enclosure: Report in triplicate

www.adilimited.ca

o:/#Project Files/#Client 6601 to 7000/6628/66280011/Reports/Final Geotechnical Report Feb'11

Disclaimer Statement

This report was prepared by *ADI Limited* for the account of HENRY BELL DEVELOPMENTLTD. Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. *ADI Limited* accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.

TABLE OF CONTENTS

1.0 INTRODUCTION 1 SITE DESCRIPTION 2.0 1 3.0 FIELD PROGRAMME 1 3.1 Organics 4 3.2 Asphalt 4 3.3 Granular Fill 4 3.4 Fill 4 3.5 Sand and Gravel 5 3.6 Till 5 Bedrock 3.7 6 Groundwater 3.8 6 4.0 DISCUSSION AND RECOMMENDATIONS 6 4.1 Site Development 6 **Building Foundations** 4.2 8 Geotechnical Parameters for Design 4.3 10 Site Classification for Seismic Site Response 4.4 11 Parking and Drive-Lanes 4.5 11 5.0 CLOSURE 11 FIGURE Test Pit Location Plan 1 2 TABLES 1 Summary of Test Pit Data 3 2 **Recommended Geotechnical Parameters** 10

APPENDIX Symbols and Terms Used on the Borehole, Test Pit, and Monitor Well Records Test Pit Records Gradation Curves

	ADI Quality S	System Checks		
Project No.:	27-6628-001.1	Date:	2011 02 14	[yr/mo/da]
Issue Status:	Final Report	Revision No.:	0	
Prepared by:	Blair D. Cameron, P.Tech. William G. Melendy, M.A.Sc., P.Eng.	blainsla	muer	[Signature]
Reviewed by:	William G. Melendy, M.A.Sc., P.Eng.		105	[Signature]

Page No.

Page 1

1.0 INTRODUCTION

Further to your request, *ADI Limited* has completed a geotechnical sub-surface investigation for a proposed parking garage located on Duckworth Street at Bell Street in St. John's, Newfoundland and Labrador. The intent of the investigation was to confirm soil conditions in the area of the proposed parking garage, and provide recommendations.

2.0 SITE DESCRIPTION

The proposed parking garage is to be located on the northern side of Duckworth Street at Bell Street, in St. John's, Newfoundland and Labrador. The property along the area of the proposed parking garage consists of Bell Street, along with several paved parking and landscaped areas. We understand that Bell Street is to be re-aligned to accommodate the proposed parking garage. Access to the site is via Duckworth Street from the south and Henry Street from the north. Site topography is generally sloping from north to south. The area is provided water and sewer services by the City of St. John's.

We understand that the proposed project will consist of slab-on-grade construction with conventional strip and column footings.


3.0 FIELD PROGRAMME

Field work was completed on May 29, 2010 and comprised the mechanical excavation of 13 test pits (TP), advanced using a *Cat 420E IT* extend-a-hoe operated by *Roley Construction Limited* of St. John's, Newfoundland and Labrador. The test pits were located in the field by *ADI Limited* through discussions with Mr. Richard Cooke of *RJC Services* and Mr. William Clarke of *Henry Bell Development Ltd*. Final test pit locations are shown on *Figure 1: Test Pit Location Plan*.

The test pits generally penetrated an organic or asphalt layer and a fill and till deposit. Bedrock was encountered at all 13 test pit locations. Groundwater was not encountered at any of the test pit locations.



(27) 6628-001.1



PLOTTED 5 USER DATE

Conditions encountered in test pits are described below and on Test Pit Records in the Appendix. *Table 1: Summary of Test Pit Data*, presents the summarized findings of the investigation.

		St. J	Duckworth St ohn's, Newfou				
Test Pit No.	Elevation	Bottom of Organic/Asphalt Layer Elevation	Top/Bottom of Fill Elevation	Top of Sand and Gravel/ Till Elevation	Top of Probable Bedrock Elevation	End of Test Pit Elevation	Ground- Water Elevation
	(m)	(m)	(m)	(m)	(m)	(m)	(m)
01	15.78	15.7	15.7 / 14.2	N/E	14.2 - 14.5	14.2	N/E
02	16.42	16.4(1)	16.4 / 15.3	N/E	15.3	15.2	N/E
03	16.52	16.5 ⁽¹⁾	16.5 / 13.7	N/E	13.7	13.7	N/E
04	23.31	22.9	22.9 / 22.4	22.4	20.8	20.8	N/E
05	18.14	17.9	N/E	N/E	17.9	17.9	N/E
06	18.83	18.7	18.7 / 15.9	N/E	15.9	15.9	N/E
07	18.63	18.6(1)	18.6 / 16.6	16,6	14.9	14.9	N/E
08	23.98	N/E	24.0 / 23.0	23.0	21.0	21.0	N/E
09	20.28	N/E	20.3 / 20.1	N/E	20.1	19.8	N/E
10	20.21	20.0	20.0 / 17.6	17.6	16.7	16.7	N/E
11	21.14	21.1 ⁽¹⁾	21.1 / 19.5	19.5	19.2	19.2	N/E
12	22.25	22.1	22.1 / 21.1	21.1	17.8	17.8	N/E
13	21.55	21.4	21.4/21.1	21.1	19.2 - 20.0	19.2	N/E

⁽¹⁾ - Asphalt surface



(27) 6628-001.1

3.1 Organics

A 100 mm to 400 mm thick Organic (grassmat) layer was encountered at ground surface in test pits TP01, TP04, TP05, TP06, TP10, and TP13.

3.2 Asphalt

A 30 mm to 70 mm thick Asphalt layer was encountered at ground surface in test pits TP02, TP03, TP07, and TP11.

3.3 Granular Fill

A 0.35 m to 0.45 m thick Granular Fill layer was encountered beneath the asphalt layer in TP02, TP03, TP07, and TP11. The granular fill extended to depths ranging from 0.4 m to 0.5 m below the existing ground surface. The composition of the Granular Fill is variable, but may generally be described as brownish-grey Gravel and Sand with traces of silt (granular sub-base and base - Class "B" and Class "A" materials).

Based on observation of the backhoe performance, the Granular Fill material is classified as loose at all test pit locations in terms of relative density.

3.4 Fill

A Fill layer ranging in thickness ranging from 0.2 m to 2.75 m was encountered at ground surface in TP08 and TP09; beneath the Organic layer in TP01, TP04, TP06, TP10, TP12, and TP13; and beneath the Granular Fill in TP02, TP03, TP07, and TP11. The Fill layer terminated on bedrock at depths ranging from 0.2 m to 2.9 m below the existing ground surface in TP01, TP02, TP03, TP06, and TP09. The Fill layer extended to depths ranging from 0.5 m to 2.6 m below the existing ground surface in TP04, TP07, TP08, TP10, TP11, TP12, and TP13. The composition of the Fill is variable, but may generally be described as a greyish-brown to brownish-grey Gravel and Sand with traces of silt and occasional to some cobbles and boulders. Some organics (roots and rootlets) were encountered in TP01, TP04, and TP08. Some debris (pieces of bricks, metal, concrete, rags, steel rods, wood, bottles, and old telephone cables) were encountered in the 12 test pits where Fill



was encountered except TP11, TP12, and TP13. It should be noted that a 0.6 m and 0.2 m thick layer of rock fill was intermixed with Gravel and Sand on the surface of the Fill layer in TP10 and TP11, respectively.

Based on observation of the backhoe performance, the Fill is classified as loose to compact in terms of relative density.

3.5 Sand and Gravel

A 0.7 m thick Sand and Gravel layer was encountered beneath the Fill layer in TP12 at a depth of 1.2 m below the existing ground surface. The composition of the Sand and Gravel is variable, but may generally be described as a tannish-brown Sand and Gravel with traces of silt, and occasional cobbles and boulders.

Based on observation of backhoe performance, the Sand and Gravel is classified as compact in terms of relative density.

3.6 Till

A Till layer was encountered beneath the Fill layer in TP04, TP07, TP08, TP10, TP11, and TP13 at depths ranging from 0.5 m to 2.6 m below the existing ground surface, and beneath the Sand and Gravel layer in TP12 at a depth of 1.9 below the existing ground surface. The Till layer extended to depths ranging from 1.9 m to 4.5 m below the existing ground surface. The composition of the Till layer is variable, but may generally be described as a brownish-grey to grey Sand and Gravel to Gravel and Sand; with traces of silt and occasional to some cobbles and boulders.

Particle size analyses was completed on four representative sample of the Till deposit, with the following results:

Gravel:	40.4 percent to 61.6 percent	(average:	50.5 percent)
Sand:	32.9 percent to 51.3 percent	(average:	41.8 percent)
Silt:	5.5 percent to 8.5 percent	(average:	7.7 percent).



February 2011 Final Report

Page 6

The natural moisture content of the Till samples tested ranged from 5.3 percent to 7.9 percent, with an average natural moisture of 6.5 percent.

Based on observation of the backhoe performance, the Till is classified as compact to dense at TP04, TP08, TP10, and TP11 and as compact to very dense at TP07, TP12, and TP13 in terms of relative density.

3.7 Bedrock

Bedrock was encountered in all 13 test pit locations. All test pits were terminated in Bedrock at depths ranging from 0.2 m to 4.5 m below the existing ground surface. Based on published geology for the area, Bedrock consists of thin, lenticular-bedded, dark grey sandstone and minor shale of the Renews Head Formation, St. John's Group (A.F. King, Map 90-120).

3.8 Groundwater

Groundwater was not encountered at any of the 13 test pit locations. It is noted that the groundwater table may generally be expected to fluctuate seasonally and in response to extended heavy rainfall events.

4.0 DISCUSSION AND RECOMMENDATIONS

The following comments are provided relative to geotechnical aspects of design and construction for the proposed new structure and parking areas. It is understood that the proposed structure is intended to be of slab-on-grade construction, with conventional concrete strip footings, column footings, and foundation walls.

4.1 Site Development

Site development within the proposed structure footprint and parking areas, from a geotechnical viewpoint, will require attention to the following aspects:



- In the areas of all exterior and interior footing construction, all Fill and native Till are to be removed to the surface of the underlaying Bedrock.
- Note that the excavated Fill is not suitable for re-use as structural fill, and may be used in landscaped areas only.
- Placement and compaction of imported pit-run fill, as/if required to attain proposed subgrade elevations, should comprise a well-graded aggregate with less than 10 percent silt content, and all particles larger than 200 mm screened off. Structural fill should be placed in maximum loose lifts of 450 mm and compacted through use of a 10- to 12-tonne vibratory roller to minimum 98 percent of the material's Standard Proctor dry density. Should space restraints prevent the use of a 10- to 12-tonne vibratory roller, loose lift thickness should be reduced to a maximum thickness of 150 mm and compacted using a heavy plate tamper such as a *BOMAG* vibrating diesel plate tamper, or equivalent, to obtain the required compaction results.
- Finish grades around the structure should be sloped to promote positive drainage away from the structure.
- Structural fill beneath floor-slab areas, where required, should be placed in loose lifts not exceeding 450 mm in thickness and compacted at optimum moisture content to 98 percent of the material's Standard Proctor dry density.
- Imported fill (where required), as previously described for structural fill, to be used in access and/or parking areas, should be placed in maximum loose lifts of 450 mm and compacted through use of a 10- to 12-tonne vibratory roller to a minimum 98 percent of the material's Standard Proctor dry density.
- We anticipate that de-watering, as may be required during construction works, can be addressed by conventional sump and pump methods, based on the groundwater conditions encountered at the time of the investigation.



• Should the use of blast-rock be selected instead of a pit-run fill, it should comprise material of 200 mm maximum particle size with less than five percent smaller than 25 mm. The rock shall be placed in loose lift thicknesses as noted for pit-run, and compacted through a minimum eight passes of a 10- to 12-tonne vibratory roller.

4.2 Building Foundations

Bearing Capacity of Footings

ADI is recommending that all building foundations be founded on bedrock. For foundations placed on competent bedrock, design loads may be based on a net allowable bearing pressure of 800 kPa. Note that the recommended allowable bearing capacity of 800 kPa is conservative for competent bedrock. Higher bearing capacity values for competent bedrock could be discussed, if required, during detailed structural design. For fractured bedrock, design loads may be based on a net allowable bearing pressure of 400 kPa.

Foundation Preparation

Prior to placement of footings, excavation and removal of Organics, Fill, Till, and Bedrock to required founding elevation is required.

Floor slabs placed on structural blast-rock fill, compacted as previously outlined in Section 4.1, should be cast on a free-draining layer of Department of Transportation and Works Class "A" aggregate at least 125 mm thick. The Class "A" should be compacted to 98 percent of the aggregate's Standard Proctor dry density.

Sieve analyses have confirmed a silt content for the native site soils ranging from 5.5 percent to 8.5 percent. Where there is a high silt content (greater than ten percent), the potential for erosion problems increases. If soil becomes soft during construction activities, the soil must be removed from the work area and replaced with structural blast-rock or suitable Fill, compacted in lifts to the satisfaction of the geotechnical engineer. Founding areas must be void of surface water and free of any loose soil prior to placement of concrete.



We anticipate that de-watering, as may be required during construction works, can be addressed by conventional sump and pump methods, based on the groundwater conditions encountered at the time of the investigation.

It is recommended that founding levels be inspected by a qualified geotechnical engineer/ technologist prior to placement of footings, and during sub-slab placement of structural fill and/or blast-rock fill where required, to ensure that specified bearing capacities have been attained.

Groundwater/Drainage Recommendations

We recommend that all perimeter walls below grade receive a water-proofing membrane and freedraining backfill be installed immediately against foundation walls.

As noted previously, groundwater was not encountered at any of the test pit locations. Project drawings dated June 12, 2010, Typical Building Section, indicate a proposed finish Level 1 floor elevation of 14.3 m. Bedrock was encountered at Elev. 21.0 m (TP08), Elev. 17.8 m (TP12), and Elev. 19.2 m (TP13), on the Henry Street side of the development. Based on this, up to approximately 6.7 m of bedrock will have to be removed to achieve the Level 1 floor slab elevation of 14.3 m. *ADI* recommends that drainage piping should be constructed immediately adjacent all perimeter footings, with positive drainage into the municipal storm system.

Given the size of the proposed structure, the removal of up to 6.7 m of bedrock, and the potential for groundwater flow from fractures in the bedrock, an under-drain system may be required beneath the slabs at the lowest levels. Typically, this would consist of a series of perforated drainage pipes placed just above the bedrock surface and backfilled with free-draining gravels. The perforated piping should be connected to a non-perforated header pipe(s) to direct the flow out of the building. This requirement should be evaluated at the time of bedrock removal at the site, taking into the groundwater conditions encountered.

If required, we recommend that PVC piping be used for drainage works and that the system be designed to ensure positive flow to the municipal storm system. A minimum slope of one percent is recommended for perimeter and under-drain piping. The invert of all sections of drainage piping should be at least 300 mm below the top of slab level. Traps should be installed for future inspection



and cleaning if required, and backwater flow valves should be installed to prevent water from entering the system from outside sources.

It is recommended that founding levels be inspected by a qualified geotechnical engineer prior to placement of footings, and during placement of structural fill and blast-rock fill, to ensure that specified bearing capacities have been attained.

4.3 Geotechnical Parameters For Design

The recommended geotechnical parameters for design of foundations acting as retaining walls are summarized below in *Table 2: Recommended Geotechnical Parameters*. It should be noted that the following earth pressure coefficients are based on an assumed horizontal engineered backfill, placed and compacted in accordance with the recommendations above. If inclined backfill or a different type of backfill is to be placed behind walls, the geotechnical engineer should be consulted for the appropriate earth pressure coefficients for design.

TABLE 2: RECOMMENDED GEOTECHNICAL PARAMETERS Proposed Parking Garage Duckworth Street at Bell Street St. John's, Newfoundland and Labrador								
Parameter	Compacted Engineered Fill							
Total Unit Weight, kN/m ³	20.5							
Buoyant Unit Weight, kN/m ³	10.5							
Effective Friction Angle, degrees	36°							
Coefficient of Active Earth Pressure, K _a	0.26							
Coefficient of Passive Earth Pressure, K _p	3.8							
Coefficient of Earth Pressure at Rest, K _o	0.41							



4.4 Site Classification for Seismic Site Response

In general, the ground profile at the site within the top 30 m may be considered as very dense soil and soft rock. Based on this, and per the requirements of the 2005 National Building Code of Canada (NBC 2005), the site classification for seismic site response, per Table 4.1.8.4.A of NBC 2005, Division B, Part 4, Structural Design, the site may be considered a Class C site classification.

4.5 Parking and Drive-Lanes

In the areas of all parking and drive-lane construction, as a minimum, the compacted Fill is to be proof-rolled and, in situations where the material becomes soft, the soft material is to be removed and replaced with imported pit-run fill or blast-rock. It is recommended that the excavated elevation be inspected by a geotechnical engineer/technologist prior to proof-rolling to confirm suitability of the sub-grade layer for proof-rolling, and to monitor the proof-rolling activities.

Structural fill, as required to attain sub-grade design elevations, should be placed on the recompacted Till only after it has been proof-rolled and re-compacted, as noted previously. Structural fill should be placed and compacted in 450 mm lifts to 98 percent of the material's Standard Proctor dry density. Materials with more than 10 percent silt and considered frost-susceptible should not be used as sub-grade structural fill.

Driving/parking surfaces for light vehicular traffic should comprise, as a minimum, a 50 mm thick asphalt course over properly-compacted base and sub-base granulars. All asphalt should be compacted to a minimum 97 percent of Marshall density. Granular sub-base (Class "B") and base (Class "A") granulars should comprise 150 mm and 100 mm, respectively, compacted to 100 percent of Standard Proctor dry density.

5.0 CLOSURE

A subsurface investigation is a limited sampling of conditions at a particular site. Should conditions be encountered which differ from those described in this report, we require immediate notification in order to permit a re-evaluation of our recommendations.

o:/#Project Files/#Client 6601 to 7000/6628/66280011/Reports/Final Geotechnical Report Feb'11



APPENDIX

.

۲

. .

•

Symbols and Terms Used on the Borehole, Test Pit, and Monitor Well Records



SYMBOLS AND TERMS USED ON THE BOREHOLE, TEST PIT, AND MONITOR WELL RECORDS

SOIL DESCRIPTION

Behavioural properties (i.e. plasticity, permeability) take precedence over particle gradation in describing soils.

Terminology describing soil structure:

Desiccated	-	having visible signs of weathering by oxidation clay minerals, shrinkage, cracks, etc.
Fissured	-	having cracks, and hence a blocky structure
Varved	-	composed of regular alternating layers of silt and clay
Stratified	-	composed of alternating layers of different soil types, e.g. silt and sand or silt and clay
Well-graded	-	having wide range in grain sizes and substantial amounts of all intermediate particle sizes
Uniformly-graded	-	predominantly of one grain size.

Terminology used for describing soil strata based upon proportion of individual particle sizes present:

-	less than 10%
-	10% to 20%
-	20% to 35%
-	35% to 50%
	-

The standard terminology to describe cohesionless soils include the relative density, as determined by laboratory test or by the Standard Penetration Test N-value: the number of blows of 140 pound (64 kg) hammer falling 30 inches (760 mm), required to drive a 2-inch (50.8 mm) O.D. split-spoon sampler 1 foot (305 mm) into the soil. On the records, where complete sampler penetration is not achieved and an N-value cannot be reported, the total number of blows are shown over actual penetration in millimetres (eg. 75/180).

Relative Density	N-value	Relative Density %
Very Loose	<4	<15
Loose	4 - 10	15 - 35
Compact	10 - 30	35 - 65
Dense	30 - 50	65 - 85
Very Dense	>50	>85

The standard terminology to describe cohesive soils include the consistency, which is based on undrained shear strength as measured by in situ vane tests, penetrometer tests, unconfined compression tests, or occasionally by Standard Penetration Tests.

	Undrained SI	N	
Consistency	Kips/sq.ft.	kPa	N-value
Very Soft	< 0.25	< 12.5	< 2
Soft	0.25 to 0.5	12.5 to 25	2 to 4
Firm	0.5 to 1.0	25 to 50	4 to 8
Stiff	1.0 to 2.0	50 to 100	8 to 15
Very Stiff	2.0 to 4.0	15 to 30	
Hard	>4.0	> 200	> 30

SAMPLES

- SS Split-spoon sample (obtained by performing the Standard Penetration Test)
- AS Auger sample
- ST Shelby tube or thin-wall tube
- PS Piston sample

OTHER TESTS

- G Specific Gravity
- H Hydrometer Analysis
- S Sieve Analysis
- MC Moisture Content
- y Unit Weight
- C Consolidation
- CD Consolidated drained triaxial

- BK Bulk sample
 WS Wash sample
 RC Rock core
 AXT, BXL, etc.
 Rock core samples obtained with the use of standard diamond drilling bits.
- CU Consolidated undrained triaxial with pore pressure measurements
- UU Unconsolidated undrained triaxial
- RCC Rock Core Compression
- DS Direct Shear
- P Field Permeability
- TPH Total Petroleum Hydrocarbons (ppm)
- ND Below Detection Limit

ROCK DESCRIPTION

The description of rock is based on the rock quality designation (RQD).


The classification is based on a modified core recovery percentage in which all pieces of sound core over 100 mm long are counted as recovery. The smaller pieces are considered to be due to close shearing, jointing, faulting, or weathering in the rock mass and are not counted. In most cases, RQD is run on NXL core; however, it can be used on different core sizes if the bulk of the fractures caused by drilling stresses are easily distinguishable from normal in situ fractures.

RQD	Rock Quality
90 to 100	excellent quality
75 to 90	good quality
50 to 75	fair quality
25 to 50	poor quality
< 25	very poor quality


CLASSIFICATION OF ROCK WITH REGARD TO STRENGTH

STRENGTH			RANGE OF UNCONFINED
Grade	Classification	FIELD IDENTIFICATION METHOD	COMPRESSIVE STRENGTH (MPa)
ŖO	Extremely weak	Indented by thumbnail	<1
RI	Very weak	Crumbles under firm blows of geological hammer; can be peeled with a pocket-knife	1 - 5
R2	Weak rock	Can be peeled by a pocket-knife with difficulty; shallow indentations made by a firm blow with point of geological hammer	5 - 25
R3	Medium strong	Cannot be scraped or peeled with a pocket-knife; specimen can be fractured with a single firm blow of geological hammer	25 - 50
R4	Strong	Specimen requires more than one blow of geological hammer to fracture	50 - 100
R5	Very strong	Specimen requires many blows of geological hammer to fracture	100 - 250
R6	Extremely strong	Specimen can be chipped by geological hammer	> 250

STRATA PLOT



WATER LEVEL MEASUREMENT





```
Borehole,
Standpipe or
Monitor Well
(static conditions)
```

WELL CONSTRUCTION



Flush-mounted Well-head Enclosure




End/Top Cap



Solid PVC Pipe

,



۰

Bentonite



Cave-in

Test Pit Records

.

.

•



	LIENT	Henry Bell Development Ltd. Proposed Parking Garage - Duckw	orth Street @ Be	ell S	treet	, St. J	ohn's, 1	NL.				JECT N F PIT N			<u>28-(</u> ГР (
		nm-yy): DUG29-05-10	WATER L				29-05-				DAT	UM _	(Geod	etic	
			ţ	ET 1	3 8	SAMI	PLES					ar Stre	-			
B	<u> </u>		ž			α		 	2	20		40 	60)	8	0
DEPTH (m)	ELEV. (m)	DESCRIPTION	7 J. 7	WATER I FVFT		NITMRER	OTHER	Wa	ter Co	ntent	& Att	erberg	Limits	, W	/p	w w₁ Ə—I
- 0 -	15.78							1	0 2	0 3	30 4	10 50) 60) 70	8	0 90
	15.7	ORGANICS: Grassmat and Topso FILL: Loose to compact greyish br GRAVEL and SAND; trace silt; som (roots and rootlets); some debris (pic bricks, metal, concrete, rags, steel ro and an old telephone wire); some co boulders; moist.	rown ne organics													
- 1 -			×													
	14.2	End of Test Pit	X	×												
- 2 -		NOTES: 1) Test pit terminated between 1.3 m end) and 1.6 m (northern end) depth probable bedrock. 2) Test pit dry at time of excavation.	n (southern s on													
- 3 -																
- 4 -																
		A D I L i m I t e d 60 Pippy Place, Suite 200 St. John's, NL, A1B 4H7 Tel 709.579.2027 Fax 709.579.7115	Technologist: B. Reviewed By: W Contractor: Role Equipment: Cat	/m.N γCo	lelenc nstruc	ction Li	mited A-Hoe	∆ ¥	Wate	r Leve		pression ime of rel			avati	on



		mm-yy): DUG	rking Garage - Duckw 29-05-10	WATER					<u>9-05-</u>				D	ATI	-		Geo	TP deti	
DEPTH (m)	ELEV. (m)		DESCRIPTION		STRATA PLOT	WATER LEVEL	SA	NUMBER	OTHER TESTS	Wa		20		4	0	ength, 6 3 Limi	50 	w _p	80 ⊣ ₩
0 -	16.42	ASPHALT:								1	0	20	30	4	0 5	50 6	50 (T	70	80
-	15.9	GRANULA GRAVEL an (Class "A") a materials]; m	d SAND; trace silt [Grand sub-base (Class "B" oist.	anular base ') /															
1 -	<u>15.3</u> 15.2	and boulders;	Shaley bedrock.	ne cobbles															
- - - - -		bedrock. 2) Test pit dr	End of Test Pit minated at 1.2 m depth y at time of excavation lab encountered at 0.7																
2 -																			
3																			
4 -							-												
5			ADILimited	Technologist:	P.C		ion			Δ	TT					ion Te			



	LIENT DCATION	Henry Bell Development Ltd. Proposed Parking Garage - Duckwo	orth Street @ Be	ll Sti	eet, S	t. Joł	ın's, 1	۱L_				JECT		27-6	628- TP (<u>001.1</u> 03
D	ATES (dd-	mm-yy): DUG <u>29-05-10</u>	WATER LE	VEL			9-05-	10		-	DAT				detic	;
0			to	VEL	SA	MPL	ES			draine 20		ar Str 40	ength, 6	kPa 0	,	30
DEPTH (m)	ELEV. (m)	DESCRIPTION	STRATA PLOT	WATER LEVEL	TYPE	NUMBER	OTHER TESTS	Wat		i		1	y Limi	1		H ₩ ₩Į ⊖—-I
- 0 -	16.52 16.5							1	0 2	20 3	30 4	10 5	50 6	0 7	0 8	30 90
	<u> 16.1</u>	ASPHALT: GRANULAR FILL: Loose brown GRAVEL and SAND; trace silt [Gran (Class "A") and sub-base (Class "B") materials]; moist. <u>FILL:</u> Loose to compact greyish bro brownish grey GRAVEL and SAND; some debris (pieces of bricks, plastic, metal, pipes, and concrete beams); oc cobbles and boulders; moist.	own to ; trace silt; , wood,													
_	13.7	End of Test Pit		8						1111			:::: ::::		::::	:::: ::::
GEOTECH 62280011.GPJ ADI.GDT 8/6/10		NOTES: 1) Test pit terminated at 2.8 m depth of probable bedrock. 2) Test pit dry at time of excavation. 3) Concrete foundation wall encounter northwestern corner of test pit.	ered in													
SEOTECH 6		A D I L i m I t e d 60 Pippy Place, Sulle 200 St. John's, NL, A1B 4H7 Tel 709.579.2027 Fax 709.579.7115	Technologist: B. (Reviewed By: Wr Contractor: Roley Equipment: Cat 4	n. Me Cons	lendy structior	n Limi Id-A-H	ed loe	Ī	Wate	r Leve		ime of	ion Te Drilli		cavat	ion

	0
Ā	Ū

	LENT DCATION	Henry Bell Development Ltd. Proposed Parking Garage - Duckwort	th Street @ Bell	Str	eet, S	t. Joł	<u>ın's, 1</u>	۱L		_			ECT		<u>27-6</u>	628- TP	<u>001.1</u> 04
		mm-yy): DUG <u>29-05-10</u>	WATER LEV			2	<u>9-05-</u>					DAT				detio	<u> </u>
(m)	(E)		PLOT	LEVEL	SA	MPL			U	ndra 20	ined		ar Stro 10 		kPa 50 		80 H
DEPTH (m)	ELEV. (m)	DESCRIPTION	STRATA PLOT	WATER LEVEL	TYPE	NUMBER	OTHER TESTS	Wat	ter C	onte	ent 8	't Att	erberg	; Limi	ts	₩ _p	₩ ₩j Ə—I
- 0 -	23.31	OD GINEGO Comercia Truck and Th	anadi Mari					1	0	20	3() 4	0	50 (50 	70	80 90
	22.9	ORGANICS: Grassmat; Turf; and To	1/ 01- 9 10- 4 10-														
	22.4	FILL: Loose to compact greyish brow GRAVEL and SAND; trace silt; some (roots and rootlets); some debris (piece bricks, plastic, bottles and a chip bag); cobbles and boulders; moist.	organics es of some					· · · · · · · · · · · · · · · · · · ·									
- 1 -		TILL: Compact to dense brownish gr grey sandy GRAVEL; trace silt; occast cobbles and boulders; moist.	ey to														
					BK	01											
- 2 -																	
	00.0								*****								
- 3 -	20.8	End of Test Pit <u>NOTES:</u> 1) Test pit terminated at 2.5 m depth of probable bedrock. 2) Test pit dry at time of excavation.	n								• • • • • • • • • • • • • • • • • • •						
- 4 -																	
GEOTECH 65220011.GPJ ADI.GOT 8/6/10																	
- 5 -		A D I L i m i t e d 50 Pippy Place, Suite 200 St. John's, NL, A1B 4H7 Tel 709.579.2027 Fax 709.579.7115	Technologist: B. C Reviewed By: Wm Contractor: Roley Equipment: Cat 42	. Me Con:	lendy structio	n Lim nd-A-I	ited -loe		Wa	ter I	eve					::::	tion

C		Henry Bell	Development Ltd.	EST PIT						Π				No. <u>27</u>		28-00 P 05	
		Proposed Pa nm-yy): DUG	arking Garage - Duckwort 29-05-10	<u>h Street @</u> WATER	Bell LEV	<u>Str</u> EL	<u>eet, S</u>	t. <u>Jol</u> 2	<u>m's, P</u> 9-05-	<u>10</u>			T PIT N		eode)
		IIII- <i>yyy.</i> Doo		<u></u>	Γ		SA	MPL	ES	U		ned Sł	ear Stre 40	ngth, kF 60	'a	80	
DEPTH (m)	ELEV. (m)		DESCRIPTION		STRATA PLOT	WATER LEVEL	TYPE	NUMBER	OTHER TESTS	Water (20 - - Conter		tterberg	Limits		p W	/ W1 →1
- 0	18.14	ORGANICS	S: Grassmat and Topsoil.		11 al					10	20	30	40 5	0 60	70	80	90
- 1	17.9	NOTES:	End of Test Pit rminated at 0.2 m depth o lrock. y at time of excavation.		in the second												
- 2																	
- 3																	
GEOTECH 66280011.GPJ ADI.GDT 8/6/10			A D 1 L i m i t e d 60 Pippy Piace, Sulte 200 St. John's, NL, A1B 4H7 Tel 709.579.2027 Fax 709.579.7115	Technologis Reviewed B Contractor: Equipment:	iy: Wi Roley	n. M / Co	ielendy	ion Lit	nited -Hoe	₩ V	Jnconf Vater I Static V	Level a	t Time	sion Tes	st ng/Ex	cavat	ion

	Á		Т	EST PIT	' RI	EC	OR	D					
	CLI	IENT	Henry Bell Development Ltd.								PROJECT No.		
			Proposed Parking Garage - Duckwor nm-vv): DUG 29-05-10	th Street @ WATER			reet, S		<u>m's, 1</u> 9-05-		TEST PIT No. DATUM		TP 06
-	DA 	TES (dd-i	nm-yy): DUG <u>29-05-10</u>				SA	 MPL		1	ned Shear Strengt		
1		û			LOI	EVE			[20	40	60	80
	ידוו זבות	ELEV. (m)	DESCRIPTION		STRATA PLOT	WATER LEVEL	TYPE	NUMBER	OTHER TESTS	Water Conte	nt & Atterberg Lir	nits	W _p W W₁ I ↔ H
- (,	18.83			3.47					10 20	30 40 50	60	70 80 90
		18.7	ORGANICS: Grassmat and Topsoil. FILL: Loose to compact greyish brow brownish grey to grey GRAVEL and S trace silt; some organics (roots and roo some debris (pieces of bricks, metal, p wood) to 1.5 m depth; some cobbles a boulders; moist to wet.	wn to SAND; otlets) and pipe, and nd			BK	01					
GEOTECH 66280011.GPJ ADI.GDT 8/6/10	4	15.9	End of Test Pit <u>NOTES:</u> 1) Test pit terminated at 2.9 m depth of probable bedrock. 2) Test pit dry at time of excavation. 3) A PVC storm sewer pipe was encound 1.3 m depth.	untered at									
SEOTECH 6			A D I L i m i t e d 60 Pipy Place, Suite 200 St. John's, NL, A1B 4H7 Tei 709.579.2027 Fax 709.579.7115	Technologist Reviewed By Contractor: R Equipment: C	: Wm oley	i. Me Con	elendy structio	on Lim	ited Hoe	📱 🛛 Water L	ned Compression evel at Time of Da /ater Level		Excavation

		•
Ā	D	

	IENT	Henry Bell Development	Ltd.								PRC	JECT	No. <u>2</u>	<u>7-66</u>	<u>28-0</u>	<u>01.</u>]	I
	CATION	Proposed Parking Garage	- Duckworth Street @	<u>)</u> Bel	l <u>Str</u>	eet <u>, S</u> t	<u>. Joł</u>	nn's, N	IL	<u> </u>		T PIT I		 Geod	<u>FP 0</u>	7	-
DA	TES (dd-i	nm-yy): DUG29-0	<u>05-10</u> WATE	RLEV				9-05-		 [Indrai		UM			enc	-	
Î	G			PLOT	EVEL	SAI	MPL			20		40				0	
DEPTH (m)	ELEV. (m)	DESCRIP.	FION	STRATA PLOT	WATER LEVEL	TYPE	NUMBER	OTHER TESTS	Water	Conte	nt & A	tterberg	; Limite	, ,	V _p V I—€	V W Ə	71 1
- 0 -	18.63			.~~~~					10	20	30 :: :::	40 5	0 60	0 7() 80 	0 9	20
-	18.2	GRANULAR FILL: Log GRAVEL and SAND; trac (Class "A") and sub-base (materials]; moist.	e silt [Granular base Class "B")														-
- 1 -		FILL: Loose to compact a GRAVEL and SAND; trac (pieces of bricks, plastic, n pipes, old wires, ash/soot a occasional cobbles and box	e silf; some debris netal, wood, rags, ind concrete beams);														
								-									
- 2 -	16.6	TILL: Compact to very d to grey GRAVEL and SAN occasional cobbles and bo	ense brownish grey ND; trace silt; ulders; moist.														
- 3 -								MC,									
						BK	01	S	D								-
	-																
	<u> 14.9</u>	End of Te	est Pit														
- 4		NOTES: 1) Test pit terminated at 3. probable bedrock.				-											-
GEOTECH 66280011.GPJ ADL.GDT 8/6/10		2) Test pit dry at time of e															
2 - 5		A D I L i m i t e d 60 Pippy Piace, Suit St. John's, NL, A1B 4 Tel 709.579.2027 Fax 709.579.7115	200 Reviewed	By: W : Role	m. M v Coi	elendy nstructi	on Lir	nited -Hoe	ž.	Water		ompres t Time evel			xcava	tion	



.

	LIENT	Henry Bell D	evelopment Ltd.							**		-		ECTN				
		Proposed Pai mm-yy): DUG	king Garage - Duckwo 29-05-10	rth Street @ WATER	Bell LEV	<u>Stre</u> EL	et, St	<u>t. Joh</u> 29	<u>n's, N</u> 9-05-1	10		-	TEST DATU	PIT N JM _		-	<u>TP 0</u> letic	
	ATES (ua-	IIII-yy). Dog					SAI	MPL	ES					ur Strei				
DEPTH (m)	ELEV. (m)		DESCRIPTION		STRATA PLOT	WATER LEVEL	TYPE	NUMBER	OTHER TESTS	Wate	2 er Co			0 erberg	60 ——+ Limits	V		0 ₩ ₩1 Ə—1
- 0 -	23.98		i		~~~					1(::::) 2	0 3	0 4	0 50) 60) 7	0 8	0 90
		FILL: Loose GRAVEL and (roots and roo bricks, metal, boulders; moi	to compact greyish bro SAND; trace silt; some tlets); some debris (piec and concrete); some co st.	e organics ces of bbles and														
- 1	23.0	TILL: Comp grey sandy GI cobbles and b	act to dense brownish g AVEL; trace silt; occa oulders; moist.	grey to sional														
- 2																		
							BK	01	MC, S	O							· · · · · · · · · · · · · · · · · · ·	
- 3	21.0	<u>NOTES:</u> 1) Test pit ter probable bedu at 1.9 m deptl 2) Test pit dr	End of Test Pit minated at 3.0 m depth ock. Shaley bedrock en at western end of test at time of excavation.	on ncountered pit.														
																		· · · · · · · · · · · · · · · · · · ·
GEOTECH 66280011.GPJ ADI.GDT 8/6/10																		
сеотесн 6628			A D I L i m I t e d 60 Pippy Place, Suile 200 51: John's, NL, A1B 4H7 ret 709.579.2027 Fax 709.579.7115	Technologis Reviewed By Contractor: I Equipment:	y: Wn Rolev	ι. Με Con	elendy structio	on Lin end-A	nited -Hoe		Wat	er Lev		mpress Fime o vel			xcave	ntion

		0
Ā	D	

		LIENT	Henry Bell Development Ltd. Proposed Parking Garage - Duckwo		11م <u>؟</u>	Str	eet S	t Io	hn's Ì	JT.		-	PROJ TEST			<u>!7-6</u>	628-0 TP (<u>001.1</u> 19
			mm-yy): DUG <u>29-05-10</u>	WATER I					<u>9-05-</u>			_	DAT			 <u>Geo</u>	detic	
					ĩ	H	SA	MPL	ES				d Shea		ngth, I	kPa		
	DEPTH (m)	ELEV. (m)	DESCRIPTION		STRATA PLOT	WATER LEVEL	TYPE	NUMBER	OTHER TESTS	Wat		20 I	4 & Atte	0 erberg	6 Limit			80 † W WI O 1
	- 0 -	20.28		×	∞					1	0 2	$\frac{20}{1}$	80 4	0 51) 6	0 7	70 8	30 90
-		20.1	FILL: Loose to compact greyish bro GRAVEL and SAND; trace silt; trace (pieces of bricks); occasional cobbles boulders; moist.	e debris			BK	01										
		19.8	BEDROCK: Shaley bedrock.															
-	· 1 -		End of Test Pit <u>NOTES:</u> 1) Test pit terminated at 0.5 m depth bedrock. 2) Test pit dry at time of excavation.	in														
	- 2 -																	
	- 3 -																	
GEOTECH 66280011.GPJ ADI.GDT 8/6/10	- 4 -																	
SEOTECH 662	- 5 -		A D I L I m I t e d 60 Pippy Place, Suite 200 St. John's, NL, A1B 4H7 Tel 709.579.2027 Fax 709.579.7115	Technologist: E Reviewed By: V Contractor: Rol Equipment: Cat	Nm. ley (. Me Cons	lendy structio	n Lim nd-A-l	ited Hoe	즈 보 포	Wate	r Leve	d Com el at Ti er Leve	me of			xcavat	tion



	LENT	Henry Bell Development Ltd.	with Streat @ I	 D11	Cł.w	not St	- Ioł	unta N	<u></u>				ECT I		27-6	<u>628-(</u> TP_1	001.1
	CATION	Proposed Parking Garage - Duckwo nm-yy): DUG 29-05-10	WATER			<u>ei, oi</u>		<u>9-05-</u>			-	DAT			Geo	detic	
	1110 (00-			î		SAI	MPL			Un	draine	ed She	ar Stre	ngth, l	kPa		
DEPTH (m)	ELEV. (m)	DESCRIPTION		STRATA PLOT	WATER LEVEL	TYPE	NUMBER	OTHER TESTS	Wat		20 ntent	& Att	l0 	6 Limit			80 H W WI O H
- 0 -	20.21		1	3.15-4					1	0 2	20	30 4	0 5	0 6	0 7	70 8	30 90
	20.0	ORGANICS: Grassmat and Topsoi		1.2. 1/01													
	19.4	FILL: Loose greyish brown COBBI fill) intermixed with GRAVEL and S trace silt; some debris (pieces of bric bottles and a piece of old sewer pipe former house); moist.	AND; ks and from a														
- 1 -		FILL: Loose to compact greyish bro GRAVEL and SAND; trace silt; som and boulders; moist.	e cobbles														
- 2 -																	
	17.6	TILL: Compact to dense brownish grey GRAVEL and SAND; trace silt	grey to														
- 3 -		occasional cobbles and boulders; mo	ust.		-												
	167					BK	01	MC, S	0								
GEOTECH 66280011.GPJ ADI.GDT 8/6/10	16.7	End of Test Pit <u>NOTES:</u> 1) Test pit terminated at 3.5 m depth probable bedrock. 2) Test pit dry at time of excavation.	on														
теотесн 662800		A D I Limited 60 Pippy Place, Suite 200 St. John's, NL, A1B 4H7 Tel 709.679.2027 Fax 709.679.7115	Technologist: Reviewed By: Contractor: Re Equipment: C	Wm oley (. Me Cons	lendy structio	n Lim nd-A-	ited Hoe	 ₽ ₽ ₽	Wat	er Lev	ed Cor vel at T ter Le	lime o			xcava	tion

	<u> </u>
D	

															POTN	τ. <i>Υ</i>	7 66'	70 A	01.1
	CL	IENT	Henry Bell I	Development Ltd. arking Garage - Duckwo	rth Street @	Bell	Str	eet. St	t. Joł	1n's. N	II.		-		ECT N PIT N			<u>28-0</u> TP 1	
			mm-yy): DUG	<u>29-05-10</u>	WATER				2	9- <u>05-</u>	10		-	DATU			leod		
ŀ						H	닖	SAI	MPL	ES					ar Strei	• •			
	B	(m				PLO	LEVI		æ				20		0	60 		8()
	HT	V. (j		DESCRIPTION		STRATA PLOT	WATER LEVEL	TYPE	NUMBER	OTHER TESTS	Wat	er Co	ntent	& Atte	rberg	Limits	W	p V	v w₁ >──1
	DEPTH (m)	ELEV. (m)				STR	WA.	H	ΠΩ	5Ħ	11 ui							-	
ŀ	-										1	0 1	20 3	0 4	0 5() 60	70	80	0 90
ł	- 0 -	$\frac{21.14}{21.1}$	ASPHALT:		/`						1	0 2					Ĩ		
	-		GRANULA	R FILL: Loose brown	ish grey														-
	i	20.7	GRAVEL an (Class "A") a	R FILL: Loose brown d SAND; trace silt [Graind sub-base (Class "B") oist.	nular base	×													
		20.5	materials]; m	oist.	j														
	-		ך <u>FILL:</u> Loos COBBLES (1	e greyish brown to brow ock fill) intermixed with	n grey ₁														
	-		IGRAVEL an	d SAND; trace silt; mois e to compact greyish bro	st/														
	- 1 -		GRAVEL an	d SAND; trace silt; som	e cobbles														
•			and boulders	; moist.															
									1										-
		19.5		····		\otimes													-
	-		TILL: Com	pact to dense brownish	grey to														
		19.2	occasional co	pact to dense brownish and SAND; trace silt; bbbles and boulders; mo	ist.	i i id													
	- 2 -		NOTES:	End of Test Pit															
	-		1) Test pit ter	rminated at 1.9 m depth	on														
	-		probable bed 2) Test pit dr	y at time of excavation.															-
																			-
	-																		
	-						1												
	- 3 -	-																	
																			-
		1.																	
																			-
	- 4 -																		
										1									
8/6/10		-								ł									
1.GDT	- ·	-							1										-
2 AD]							1										
011.0										ł									
GEOTECH 66280011.GPJ ADI.GDT 8/6/10	- 5			ADILImited	Technologis	t: B. C	Cam	eron	1	1	Δ				npress				
NTECH		Ā		60 Pippy Place, Suite 200 St. John's, NL, A1B 4H7 Tel 709.579.2027	Reviewed B Contractor: Equipment:	Roley	Cor	structio	on Lin	nited -Hoe	₩ 2			vel at T ter Lev	fime of vel	f Drilli	ng/Ex	cavat	tion
GEC				Fax 709.579.7115		<u> </u>	206				<u> </u>								


				ST PIT	R	EC	ori	5					-			7 66	<u>, o</u> v	 1_1	
	CLI	ENT	Henry Bell Development Ltd. Proposed Parking Garage - Duckworth	Street @	Bell	Str	eet. St	t. Joł	<u>n's.</u> N	IL_				ECT N PIT N			<u>28-0</u> ГР 1		
			<u>Proposed Parking Galage - Duckword</u> nm-yy): DUG <u>29-05-10</u>	WATER	LEV	/EL		2	9-05-	10]	DATT		_(Beod	etic		
-					ЪТ	EL	SAI	MPL	ES		Und 20			ar Strer 0	ngth, k 60		8)	
	DEPTH (m)	ELEV. (m)	DESCRIPTION		STRATA PLOT	WATER LEVEL	TYPE	NUMBER	OTHER TESTS	Wate				erberg :		V	—_ /p\ }	v wj ∋—1	Į
-	0 +	22.25	ORGANICS: Grassmat and Topsoil.		<u>× 5</u>					1) 20) 3	0 4	0 50) 60) 70) 8) 90) -
		22.1	FILL: Loose greyish brown GRAVEI SAND; trace silt; some cobbles and bo moist.	, and ulders;															• - - -
		_21.1	SAND and GRAVEL: Compact tann brown SAND and GRAVEL; trace silt occasional cobbles and boulders; moist			Na	ВК	01											- - -
	2	_20.4	<u>TILL</u>: Compact to very dense browni to grey SAND and GRAVEL; trace sile occasional cobbles and boulders; mois	sh grey ; t.															
	3 -						BK	02	MC, S	0									
EOTECH 66280011.GPJ ADI.GDT 8/6/10	т	17.8	End of Test Pit <u>NOTES:</u> 1) Test pit terminated at 4.5 m depth of probable bedrock.	'n															
EOTECH 66280011.	• 5 •		probable bedrock. 2) Test pit dry at time of excavation. ADILIMITED ADILIMITED 60 Pippy Place, Suite 200 St. John's, NL, A1B 4H7 Tel 709.579.2027 Fax 709.579.7115	Technologis Reviewed B Contractor: Equipment:	iy: W Role	'm. M v Co	lelendy nstruct	ion Li	mited		Wat	er Lev	ed Co vel at ter Lo	mpress Time o evel	sion To f Dril	est ling/E	xcava	tion	[



	CLIENT _	Henry Bell Development Ltd.	auth Streat @ Pa	11 94	raat S	t Tak	unta N			-		JECT] F PIT]		27-6	<u>628-</u> TP	<u>001.1</u> 13
1		Proposed Parking Garage - Duckwe mm-yy): DUG29-05-10	WATER LE				<u>9-05-</u>				DAT			Geo	detic	
			[=	j,	SA	MPL	ES		Un	drain	ed She	ar Stre	ength,	kPa		
DEPTH (m)	ELEV. (m)	DESCRIPTION	STRATA PLOT	WATER LEVEL	TYPE	NUMBER	OTHER TESTS	Wat		20 - ontent		40 		50 ts		80 † W W _I O I
- 0	21.55	100						1	0 2	20	30	40 5	0 6	50 (70 8	30 90
	21.4	ORGANICS: Grassmat and Topso	20	0												-
-	21.1	FILL: Loose greyish brown GRAV SAND; trace silt; some debris (piece bricks); occasional cobbles and boul	s of ders; moist													
	•	TILL: Compact to very dense brow to grey SAND and GRAVEL; trace s occasional cobbles and boulders; mo	silt; bist.													
- 1	-															-
_	-				ВК	01										
- 2	19.2															
- 3		End of Test Pit <u>NOTES:</u> 1) Test pit terminated at 2.4 m depth probable bedrock. Knob of bedrock encountered at 1.6 m depth on west s pit. 2) Test pit dry at time of excavation.	side of test													
GEOTECH 68280011.GPJ ADI.GDT 2216/10																
SEOTECH 662800		A D I L I m i t e d 60 Pippy Place, Suite 200 St. John's, NL, A IB 4H7 Tel 709.579.2027 Fax 709.579.7115	Technologist: B. Reviewed By: Wi Contractor: Roley Equipment: Cat	m. M y Cor	elendy structio	n Limi nd-A-ł	ited Ioe	 ₽ ₽ ₽	Wate	er Lev		npress fime of vel			xcava	tion .

Gradation Curves

.



• .

ADI Limited Letter-form Report:

Geotechnical Sub-surface Investigation Proposed parking Garage Duckworth at Bell Street St. John's, Newfoundland and Labrador Date: February 14, 2011

,



{

ADI File 27-6628-001.1

SHE CO

ADI Limited A Trow Global Company

Henry Bell Development Ltd. 12 Caldwell Place St. John's, Newfoundland Labrador A1E 6A4

Archilecture Engineering Consulting Procurement Project Management

Attention: Mr. William Clarke

Dear Sirs:

RE: Geotechnical Sub-surface Investigation *Proposed Parking Garage* Duckworth Street at Bell Street St. John's, Newfoundland and Labrador

ł



Acting on the request of Mr. William Clarke of *Henry Bell Development Ltd., ADI Limited* has completed a follow-up geotechnical sub-surface investigation to determine the quality of the bedrock encountered during the initial geotechnical test pit sub-surface investigation completed on May 29, 2010, and reported in *ADI's* report dated June 15, 2010.

Field Program

Field work was completed on January 22 and 23, 2011, and consisted of three boreholes (BH), advanced using a *CME-55* drill rig operated by *Logan Geotech Inc.* of Dieppe, New Brunswick. The boreholes were located in the field by *ADI Limited* in discussion with Mr. Clarke. Final borehole locations are shown on *Figure 1: Borehole and Test Pit Location Plan.* Twenty-five-millimeter-diameter PVC stand-pipes were installed in each borehole to allow for static groundwater level measurements.

60 Pippy Place Suite 200 St. John's, NL A1B 4H7 Canada Telephone: 709.579.2027 Fax: 709.679.7115 Email: nfid@adi.ca Conditions encountered in the boreholes are described below and on the Borehole Records attached. *Table 1: Summary of Borehole Data* presents the summarized findings of the investigation.

<u>Bedrock</u>

Bedrock was encountered beneath the overburden layer (Fill or Till) in BH01, BH02, and BH03 at depths of 1.8 in, 5.4 m, and 1.1 m, respectively, below the existing ground surface. All boreholes were terminated in the bedrock at depths ranging from 4.1 m to 9.8 m below the existing ground surface (approximate elevation 13.0 m geodetic).

www.adilimited.ca

- - -	Proposed	Geotechnical Sub-s Parking Garage - 1 St. John's, Newfour	Duckworth Stree	t at Bell Street		
Borehole No.	Ground Surface Blevation (m)	Bottom of Overburden Blevation (m)	Top of Bedrock Elevation (m)	End of Borehole Blevation (m)	Ground- Water Elevation (m)	
BH01	17.77	16.0	16.0	13.7	16.9	
BH02	21.63	16.2	16.2	12.6	19.2	
BH03	22.76	21.7	21,7	13.0	21.3	

Publisher geology for the area indicates the bedrock consists of thin lenticular-bedded, dark grey sandstone and minor shale of the Renews Head Formation, St. John's Group. Bedrock is variable, but may be described as a medium grey sandstone. Rock quality designations (RQD) ranged from 0 to 68 and, on this basis, the bedrock may be characterized as very-severely-fractured to fractured.

Compressive testing was completed on nine selected bedrock core samples. Results are presented in *Table 2: Bedrock Compressive Strength Results*.

Proposed Par	OCK COMPRESSIVE STRI eking Garage - Duckworth Str ohn's, Newfoundland and La	eet at Bell Street
Borehole Location	Sample Depth (m)	Compressive Strength (MPa)
BH01-01	3.0 m to 3.2 m	Rock core broke prematurely
BH01-02	3.6 m to 3.8 m	18,4
BH02-01	3.5 m to 3.8 m	35.2
BH02-02A	8.2 m to 8.5 m	39.1
BH03-02B	8.5 m to 8.8 m	39.7
BH03-01	3.2 m to 3.5 m	25.9
BH03-02	4.7 m to 5.0 m	61.5
BH03-03A	7.6 m to 7.9 m	46.1
BH03-03B	7.9 m to 8.2 m	35.1
BH03-04	9.1 m to 9.3 m	27.1



Groundwater

Twenty-five-millimetre-diameter stand-pipes were installed in each of the three boreholes. Depth to groundwater obtained on January 26, 2011, were as follows: BH01, 1.0 m; BH02, 2.5 m; BH03, 1.8 m, below the existing ground surface. Note that each borehole location (stand-pipe) was purged and allowed to obtain its static level prior to measurement.

Discussion

Groundwater was not encountered in test pits excavated during the June 2010 geotechnical investigation. Recent boreholes installed at the site have confirmed groundwater elevations ranging from 16.9 m to 21.3 m. Project drawings dated June 12, 2010, Typical Building Section, indicate a proposed finish Level 1 floor elevation of 14.3 m. Based on the findings of the follow-up borehole program, *ADI* recommends that drainage piping be constructed immediately adjacent all perimeter footings, with positive drainage into the municipal storm system, and an under-drain system be installed beneath the slabs at the lowest levels. Typically, this would consist of a series of perforated drainage pipes placed just above the bedrock surface, and backfilled with free-draining gravels. The perforated piping should be connected to a non-perforated header pipe(s) to direct the flow out of the building. It is recommended that PVC piping be used for drainage works and that the system be designed to ensure positive flow to the municipal storm system. A minimum slope of one percent is recommended for perimeter and under-drain piping. The invert of all sections of drainage piping should be at least 300 mm below the top of slab level. Traps should be installed for future inspection and cleaning, and backwater flow valves should be installed to prevent water from entering the system from outside sources.

Bedrock encountered at the site is classified as very-severely-fractured to fractured in terms of rock quality. Based on the bedrock quality, bedrock removal using a hydraulic rock buster should be achieved at the site. Bedrock quality typically encountered in the upper 2.0 m to 3.6 m is considered very-severely-fractured, becoming more sound with depth.

A subsurface investigation is a limited sampling of conditions at a particular site. Should conditions be encountered which differ from those described in this letter-report, we require immediate notification in order to permit a re-evaluation of our recommendations.



.

Page 4

We trust this submission meets your current requirements. Should you have any questions or require clarification on any aspect of this report, please do not hesitate to contact our office.

Yours very truly,

ADI Limited

and annon

Blair D. Cameron, P.Tech. Sr. Geo-Environmental Tech.


BDC/WGM;dgn

Attachments: Figure 1: Borehole and Test Pit Location Plan Borehole Records (3)

6/#Project Files/#Client 6601 to 7000/6628/65280011/Reports/Rock Core Letter-Report



William G. Melendy, M.A.Sc., P.Eng. Gröup Manager, Geotechnical/Environmental Engineering



L		Proposed Parking Garage - Duckweet	oith Street at Bel 		et, i	St. Jol	11.	1-26		BO DA	REHO TUM	No. 2 LE No.] Geod	3H leti
DEPTH (m)	ELEV. (m)	DESCRIPTION		STRATA PLOT	WATER LEVEL	TYPE	SA	RECOVERY	N-VALUE OR RQD	Benzene	Tolucne	Ethyl Benzene	ratory XVICIC	
- 1 - 2 - 3 - 4 - 5 - 7 - 8 - 9 - 10 - 10 - 10 - 10 - 10 - 10 - 10	17.77 17.7 17.3 16.0	GRANULAR FILL: Loose brown GRAVEL and SAND; trace silt [Gra (Class "A") and sub-base (Class "B") imoist. FILL: Loose to compact greyish bro	nyn GRAVBL ind boulders; I to severely		¥ ¥	RC RC		100%	0 - 14					

·)	BOREHOL	ERE	EC	ORI)								
	LIENT	Proposed	Parking Garage - D	uckworth Street at Be	all Stre	ot	St. Io	1	MI	<u> </u>			'No. LB No		28-0 3H 0	
		mm-yy): BORIN					01. 30		- <u>1-26</u>		DA	TUM		Geod	letic	
2					5	Ę		SA	MPLE	S	CH	EMIC/	AL AN Labo	ALYS ratory	E S (m	g/kg
DEPTH (m)	ELEV. (m)		DESCRIPTI	ON	STRATA PLOT	WATER LEVEL	TYPE	NUMBER	RECOVERY	N-VALUE OR RQD	Benzene	Tolucne	Ethyl Benzene	Xylene	HdI	Headspace
0 -	21.63								mm		ļ					
1	20.4			RAVEL and SAND; Iders; moist. act tannish brown ; occasional cobbles	-				-							
2	19.7	and boulder	rs; moist. mpact to very dense b and GRAVBL; trac s - becoming cobble n depth; moist.		Contraction of the second	\$										
4										-						
5	16.2															
		BEDROCI SANDSTO	 Very severely fraction 	ctured to fractured			RC	01	100%	0						
6							RC	02	100%	0						
7							RC	03	100%	21						
8							RC	0 4	100%	68						
9	12.6	Noma	End of Borcho	le	╶╞┱┹╣	+							·			
0		NOTES: 1) Soll samp obtained from	eles not collected, So m TP12 excavated of	bil strata and depths n May 29, 2010.		1										
1										1						

•



ł


BOREHOLE RECORD


Ĺ

C	lient _	Proposed Parking Garage - Duckworth Street at Be	II Stre	et	St Io	hnle	NI.	.			ľ No. – ILE No		28-0 BH 0	
		mm-yy): BORING <u>22-1-11</u> WATER I			01.00		1-26	······································		TUM		Geod		<u> </u>
-				Γ.			MPLES	3			AL AN		ES (m	g/kg)
DEPTH (m)	ELEV. (m)	DESCRIPTION	STRATA PLOT	WATER LEVEL	TYPE	NUMBER	2	N-VALUE OR RQD	Eenzene	Tolucnc	Ethyl Benzene	xylcnc Xylcnc	Hal	Hendspace Levels (ppm)
	22.76					1	num							
0	22,4	ORGANICS: Grassmat; Turf; and Topsoil.	14	1			1							
- 1	21.7	EILL: Loose to compact greyish brown GRAVEL and SAND; trace sill; moist. BEDROCK: Very severely fractured to fractured SANDSTONE.	-	Ā										
2		SANDSTONE.		Ż.	RĊ	01	100%	38						
- 3					RĊ	02	100%	0						
- 4					RC	03	100%	12						
- 5					RC	04	100%	30						
- 6					RC	05	100%	65						
- 8					RC	06	100%	43						
9	13.0				RC	07	100%	62						
- 10		End of Borehole <u>NOTES:</u> 1) Soil samples not collected. Soil strata and depths obtained from TP04 excavated on May 29, 2010.												
- 11		ADILINITION CONTRACTOR SUID ATE 100,579,2027 Fax 700,579,2027 Fax 700,570,2027 Fax 700,570,2027	elendy	nc.			-	Valer Lev tatic Wat			Drilling	/Excav	ation	

Appendix B

Drawings Received from Clients







)	GENERAL NOTES
M.H. $M.H.$	NHOLE MANHOLE CH BASIN CATCH BASIN E VALVE GATE VALVE GATE VALVE TOP ATION STOP AIN SEWER MAIN SEWER MAIN	C REVISED FOR APPROVALS C REVISED FOR APPROVALS D J.J.M. 02/17/12 B ISSUED FOR CLIENT REVIEW D.J.M. 08/31/11
		No. REVISIONS BY DATE A A PLAN, SECTION, ELEVATION, OR DETAIL No. B B No. OF DRAWING WHERE ABOVE IS DRAWN REFERENCE: STAMP: Image: Construct of the state
		PROVINCE OF NEWFOUNDLAND PERMIT HOLDER CLASS "A" This Permit Allows PETER A. HUTTON To practice Professional Engineering in Newfoundland and Labrador Permit No. as issued by APEGN <u>D0084</u> which is valid for the year <u>2012</u>
		CELL: (709) 682-3488 PHONE: (709) 368-1669 EAX: (709) 368-0318 E-MAIL: djmadden@nl.rogers.com
		ENGINEER/ARCHITECT: PETER HUTTON, P. ENG. ADVANTAGE MANAGEMENT LTD. 322 WATERFORD BRIDGE ROAD ST. JOHN'S, NF A1E 1E9 TEL. /FAX. (709) 368-8547 CELL (709) 685-3671 OWNER/CLIENT NAME:
		HENRY BELL DEVELOPMENTS LTD. PROJECT TITLE: DUCKWORTH STREET PARKING GARAGE AND CONDOMINIUM
		DRAWING TITLE: EXISTING SITE PLAN DRAWN/DESIGNED BY: D.J.M. DATE: JULY 2010
	0m	APPROVED BY: P.A.H. SCALE: AS SHOWN PROJECT No.: 10208 DRAWING No.: C2 C





LEGEND	GENERAL NOTES
NEW MANHOLE	1. DO NOT SCALE FROM DRAWINGS.
	2. ALL WORK MUST BE PERFORMED IN ACCORDANCE WITH THE REQUIREMENTS OF THE APPLICABLE
	SECTIONS OF THE CITY OF ST. JOHN'S SPECIFICATIONS BOOK.
│	3. CONTRACTOR SHALL CONFIRM LOCATION,
	ALIGNMENT, INVERTS AND TYPE OF MATERIAL OF ALL UNDERGROUND SERVICES AND SHALL NOTIFY THE
$- \overline{C} - CURB STOP$ $- \overline{C} - CORPORATION STOP$	ENGINEER/OWNER PRIOR TO COMMENCING ANY WORK. 4. ANY DISTURBED AREAS DURING CONSTRUCTION
	SHALL BE REPLACED WITH NEW AS DIRECTED IN FIELD WITH ENGINEER.
WATER MAIN	5. STREET EXCAVATION PERMIT MUST BE OBTAINED PRIOR TO STARTING ANY WORK WITHIN THE PUBLIC
SANITARY SEWER MAIN	STREET RIGHT-OF-WAY.
STORM SEWER MAIN	
$- \times \times FENCE$ - W - W - RETAINING WALL	
-c - c - U/G CABLE	
100.00 EXISTING ELEVATION	
	CREVISED FOR APPROVALSD.J.M.02/17/12BISSUED FOR PHASE 1 CONSTRUCTIOND.J.M.11/30/11
	A ISSUED FOR CLIENT REVIEW D.J.M. 08/31/11
	No. REVISIONS BY DATE
	A – PLAN, SECTION, ELEVATION, OR DETAIL No.
	B B - No. OF DRAWING WHERE ABOVE IS DRAWN
	REFERENCE: STAMP:
	ROLFESS/014
	PETER A. HUTTON
	$\frac{02/17/12}{DATE}$
	PERMIT STAMP: PROVINCE OF NEWFOUNDLAND
	PERMIT HOLDER CLASS "A"
	This Permit Allows
	PETER A. HUTTON To practice Professional Engineering in Newfoundland and Labrador
	Permit No. as issued by APEGN <u>D0084</u> which is valid for the year <u>2012</u>
	YNAMIC
	EVELOPMENT
	ERVICES LTD
	CELL; (709) 682-3488 P.O., Box 293 PHONE; (709) 368-1669 ST, JOHN'S, NL
	FAX; (709) 368-0318 AIS IG4 E-MAIL; djmadden@nl,roqers.com
	ENGINEER/ARCHITECT:
	PETER HUTTON, P. ENG. ADVANTAGE MANAGEMENT LTD.
	322 WATERFORD BRIDGE ROAD
	ST. JOHN'S, NF A1E 1E9
82	TEL. /FAX. (709) 368-8547 CELL (709) 685-3671
	OWNER/CLIENT NAME:
	HENRY BELL
	DEVELOPMENTS LTD.
	PROJECT TITLE: DUCKWORTH STREET
	PARKING GARAGE
	AND CONDOMINIUM
	DRAWING TITLE:
	SITE DEVELOPMENT PLAN
	DRAWN/DESIGNED BY: DATE:
	D.J.M. JUNE 2010
0 5 10m	APPROVED BY: P.A.H. SCALE: AS SHOWN
	PROJECT No.: DRAWING No.: REV.:
	10208 C3 C




	LEGEND	general notes
``	NEW MANHOLE	1. DO NOT SCALE FROM DRAWINGS.
`\	COCCCCCCCCCCCCCCCCCCCCCCCCCCCCCCCC	2. ALL WORK MUST BE PERFORMED IN ACCORDANCE WITH THE REQUIREMENTS OF THE APPLICABLE SECTIONS OF THE CITY OF ST. JOHN'S SPECIFICATIONS BOOK.
Þ	EXISTING CATCH BASIN	3. CONTRACTOR SHALL CONFIRM LOCATION, ALIGNMENT, INVERTS AND TYPE OF MATERIAL OF ALL UNDERGROUND
<i>,</i>		PRIOR TO COMMENCING ANY WORK.
	CCURB STOP	4. MINIMUM WIDTH OF ASPHALT REINSTATEMENT FOR THE TRENCH SHALL BE 3.0m. ASPHALT REINSTATEMENT MUST
/ 84	CORPORATION STOP	BE PERFORMED IN ACCORDANCE WITH THE REQUIREMENTS OF ITEM NO. 352, FULL DEPTH ASPHALT PATCH, OF THE
/	 TEE WATER MAIN	CITY OF ST. JOHN'S SPECIFICATIONS BOOK. 5. STREET EXCAVATION PERMIT MUST BE OBTAINED PRIOR TO STARTING ANY WORK WITHIN THE PUBLIC STREET
	SANITARY SEWER MAIN	6. A PERMIT TO CONNECT MUST BE OBTAINED PRIOR TO
		7. ALL WORK ON EXISTING WATER MAINS SHALL BE DONE
730 6.88m 26.63m	- × × FENCE - W W RETAINING WALL	BY CITY FORCES. 8. CONNECTION TO EXISTING WATER MAINS SHALL BE
	-C-C-U/G CABLE	DONE AS PER SECTION 230, IN PARTICULAR ITEM 230.17, OF THE CITY OF ST. JOHN'S SPECIFICATION BOOK.
/	100.00 EXISTING ELEVATION	D REVISED FOR APPROVALS D.J.M. 04/05/12 C REVISED FOR APPROVALS D.J.M. 02/17/12
		B ISSUED FOR PHASE 1 INFORMATION D.J.M. 11/30/11 A ISSUED FOR CLIENT REVIEW D.J.M. 08/31/11
		No. REVISIONS BY DATE
	$\langle \rangle$	A - PLAN, SECTION, ELEVATION, OR DETAIL No.
		B B - No. OF DRAWING WHERE ABOVE IS DRAWN
		REFERENCE: STAMP:
		ROFESSIONAL EN
		PETER A. HUTTON
' /		32 <u>Signature</u> 22 <u>04/05/12</u>
/		ALLA OF NEWFOULD
/		PERMIT STAMP:
1		PROVINCE OF NEWFOUNDLAND PERMIT HOLDER
/		CLASS "A" This Permit Allows
/		PETER A. HUTTON To practice Professional Engineering in Newfoundland and Labrador
		Permit No. as issued by APGCN <u>D0084</u> which is valid for the year <u>2012</u>
HEAD ND		EVELOPMENT
		EDVICEC IT
		ERVICES LIV
		CELL: (709) 682-3488 P.O. Box 293
		PHONE: (709) 368-1669 ST. JOHN 5, N. FAX: (709) 368-0518 AI5 164
		E-WAIL: djmadden@ril.roqers.com
\		PETER HUTTON, P. ENG.
$\overline{\ }$		ADVANTAGE MANAGEMENT LTD.
$^{\sim}$		322 WATERFORD BRIDGE ROAD ST. JOHN'S, NF
		A1E 1E9 TEL. /FAX. (709) 368–8547 CELL (709) 685–3671
¢		OWNER/CLIENT NAME:
		HENRY BELL
		DEVELOPMENTS LTD.
		PROJECT TITLE: DUCKWORTH STREET
		PARKING GARAGE
		AND CONDOMINIUM
L		DRAWING TITLE:
		SITE SERVICES PLAN
		DRAWN/DESIGNED BY: DATE:
		D.J.M. JUNE 2010 APPROVED BY: SCALE:
	0 5 10m	P.A.H. AS SHOWN
		project no.: Drawing no.: Rev.: 10208 C4 D









	GENERAL NOTES
	1. DO NOT SCALE FROM DRAWINGS. 2. ALL WORK MUST BE PERFORMED IN ACCORDANCE
	WITH THE REQUIREMENTS OF THE APPLICABLE SECTIONS OF THE CITY OF ST. JOHN'S SPECIFICATIONS BOOK. 3. CONTRACTOR SHALL CONFIRM LOCATION, ALIGNMENT,
	INVERTS AND TYPE OF MATERIAL OF ALL UNDERGROUND SERVICES AND SHALL NOTIFY THE ENGINEER/OWNER PRIOR TO COMMENCING ANY WORK.
	4. CONTRACTOR IS RESPONSIBLE FOR ALL TRAFFIC COORDINATION, SIGNAGE AND OTHER REQUIREMENTS AS PER THE REGULATIONS OF THE CITY OF ST. JOHN'S
CLOSED AHEAD ROSS HERE" SIGN	AND OTHER GOVERNING AUTHORITIES. REFER TO DIVISION 7 FOR SIGNAGE DETAILS. 5. SITE HOARDING FOR EACH PHASE TO BE DONE BY
	OTHERS. 6. SLOPE STABILIZATION FOR ALL EXCAVATIONS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. ALL
	METHODS USED SHALL REQUIRE ACCEPTANCE FROM GEOTECHNICAL ENGINEER AND ALL HEALTH AND SAFETY REGULATIONS.
	A ISSUED FOR APPROVALS D.J.M. 02/17/12 No. REVISIONS BY DATE
	A - PLAN, SECTION, ELEVATION, OR DETAIL No. B - No. OF DRAWING WHERE ABOVE IS DRAWN
	REFERENCE: STAMP:
	PROFESSION CT
	PETER A. HUTTON
	OZ/17/12 DATE OF NEWFOUND
	PERMIT STAMP: PROVINCE OF NEWFOUNDLAND
	PERMIT HOLDER CLASS "A" This Permit Allows
	PETER A. HUTTON To practice Professional Engineering in Newfoundland and Labrador
	Permit No. as issued by APEGN <u>D0084</u> which is valid for the year <u>2012</u>
	\mathbf{M}
	EVELOPMENT
<u>NOTE:</u> LOCATION, SPACING, HEIGHT, ETC OF ALL SIGNAGE SHALL BE AS PER THE REGULATIONS OF THE CITY	
OF ST. JOHN'S AND OTHER GOVERNING AUTHORITIES.	ERVICED LID
	CELL; (709) 682-3488 P.O. Box 293 PHONE; (709) 368-1669 ST, JOHN'S, NL FAX; (709) 368-0318 AIS 1G4
	E-MAIL; djmadden@nl.roqers.com ENGINEER/ARCHITECT:
	PETER HUTTON, P. ENG.
"CONSTRUCTION AHEAD" SIGN	ADVANTAGE MANAGEMENT LTD. 322 waterford bridge road
	ST. JOHN'S, NF A1E 1E9 Tel. /fax. (709) 368–8547 Cell (709) 685–3671
•	OWNER/CLIENT NAME:
	HENRY BELL DEVELOPMENTS LTD.
	PROJECT TITLE: DUCKWORTH STREET
	PARKING GARAGE AND CONDOMINIUM
	DRAWING TITLE: HOARDING AND
	TRAFFIC CONTROL PLAN PHASE 2
	DRAWN/DESIGNED BY: DATE:
	D.J.M. FEBRUARY 2012
0 5 10m	PROJECT No.: DRAWING No.: REV.:
	10208 C7 A






:\Current Projects\10030 Henry Bell Developments Ltd\-01 Duckworth Street Development\Drawing\REV 2\S1-S4 rev2, S5rA,S6rA,S7rA.dwg, S1r2, 7/3/2012 3:58:24 PM, mpumphre

c - 30	
	NOTES
	CONTRACTORS TO VERIFY ALL DIMENSIONS ON THE SITE BEFORE PROCEEDING WITH THIS WORK. "THESE DESIGN DOCUMENTS ARE PREPARED SOLELY FOR THE USE OF HENRY BELL DEVELOPMENTS LTD.WITH WHOM ACUREN GROUP INC. (ACUREN) HAS ENTERED INTO A CONTRACT & THERE ARE NO REPRESENTATIONS OF ANY KIND MADE BY ACUREN TO ANY PARTY WITH WHOM ACUREN HAS NOT ENTERED INTO A CONTRACT."
2320 2200 23.94	2 PILE ADDED BY CONTRACTOR 12.07.03 1 PILE ADDED – SITE CONDITIONS 12.05.24
	0 ISSUED FOR CONSTRUCTION 12.02.21 D ISSUED FOR MATERIAL PURCHASE 12.02.13
-22.77	C ISSUED FOR REVIEW 12.02.13
	B ISSUED FOR REVIEW 12.01.17
2/52 [22.57]	A ISSUED FOR DISCUSSION 12.01.13 YY.MM.DD
22.57	NO. DESCRIPTION DATE
	ISSUES
3m 6m 21.95	PROVINCE OF NEWFOUNDLAND AND LABRADOR
	REFERENCE AND GEOGENEESE This Permit Allows
20,93	ACUREN GROUP INC.
	To practice Professional Engineering in Newfoundland and Labrador.
TIONS DISTANCE DISTANCE TO TO TO COORDINATES HENRY ST. EXCAVATION 5 269 481.975 326 701.771 0.5m 5.225m 5 269 484.937 326 702.268 0.5m 3.993m 5 269 487.895 0.5m 0.570m	Permit No. as issued by PEGNL D0056
326 702.768 0.5m 2.538m 5 269 490.851 326 703.261 0.5m 1.065m 5 269 493.813 326 703.758 0.5m 2.154m 5 269 496.768 326 704.254 0.5m 3.296m	HENRY BELL DEVELOPMENTS LTD.
5 269 499.727 326 704.751 0.5m 4.432m	DRAWN BY: DATE: YY.MM.DD MARY PUMPHREY 12.01.05
5 269 502.690 326 705.255 0.5m 4.956m	CHECKED BY: DATE: YY.MM.DD GREG BARTON 12.02.13
5 269 505.644 326 705.744 0.5m 4.913m	APPROVED BY: DATE: YY.MM.DD GREG BARTON 12.02.13
5 269 508.602	SCALE: AS NOTED
5 269 511.566	A B DETAIL NO. DRAWING NO. WHERE DETAILED
<u>326 706.745 0.5m 3.425m</u> 5 269 479.290	
5 269 476.438	JOB TITLE
<u>326 700.841 0.5m 3.599m</u>	MARCONI BUILDING HENRY STREET RETAINING WALL PHASE 1
	DRAWING TITLE
	SITE PLAN INDICATING RETAINING WALL LOCATION
	PROJECT NO. SHEET NO. REV.
	10030–01 S1 2





int Projects/10030 Henry Bell Developments Ltd/-01 Duckworth Street Development/Drawing/REV 2/S1-S4 rev2, S5rA,S6rA,S7rA.dwg, S4r2, 7/3/2012 3:58:41 P

NOTES CONTRACTORS TO VERIFY ALL DIMENSIONS ON THE SITE BEFORE PROCEEDING WITH THIS WORK. "THESE DESIGN DOCUMENTS ARE PREPARED SOLELY FOR THE USE OF HENRY BELL DEVELOPMENTS LTD.WITH WHOM ACUREN GROUP INC. (ACUREN) HAS ENTERED INTO A CONTRACT & THERE ARE NO REPRESENTATIONS OF ANY KIND MADE BY ACUREN TO ANY PARTY WITH WHOM ACUREN HAS NOT ENTERED INTO A CONTRACT." 2 PILES ADDED 12.07.03 2 1 ISSUED FOR CITY APPROVAL 12.03.01 YY.MM.DD DATE NO. DESCRIPTION ISSUES PROFESSION GREGORY BARTON PROVINCE OF NEWFOUNDLAND AND LABRADOR PERMIT HOLDER ACUREN GROUP INC. o practice Professional Engineering in Newfoundland and Labrador. Permit No. as issued by PEGNL _D0056_ ACUREN Acuren Group Inc. 112 Forest Rd. St. John's, NL A1A 1E6 Tel: (709)753-2100 / Fax: (709)753-7011 email: receptionnl@acuren.com HENRY BELL DEVELOPMENTS LTD. DATE: YY.MM.DD DRAWN BY: 12.01.05 MARY PUMPHREY CHECKED BY: DATE: YY.MM.DD 12.02.13 GREG BARTON APPROVED BY: DATE: YY.MM.DD GREG BARTON 12.02.13 SCALE: AS NOTED A DETAIL NO. B DRAWING NO. WHERE DETAILED Ά В JOB TITLE $\sim\sim\sim\sim\sim$ MARCONI BUILDING HENRY STREET RETAINING WALL PHASE 1 DRAWING TITLE PHASE 1 HENRY STREET RETAINING WALL ANCHORS AND SAN/STORM SEWER PROFILE SHEET NO. PROJECT NO. REV. 10030-01 **S4** 2

 2^{2}

Appendix C

Soil Profile Drawings

Project No.: 0001

Project Name: Duckworth Street Retaining Wall

Document: Soil Profile Drawings

To:

Acuren Group Inc.

112 Forest Rd

St. John's, NL, A1A 1E6

From:

Erica Soucy, Chenel Waight, Chantel Nicolle, Qiong Zhang

Group N - QCEC

Memorial University of Newofundland


St. John's, NL, A1B 3X5


Submission Date: April 03, 2013


Drawing Lists:


Figure 1. Site Plan with Borehole and Testpit Locations


- Figure 2. Cross Section Locations
- Figure 3. Soil Profile for Cross Section 1-1'
- Figure 4. Soil Profile for Cross Section 2-2', 3-3', and 4-4'
- Figure 5. Site Plan with Retaining Wall Location





















$$2-2'$$
, $3-3'$, and $4-4'$



Appendix D

Soldier Pile and Rigid Gravity Retaining Wall Drawings

Project No.: 0001

Project Name: Duckworth Street Retaining Wall

Document: Soldier Pile Retaining Wall Detailed Drawing

To:

Acuren Group Inc.

112 Forest Rd

St. John's, NL, A1A 1E6

From:

Erica Soucy, Chenel Waight, Chantel Nicolle, Qiong Zhang

Group N - QCEC

Memorial University of Newofundland


St. John's, NL, A1B 3X5


Submission Date: April 03, 2013

Drawing Lists:


- Figure 1. Site Layout
- Figure 2. Excavation Profile
- Figure 3. Soldier Pile Retaining Wall Plan View (Top) and Elevation View (Bottom)


Figure 4. Soldier Pile Retaining Wall Detailed Drawings





	General Notes
d Surface	
ck	
tion Line	
	No. Revision/Issue Date
	Firm Name and Address Quality Civil Engineering Consultants Memorial University of Newfoundland St. John's, NL, A1B 3X5
	Project Name and Address
	Duckworth Street Retaining Wall St. John's, NL
	Project Sheet
	Date 03.04.2013 Scale





	General N	Notes	
е			
Bar			
°a nent Grout			
0.168			
a Length			
Sength			
	No. Revision/	Issue Date	
	Firm Name and Address Quality Civil Engineerir Memorial University of St. John's, NL, A1B 3	ng Consultants Newfoundland	
	Project Name and Address Duckworth Street	Retaining Wall	
	St. John's, NL		
	Project	Sheet	
	0001 ^{Dote} 03.04.2013	A - 04	
	Scale		

Appendix E

Preliminary Soil Nailing Retaining Wall Drawings

Project No.: 0001

Project Name: Duckworth Street Retaining Wall

Document: Soil Nailing Retaining Wall Preliminary Drawing

To:

Acuren Group Inc.

112 Forest Rd

St. John's, NL, A1A 1E6

From:

Erica Soucy, Chenel Waight, Chantel Nicolle, Qiong Zhang

Group N - QCEC

Memorial University of Newofundland


St. John's, NL, A1B 3X5


Submission Date: April 03, 2013

Drawing Lists:

Figure 1. Soil Nailing Retaining Wall Plan View (Top) and Elevation View (Bottom)

Figure 2. Soil Nailing Retaining Wall Side View








General Notes	
No. Revision/Issue Date	
Firm Name and Address Quality Civil Engineering Consultants Memorial University of Newfoundland St. John's, NL, A1B 3X5	
Project Name and Address Duckworth Street Retaining Wall	
St. John's, NL	
Project Sheet	
03.04.2013 Scale	


Appendix F


S-FRAME and S-STEEL Results


























QCEC S.J. Carew Building St. John's, NL, A1B 3X5	Code Details Project: Retaining Wall Calculation Structure: Duckworth Street Retaining Filename: G:\8700\S-FRAME - RETAINING WALL\RETA Engineer: Chenel C. Waight	g Wall
Note: Member in braced frame	<i>I, shear</i> <1.0 <i>kN, moment</i> <1.0 <i>kNm</i>	HP310X110
Load Case 1 (Bending)		
Section classification $(f_y = Strong Axis Shear - (kN)$	345 MPa); Section Class = 3 8.89 (m)	<u>Clause 11</u>
-657.2 Strong axis shear strength c $A_{w} = 4743 \text{ mm}^{2};$ Strong Axis Moment - (kN-	$\frac{V_{fy}}{\phi A_w F_s} = \frac{V_{fy}}{\phi A_w 0.66F_y} = \frac{657}{972} = 0.676$	<u>Clause 13.4.1.1(a)</u>
$\begin{array}{c c} \hline 1974.8 \\ \hline 0.00 \\ \hline \\ \hline \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\$	$\frac{M_{fx}}{M_{rx}} = \frac{1975}{478} = 4.130$	<u>Clause 13.6(b)</u> > 1.00; FAIL
0.00	ion - (mm) Deflection Option: Relative to Minimum End 633.19 8.50 (m)	
Deflection check Max deflection =633.19m	n; $\frac{(L/Deflection)_{Limit}}{L/(Deflection)_{Max}} = \frac{200}{13} = > 10$	<u>Clause 6.3.1</u> > 1.00; FAIL

St	QCEC S.J. Carew Building . John's, NL, A1B 3X5	Code Detai Project: Retaining Wall C Structure: Duckworth Street H Filename: G:\8700\S-FRAME - RETAINING WA Engineer: Chenel C. V	alculations Retaining Wall ALL/RETAINING WALL.TEI	Page: 1 Date:25/03/2013		
Member Note: N Note: M	er (continuous): [29-30] r is part of group: Section 1 feglecting: axial<1.0 kN, shear<1 fember in braced frame(s). ad Case 1 (Bending + Compress		√y↓ 15.5 ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓			
	Section classification $(f_y=345 \text{ MPa});$ Governing geometrical slenderness ratio $k_x=1.00; k_y=1.00; k_xL/r_x=65.6;$ Axial Load - (kN)	Section Class = $\frac{k_y L/r_y}{200} = \frac{115}{200} =$	3 <u>Clause 11</u> 0.575	<u>4.2.1</u>		
	0.00 -131.9 Factored Compressive Resistance Check n=1.34; λ_y =1.520 Strong Axis Shear - (kN)		9 (m) 0.086	<u>3.1</u>		
	$\begin{array}{c} 0.00 \\ -428.8 \\ \hline \\ Strong axis shear strength check \\ A_w = 4743 \text{ mm}^2; \\ \hline \\ Strong Axis Moment - (kN-m) \\ \hline \\ 490.0 \\ \hline \\ \end{array}$	$\frac{V_{fy}}{\phi A_w F_s} = \frac{V_{fy}}{\phi A_w 0.66F_y} = \frac{429}{972} =$	9 (m) <u>Clause 13.</u>	<u>4.1.1(a)</u>		
	Bending Stability Check $L_u=8.50 \text{ m}; \omega_2=2.432;$	$ \underbrace{3.71}_{-237.1} \underbrace{6.6.49}_{6.6.49} \underbrace{8.50}_{-8.50} \\ \underbrace{M_{fx}}_{M_{rx}} = \frac{490}{478} = $	0 (m) 1.025 Clause 13. > 1.00; FAII			
	Axial Compression and Bending cross-se ω_{1x} =1.00; U _{1x} =1.02; Axial Compression and Bending overall ω_{1x} =1.00; U _{1x} =1.02;	$\frac{C_{f}}{\phi A F_{y}} + \frac{M_{fx}}{\phi S_{x} F_{y}} =$ member Strength Check	Clause 13. 1.076 > 1.00; FAII Clause 13. > 1.00; FAII 1.090 > 1.00; FAII	8.3(b)		
	Axial Compression and Bending later: $\omega_{1x}=1.00; U_{1x}=1.02;$	al torsional buckling strength check	1.132 Clause 13 > 1.00; FAII	. <u>8.3(c)</u>		
	0.00 Deflection check Max deflection =18.38mm;	3.57 6.60		.1		
Design Code: CAN/CSA S16-09 Steel Table : Canadian (CISC) Analysis Program: S-FRAME (Linear static analysis)S-STEEL Version 10.00.1 (Lite Version) © Copyright S-FRAME Software Inc. 1995-2012						

S	QCEC S.J. Carew Building t. John's, NL, A1B 3X5	Code Detai Project: Retaining Wall C Structure: Duckworth Street I Filename: G:\8700\S-FRAME - RETAINING WA Engineer: Chenel C. Y	alculations Retaining Wall	Page: 1 Date:25/03/2013
Membe Note: N Note: N	er (continuous): [31-32-33] er is part of group: Section 1 Neglecting: axial<1.0 kN, shear<1 Member in braced frame(s). ad Case 1 (Bending + Compress	Angle Gamma is -90.0 degrees	HP310X110	↓ 15.5 × 15.4
		Section Class =	3 <u>Clause 11</u>	0N
	Section classification $(f_y=345 \text{ MPa});$ Governing geometrical slenderness ra $k_x=1.00; k_y=1.00; k_xL/r_x=65.6;$		Clause 10.	<u>4.2.1</u>
	Axial Load - (kN) 000 -237.7 Factored Compressive Resistance Check		9 (m) <u>Clause 13.3</u>	<u>3.1</u>
	Strong Axis Shear - (kN) 000 1.88 -245.5	$\frac{C_{\rm f}}{\Phi AF_{\rm y}(1+\lambda^{2n})^{-1/n}} = \frac{C_{\rm f}}{\Phi A(121 \text{ MPa})} = \frac{238}{1536} =$ $\frac{1165.0}{8149^{-1.10}} = \frac{5.07}{50.7} = 8.50$	0.155 9 (m)	
	Strong axis shear strength check $A_w = 4743 \text{ mm}^2$; Strong Axis Moment - (kN-m) 155.1 0.00 0.82 1.88 2.2	$\frac{V_{fy}}{\phi A_w F_s} = \frac{V_{fy}}{\phi A_w 0.66F_y} = \frac{245}{972} =$ 993.49 4.34 519.5 8.50 8.50	0.253 <u>Clause 13.4</u>	<u>4.1.1(a)</u>
	$\begin{array}{c} -67.4 \\ \hline \\ \text{Bending Stability Check} \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\$	$\frac{M_{fx}}{M_{rx}} = \frac{155}{478} =$	0.324 <u>Clause 13.</u>	<u>6(b)</u>
	Axial Compression and Bending cross-set ω_{1x} =1.00; U _{1x} =1.04;		Clause 13.	<u>8.3(a)</u>
	Axial Compression and Bending overall ω_{1x} =1.00; U _{1x} =1.04;		Clause 13.8	<u>8.3(b)</u>
	Axial Compression and Bending lateral $\omega_{1x}=1.00; U_{1x}=1.04;$	torsional buckling strength check $\frac{C_{f}}{C_{ry}} + \frac{U_{1x} M_{fx}}{M_{rx}} =$	Clause 13	<u>8.3(c)</u>
	S-FRAME Section z Deflection - (mm) 2.19 0.00 1.92	Deflection Option: Relative to Minimum End	8 9 (m)	
	Deflection check Max deflection =2.19mm;	$\frac{(L/Deflection)_{Linit}}{L/(Deflection)_{Max}} = \frac{200}{3876} =$	0.052 <u>Clause 6.3.</u>	1
	ode: CAN/CSA S16-09 le :Canadian (CISC)		S-S	TEEL

Analysis Program: S-FRAME (Linear static analysis)

S	QCEC S.J. Carew Building t. John's, NL, A1B 3X5	Code Detai Project: Retaining Wall C Structure: Duckworth Street I Filename: G:\8700\S-FRAME - RETAINING WA Engineer: Chenel C. V	Page: 1 Date:25/03/2013	
Note: N Note: N	er: 7 r is part of group: Section 1 Veglecting: axial<1.0 kN, shear<1 Member in braced frame(s). ad Case 1 (Bending)	S-FRAME Section is HP310X110 .0 kN, moment<1.0 kNm Angle Gamma is -90.0 degrees	HP310X110	x 15.4
		Section Class -	3 Clause 11	——————————————————————————————————————
	Section classification (f _y =345 MPa); Strong Axis Shear - (kN) 0.00 -519.9	Section Class =	3 <u>Clause 11</u> 9 (m)	
	Strong axis shear strength check $A_w = 4743 \text{ mm}^2$; Strong Axis Moment - (kN-m) 1387.5	$\frac{V_{fy}}{\phi A_w F_s} = \frac{V_{fy}}{\phi A_w 0.66F_y} = \frac{520}{972} =$		<u>1.1(a)</u>
	0.00 Bending Stability Check		0 (m) <u>Clause 13.60</u> > 1.00; FAIL	<u>b)</u>
	L _u =7.50 m; ω_2 =2.500; S-FRAME Section z Deflection - (mm) $\overline{\boldsymbol{0.00}}$	$\frac{M_{fx}}{M_{rx}} = \frac{1388}{478} =$ Deflection Option: Relative to Minimum End 348 7.56		
	Deflection check Max deflection =348.74mm;	$\frac{(L/Deflection)_{Limit}}{L/(Deflection)_{Max}} = \frac{200}{22} =$	9.300 Clause 6.3.1 > 1.00; FAIL	L

Design Code: CAN/CSA S16-09 Steel Table : Canadian (CISC) Analysis Program: S-FRAME (Linear static analysis)

St	QCEC S.J. Carew Building t. John's, NL, A1B 3X5	Code Detai Project: Retaining Wall C Structure: Duckworth Street I Filename: G:\8700\S-FRAME - RETAINING WA Engineer: Chenel C. V	alculations Retaining Wall ALL/RETAINING WALL.TEI	Page: 1 Date:25/03/2013
Membe Note: N Note: M	er (continuous): [8-9] r is part of group: Section 1 Veglecting: axial<1.0 kN, shear<1 Member in braced frame(s). ad Case 1 (Bending + Comprese	Angle Gamma is -90.0 degrees	HP310X110	₩ 15.5 x 15.4
	Section classification $(f_v=345 \text{ MPa});$	Section Class =	3 Clause 11	0
	Governing geometrical slenderness ratio			4.2.1
	$k_x = 1.00; k_y = 1.00; k_x L/r_x = 57.8;$	$\frac{k_y L/r_y}{200} = \frac{101}{200} =$	0.507	<u>4.2.1</u>
	Axial Load - (kN)			
	-112.8	7.50	0 (m)	
	Factored Compressive Resistance Check		Clause 13.	3 1
		C C 112	0.061	<u></u>
	0.00 -324.6	3.11 355 7 7.50	0 (m)	
	Strong axis shear strength check		Clause 13.	4.1.1(a)
	$A_{w} = 4743 \text{ mm}^{2};$	$\frac{V_{fy}}{\phi A_w F_s} = \frac{V_{fy}}{\phi A_w 0.66 F_v} = \frac{325}{972} =$	0.334	
	Strong Axis Moment - (kN-m) 313 4 0.00 1.27	3.11 5.2 1 .50 7.50 -151.1	0 (m)	
	Bending Stability Check $L_u=7.50 \text{ m}; \omega_2=2.464;$	$\frac{M_{fx}}{M_{rx}} = \frac{313}{478} =$	<u>Clause 13.</u> 0.656	<u>6(b)</u>
	Axial Compression and Bending cross-set ω_{1x} =1.00; U _{1x} =1.01;	C M	0.690 <u>Clause 13.</u>	<u>8.3(a)</u>
	Axial Compression and Bending overall ω_{1x} =1.00; U _{1x} =1.01;	member Strength Check $\frac{C_f}{C_{rx}} + \frac{U_{1x}M_{fx}}{\phiS_xF_y} =$	<u>Clause 13.</u> 0.699	<u>8.3(b)</u>
	Axial Compression and Bending later ω _{1x} =1.00; U _{1x} =1.01;		Clause 13	. <u>8.3(c)</u>
	S-FRAME Section z Deflection - (mm)	Deflection Option: Relative to Minimum End 8.73 3.02 5.66 7.50		
		-7.3		
	Deflection check Max deflection =8.73mm;	$\frac{(L/Deflection)_{Limit}}{L/(Deflection)_{Max}} = \frac{200}{859} =$	0.233	.1
Design Ca	ode: CAN/CSA S16-09			
	e : Canadian (CISC)		S-S	TEEL
	Program: S-FRAME (Linear sta	tic analysis)		00.1 (Lite Version) ME Software Inc. 1995-2012

QCEC S.J. Carew Building St. John's, NL, A1B 3X5	Code Detai Project: Retaining Wall Ca Structure: Duckworth Street F Filename: G:\8700\S-FRAME - RETAINING WA Engineer: Chenel C. V	alculations Retaining Wall ALL/RETAINING WALL.TEL Page: 1
tember (continuous): [10-11-12] ember is part of group: Section 1 pte: Neglecting: axial<1.0 kN, shear< pte: Member in braced frame(s). Load Case 1 (Bending + Compre	Angle Gamma is -90.0 degrees	HP310X110 308 15.5 15.4 15.4
Section classification $(f_y=345 \text{ MPa});$	Section Class =	3 <u>Clause 11</u>
Governing geometrical slenderness r k _x =1.00; k _y =1.00; k _x L/r _x =57.8;	atio $\frac{k_{\rm y} {\rm L/r_y}}{200} = \frac{101}{200} =$	0.507
-208.7		9 (m)
Strong Axis Shear - (kN)	$\frac{C_{f}}{C_{ry}} = \frac{C_{f}}{\phi A F_{y}(1+\lambda^{2n})^{-1/n}} = \frac{C_{f}}{\phi A (145 \text{ MPa})} = \frac{209}{1840} =$ 4.8 50 50 50 50 50 50 50 50 50 50 50 50 50	0.113 <u>Clause 13.3.1</u>
$\frac{-158.5}{158.5} -1$ Strong axis shear strength check $A_{w} = 4743 \text{ mm}^{2};$ Strong Axis Moment - (kN-m)	11.2 $\frac{V_{fy}}{\phi A_w F_s} = \frac{V_{fy}}{\phi A_w 0.66F_y} = \frac{158}{972} =$	0.163 Clause 13.4.1.1(a)
Bending Stability Check $L_u=7.50 \text{ m}; \omega_2=2.343;$	$\frac{8}{502.99} \underbrace{1000}_{-31.7} \underbrace{4.945.50}_{7.50} 7.50$	0 (m) <u>Clause 13.6(b)</u> 0.162
Axial Compression and Bending cross- ω_{1x} =1.00; U _{1x} =1.03;	sectional Strength Check	0.214 <u>Clause 13.8.3(a)</u>
Axial Compression and Bending overa ω_{1x} =1.00; U _{1x} =1.03;		0.231
Axial Compression and Bending latera ω_{1x} =1.00; U _{1x} =1.03;	$\frac{C_{f}}{C_{ry}} + \frac{U_{1x} M_{fx}}{M_{rx}} =$	0.280 <u>Clause 13.8.3(c)</u>
S-FRAME Section z Deflection - (mm)	Deflection Option: Relative to Minimum End 1.27 3.92	3 9 (m)
		<u>Clause 6.3.1</u>

Design Code: CAN/CSA S16-09 Steel Table : Canadian (CISC) Analysis Program: S-FRAME (Linear static analysis)

S	QCEC S.J. Carew Building t. John's, NL, A1B 3X5	Code Detai Project: Retaining Wall CA Structure: Duckworth Street H Filename: G:\8700\S-FRAME - RETAINING WA Engineer: Chenel C. V	alculations Retaining Wall ALL/RETAINING WALL.TEL	Page: 1 Date:25/03/2013
Note: N Note: N	er is part of group: Section 1 Neglecting: axial<1.0 kN, shear<1 Member in braced frame(s).	S-FRAME Section is HP310X110 .0 kN, moment<1.0 kNm Angle Gamma is -90.0 degrees	HP310X110	x 15.5 x 15.4
	pad Case 1 (Bending)			——————————————————————————————————————
	Section classification $(f_y=345 \text{ MPa});$	Section Class =	3 <u>Clause 11</u>	
	Strong Axis Shear - (kN) 0.00 -398.6 Strong axis shear strength check $A_w = 4743 \text{ mm}^2$;	$\frac{V_{fy}}{\phi A_w F_s} = \frac{V_{fy}}{\phi A_w 0.66F_y} = \frac{399}{972} =$	9 (m) 0.410	<u>1.1(a)</u>
	Strong Axis Moment - (kN-m) 929.6 0.00 Bending Stability Check	6.50	9(m)	b)
	L_{μ} =6.50 m; ω_2 =2.500;	$\frac{M_{fx}}{M_{rx}} = \frac{930}{478} =$	1.944 <a> <a> <a> <a> <a> <br< td=""><td><u>0)</u></td></br<></br></br></br></br></br></br></br></br></br></br></br></br></br></br></br></br></br></br></br></br></br></br></br></br></br>	<u>0)</u>
	S-FRAME Section z Deflection - (mm)	Deflection Option: Relative to Minimum End		
	Deflection check Max deflection =177.08mm;	$\frac{(L/Deflection)_{Limit}}{L/(Deflection)_{Max}} = \frac{200}{37} =$	5.449 Clause 6.3.1 > 1.00; FAIL	<u> </u>

QCEC S.J. Carew Building St. John's, NL, A1B 3X5	Code Detai Project: Retaining Wall C Structure: Duckworth Street I Filename: G:\8700\S-FRAME - RETAINING WA Engineer: Chenel C. V	alculations Retaining Wall ALL/RETAINING WALL.TEL	Page: 1 Date:25/03/2013			
Member (continuous): [14-15] Member is part of group: Section 1 Note: Neglecting: axial<1.0 kN, shear<1	Angle Gamma is -90.0 degrees	HP310X110	x 15.4			
Section classification $(f_v = 345 \text{ MPa});$	Section Class =					
Governing geometrical slenderness ra		Clause 10.4	.2.1			
$ \begin{array}{c} \hline \\ k_x = 1.00; k_y = 1.00; k_x L/r_x = 50.1; \\ \hline \\ \hline \\ Axial Load - (kN) \end{array} $	$\frac{k_{y} L/r_{y}}{200} = \frac{88}{200} =$	0.440				
<i>0.00</i> -95.8	6.50	0 (m)				
	$\frac{C_{f}}{V_{ry}} = \frac{C_{f}}{\phi A F_{y} (1 + \lambda^{2n})^{-1/n}} = \frac{C_{f}}{\phi A (174 \text{ MPa})} = \frac{96}{2212} = 0$	0.043	1			
Strong Axis Shear - (kN)	2.49 45807 6.50	0 (m)				
Strong axis shear strength check $A_w = 4743 \text{ mm}^2$;	$\frac{V_{fy}}{\phi A_w F_s} = \frac{V_{fy}}{\phi A_w 0.66F_y} = \frac{233}{972} =$	0.239 <u>Clause 13.4.</u>	<u>1.1(a)</u>			
Strong Axis Moment - (kN-m) 182.8 <i>0.00</i> <i>1.03</i>	2.49 4.124.50 6.50 -86.5	0 (m)				
Bending Stability Check $L_u=6.50 \text{ m}; \omega_2=2.500;$	$\frac{M_{fx}}{M_{rx}} = \frac{183}{478} =$	0.382 <u>Clause 13.6(</u>	<u>b)</u>			
Axial Compression and Bending cross-s ω_{1x} =1.00; U _{1x} =1.01;		Clause 13.8.	<u>3(a)</u>			
Axial Compression and Bending overall ω_{1x} =1.00; U _{1x} =1.01;	· · · · ·	Clause 13.8.	<u>3(b)</u>			
Axial Compression and Bending lateral ω_{1x} =1.00; U _{1x} =1.01;	$\frac{C_{f}}{C_{ry}} + \frac{U_{1x} M_{fx}}{M_{rx}} =$	0.429	<u>3(c)</u>			
	Deflection Option: Relative to Minimum End 3.62					
Deflection check		<u>Clause 6.3.1</u>				
Max deflection =3.62mm;	$\frac{(L/Deflection)_{Limit}}{L/(Deflection)_{Max}} = \frac{200}{1795} =$	0.111				
Design Code: CAN/CSA S16-09 Steel Table : Canadian (CISC) Analysis Program: S-FRAME (Linear sta						

QCEC S.J. Carew Building St. John's, NL, A1B 3X5	Code Detai Project: Retaining Wall C Structure: Duckworth Street D Filename: G:\8700\S-FRAME - RETAINING WA Engineer: Chenel C.	alculations Retaining Wall	ALL.TEL Page: 1 Date:25/03/2013
Member (continuous): [16-17-18] Member is part of group: Section 1 Note: Neglecting: axial<1.0 kN, shear<1	Angle Gamma is -90.0 degrees	HP3102 7	X110 15.5 308 15.4
Section classification $(f_v = 345 \text{ MPa});$	Section Class =	3 Clau	use 11
Governing geometrical slenderness ra		-	use 10.4.2.1
$ k_x=1.00; k_y=1.00; k_x L/r_x=50.1;$	$\frac{k_{y} L/r_{y}}{200} = \frac{88}{200} =$	0.440	<u>use 10.4.2.1</u>
Axial Load - (kN) 0.00 -181.3		0 (m)	
Factored Compressive Resistance Check n=1.34; λ_y =1.162 $\frac{C}{C}$	C C 191	0.082	<u>use 13.3.1</u>
Strong Axis Shear - (kN) 67.3 7.50 -84.6 -107.1 Strong axis shear strength check	-50.7	0 (m)	use <u>13.4.1.1(a)</u>
A _w = 4743 mm ; Strong Axis Moment - (kN-m) 39.8 0.00	$\frac{V_{fy}}{\phi A_w F_s} = \frac{V_{fy}}{\phi A_w 0.66F_y} = \frac{107}{972} =$ 2.86 3.98 4.50 6.50 -38.4	0 (m)	
Bending Stability Check $L_u=6.50 \text{ m}; \omega_2=1.399;$	$\frac{M_{fx}}{M_{rx}} = \frac{40}{476} =$	0.084	<u>use 13.6(b)</u>
Axial Compression and Bending cross-s ω_{1x} =1.00; U _{1x} =1.02;	ectional Strength Check $\frac{C_{f}}{\phi \ A \ F_{y}} + \frac{M_{fx}}{\phi \ S_{x} \ F_{y}} =$	0.127	use <u>13.8.3(a)</u>
Axial Compression and Bending overall ω_{1x} =1.00; U _{1x} =1.02;	member Strength Check $\frac{C_{f}}{C_{rx}} + \frac{U_{1x} M_{fx}}{\phi S_{x} F_{y}} =$	0.136	use 13.8.3(b)
Axial Compression and Bending lateral ω_{1x} =1.00; U _{1x} =1.02; S-FRAME Section z Deflection - (mm)		Clai	<u>use 13.8.3(c)</u>
0.00	1.27	2 0 (m)	
Deflection check		Clar	use 6.3.1
Max deflection =1.27mm;	$\frac{(L/Deflection)_{Limit}}{L/(Deflection)_{Max}} = \frac{200}{5103} =$	0.039	

Design Code: CAN/CSA S16-09 Steel Table : Canadian (CISC) Analysis Program: S-FRAME (Linear static analysis)

Appendix G

Design Anchor Capacity Estimates

Design Anchor Capacity Estimates - New Parking Garage and Condominium Henry Bell Developments Limited, St. John's, NL

Geotechnical Resistance Factor = ϕ

0.4

Ultimate Anchor Capacity $P_{ult} = \alpha_{bond} \times PI \times Diam_{socket} \times bond-length$

Factored Ultimate Anchor Capacity $\Phi P_{ult} = \Phi \times \alpha_{bond} \times Pl \times Diam_{socket} \times bond-length$

 $\Phi_{Axial Tension - empircal data} = 0.3$ Current analyses - designing using ultimate bond stress based on rock and soil types

 $\phi_{Axial Tension - load test} =$

*ext

Alternative approach - design to be confirmed prior to permanent anchor construction by load testing


Basis For Geotechnical Resistance Factor	Bond	Bond	Ultimate	Ultimate	Factored Ultimate	
	Diameter	Length	Bond Stress	Anchor Capacity	Anchor Capacity	Material Type Over Bonded Length
	mm	m	α_{bond} , kPa	P _{ult} , kN	φΡ _{ult} , kN	
	168	3.0	300	475	143	
Empirical Design	168	4.5	300	713	214	Anchor bonded in random sand and gravel fill
Approach	168	3.0	500	792	238	
φ = 0.3	168	4.5	500	1188	356	Anchor bonded in till or severely fractured bedroo
φ. 0.5	168	3.0	800	1267	380	
	168	4.5	800	1900	570	Anchor bonded in fractured sandstone bedrock
Design Confirmed by	168	3.0	300	475	190	
Load Testing Prior To Production Anchor Construction	168	4.5	300	713	285	Anchor bonded in random sand and gravel fill
	168	3.0	500	792	317	
	168	4.5	500	1188	475	Anchor bonded in till or severely fractured bedrock
$\phi = 0.4$	168	3.0	800	1267	507	
φ - 0.4	168	4.5	800	1900	760	Anchor bonded in fractured sandstone bedrock

Appendix H

Soldier Pile Retaining Wall Calculations




Υ=	20.5	KN/m ³
Ka=	0.26	
φ=	36	0
q =	12	kPa
H =	8.5	m



Find pressure o	n retaining wall fr	om surcharge (q):
i ina pressare o		

Find active soil pressure on retaining wall:




MAX allowable deflection (.005H) =

42.5 mm

Reference: US Army Corps of Engineers




20.5	KN/m ³
0.26	
36	0
12	kPa
7.5	m
	0.26 36 12



Find pressure on retaining wall from surcharge (q):

Find active soil pressure on retaining wall:

p2 = Ka* Y * H =	39.975 kPa
p=	001070 10 0




MAX allowable deflection (.005H) = 37.5 mm

Reference: US Army Corps of Engineers

32.5 mm




Υ=	20.5	KN/m ³
Ka=	0.26	
φ=	36	0
q =	12	kPa
H =	6.5	m



Find pressure on	retaining wall fro	m surcharge (q):

Find active soil pressure on retaining wall:



MAX allowable deflection (.005H) =

Reference: US Army Corps of Engineers


Tieback Design Calculations

Assumption:

- 1 Non-cohensive soil
- 2 Groundwater level is neglectable
- 3 Non-inclined backfill
- 4 Use φ' as φ'_{cs} and $\,\varphi'_{p}$

Notes:

- 1 Using Rankine's Equation
- 2 Critical design depth equals to 8.41 meters
- 3 Using Safety Factor equals to 1.5
- 4 Drilled hole diameter = 550mm



Reference: US Army Corps of Engineers

For Hc = 8.5m

			27 deg =	0.471239 rad
failure plane				
x (m)		у		
	0	0)	
	1	1.962611		
	2	3.925221		
	3	5.887832		
	4	7.850442		

5 9.813053





First Tiebad	ck	30 deg =	0.523599 rad
x (m)	y (m)		
0	6.5		
1	5.92265		
2	5.345299		
3	4.767949		
4	4.190599		
5	3.613249		
Second Tie	back	30 deg =	0.523599
x (m)	y (m)	-	
0	3.5		
1	2.92265		
2	2.345299		
3	1.767949		
4	1.190599		
5	0.613249		
From grap	n:		
First tiebac	k intercept	s failure pla	ne at:
x =	2.55	m	
y =	5	m	
Length of tieback from face of wall to theoretical failure plane =			
Second tiek	back interc	epts failure j	plane at:
x =	1.4	-	
y =	2.7	m	
Length of t	ераск ггоп	n face of wa	ll to theoretical failure plane =
Minimum anchor free length			
The greater of:			
_			all to theoretical failure plane + H/5
ii) length of tieback from face of wall to theoretical failure plane + 1.5			
Reference: US Army Corps of Engineers			
First Tieba	ck		

FILST HEDACK				
i) 2.9m + 8.5m/5 =	4.6 m	Anchor free length =	4.5 m	**
ii) 2.9m + 1.5m =	4.4 m			
Second Tieback		Anchor free length =	3.5 m	
			0.0	
i) 1.7m + 8.5m/5 =	3.3 m			

2.9 m


1.6 m



			Lengths in t	the:
Bond length is either 3.0m or 4.5m depe	<u>X-dir (m)</u>	<u>Y-dir (m)</u>		
Total anchor length (First Tieback) =		7.5 m	6.5	3.8
	OR	<mark>9</mark> m	7.8	4.5
Total anchor length (Second Tieback) =		6.5 m	5.6	3.3
	OR	8 m	6.9	4.0

NOTE: Available horizontal distance from soldier pile wall to buildings across Henry St. Is approximately 8.5m

Therefore, the maximum tie lengths will be ok for the site




Tieback Design Calculations

Assumption:

- 1 Non-cohensive soil
- 2 Groundwater level is neglectable
- 3 Non-inclined backfill
- 4 Use φ' as φ'_{cs} and φ'_{p}

Notes:

- 1 Using Rankine's Equation
- 2 Critical design depth equals to 8.41 meters
- 3 Using Safety Factor equals to 1.5
- 4 Drilled hole diameter = 550mm



Reference: US Army Corps of Engineers

For Hc = 7.5m

			27 deg =	0.471239 rad
failure p	lan	e		
x (m)		у		
	0	0		
	1	1.962611		
	2	3.925221		
	3	5.887832		
	4	7.850442		
	5	9.813053		
First Tie	bac	k	30 deg =	0.523599 rad
x (m)		y (m)		
	0	5.5		
	1	4.92265		
	2	4.345299		
	3	3.767949		





4	3.190599

5 2.613249

Second Tieback $30 \text{ deg} = 0.523599$ x (m)y (m)02.511.9226521.34529930.76794940.1905995-0.38675					
From graph: First tieback intercepts failure plane at: x = 2.15 m y = 4.2 m Length of tieback from face of wall to theoretical	al failure plane = 2.	5 m			
Second tieback intercepts failure plane at: x = 1 m y = 1.9 m Length of tieback from face of wall to theoretica	al failure plane = 1.	2 m			
Minimum anchor free length The greater of: i) length of tieback from face of wall to theoreti ii) length of tieback from face of wall to theoret Reference: US Army Corps of Engineers					
First Tieback					
i) $2.5m + 7.5m/5 = 4.0$	Anchor free length =	4	m		
ii) 2.5m + 1.5m = 4.0					
Second Tieback	Anchor free length =	3	m		
i) 1.1m + 7.5m/5 = 2.7 ii) 1.1m + 1.5m = 2.7					
Lengths in the:Bond length is either 3.0m or 4.5m depending on required capacity:X-dir (m)Y-dir (m)					
Total anchor length (First Tieback) =	7 m	6.1	3.5		

OR

8.5 m

7.4


Tieback Design Calculations



Total anchor length (Second Tieback) =		6 m	5.2	3.0
	OR	7.5 m	6.5	3.8

NOTE: Available horizontal distance from soldier pile wall to buildings across Henry St. Is approximately 8.5m

Therefore, the maximum tie lengths will be ok for the site




Tieback Design Calculations

Assumption:

- 1 Non-cohensive soil
- 2 Groundwater level is neglectable
- 3 Non-inclined backfill
- 4 Use φ' as φ'_{cs} and φ'_{p}

Notes:

- 1 Using Rankine's Equation
- 2 Critical design depth equals to 8.41 meters
- 3 Using Safety Factor equals to 1.5
- 4 Drilled hole diameter = 550mm



Reference: US Army Corps of Engineers

For Hc = 6.5m

			27 deg =	0.471239 rad
failure p	lan	e		
x (m)		у		
	0	0		
	1	1.962611		
	2	3.925221		
	3	5.887832		
	4	7.850442		
	5	9.813053		
First Tie	bac	k	30 deg =	0.523599 rad
x (m)		y (m)		
	0	4.5		
	1	3.92265		
	2	3.345299		
	3	2.767949		





4	2.190599
-	4 64 9 9 4 9

5	1.613249	
5	1.015245	

Second Tiel	back	30 deg =	0.523599			
x (m)	y (m)					
0	1.5					
	0.92265					
2	0.345299					
3	-0.23205					
	-0.8094					
5	-1.38675					
From graph	1:					
		failure plar	ne at:			
x =	1.8	-				
y =	3.2	m				
,						
Length of ti	eback from	face of wal	l to theoretical failure	plane =	2.1 m	
	a ali interna	nto foiluna m				
		pts failure p	blane at:			
x =	0.6					
y =	1.2	m				
Length of ti	eback from	face of wal	l to theoretical failure	plane =	0.7 m	
Minimum a		length				
The greater		с с				
-			all to theoretical failur			
II) length of	tieback fro	m face of w	all to theoretical failu	re plane + 1.5		
Reference:	US Army Co	orps of Engi	neers			
	,					
First Tiebac	:k					
i) 2.1m + 6.	5m/5 =	3.4		Anchor free lengt	h =	3.5 m
ii) 2.1m + 1	.5m =	3.6				
Second Tiel	back			Anchor free lengt	h –	2.5 m
i) 0.7m + 6.		2.0		Anchor free lengt	n –	2.5 11
ii) 0.7m + 0.	-	2.0				
ii) 0.7111 + 1.	- 111	۷.۷				

Bond length is either 3.0m or 4.5m dep	required capacity:	Lengths in t <u>X-dir (m)</u>	he: <u>Y-dir (m)</u>	
Total anchor length (First Tieback) =	OR	6.5 m 8 m	5.6 6.9	3.3 4.0


**



Total anchor length (Second Tieback) =		5.5 m	4.8	2.8
	OR	7 m	6.1	3.5

NOTE: Available horizontal distance from soldier pile wall to buildings across Henry St. Is approximately 8.5m

Therefore, the maximum tie lengths will be ok for the site



Determine Embedment Depth from S-Frame Analysis




NOTE:

Use critical section (8.5m) to determine ebedment depth Embedment depth is based on the shear force at the base of the retaining wall

The equation below is from the US Army Corps of Engineers State of the Practice in the Design of Tall, Stiff, and Flexible Tieback Retaining Walls

$$F_{p} = \gamma d^{2} \left[\frac{K_{0}d\tan\phi\sin\beta}{\tan(\beta-\phi)\cos\alpha} + \frac{\tan\beta}{\tan(\beta-\phi)} \left(\frac{b}{2} + \frac{d}{3}\tan\beta\tan\alpha \right) + \frac{K_{0}d\tan\beta}{3} (\tan\phi'\sin\beta - \tan\alpha) \right]$$



Solve the above equation for d:

D= **1.57** m

D x FS = **2.4** m



Therefore, use an embedment depth of 3.0 meters for all soldier piles



Timber Lagging Design

Assumptions

- 1. Use sawn timbers as material
- 2. Members intend to support permannent loads
- 3. Single member configuration
- 4. Wet service condition
- 5. Untreated wood
- 6. Species Indentification is SPF Grade No.1 and No.2
- 7. Members are restricted against lateral displacement and rotation at their end
- 8. Not notched
- 9. Simple supproted beam with a normal distribted load
- 10. Uniform distributed load, no intermediate support
- 11. No live load is considered


Geotechnical Parameters for design:

Υ=	20.5	KN/m3
φ'=	0.628	rad
Ka=	0.26	
Кр=	3.8	
Ko=	0.41	
q=	12	kPa

Wood Lagging Design Criteria:

36 Degree

00	, 0	0		
Length (L)	3	m	0.0254 in	
Width (d)	0.25	m		
		-		Unit
Factored L	oad: w=	=(Ka*Ƴ*(I	H-d/2)+Ka*q)*d*0.6*1.25	KN/m
Moment: N	∕l=w*L⁄	`2/8		KN.m
Section Mo	m^3			
Bending st	КРа			





Load Analy	/sis		250*75				250*100				250*150				250*200			
			b=	0.25	m		b=	0.25	m		b=	0.25	m		b=	0.25	m	
			t=	0.075	m		t=	0.1	m		t=	0.15	m		t=	0.2	m	
Depth (m)	w	М	S	σ/1000	fb	Check	S	σ/1000	Fr		S	σ/1000	Fr	Check	S	σ/1000	Fr	Check
0.50	0.96	1.08	0.00	4.61	8.47	Pass	0.00	2.59	8.47	Pass	0.00	1.15	8.47	Pass	0.00	0.65	8.47	Pass
1.00	1.46	1.64	0.00	7.01	8.47	Pass	0.00	3.94	8.47	Pass	0.00	1.75	8.47	Pass	0.00	0.99	8.47	Pass
1.50	1.96	2.20	0.00	9.40	8.47	Fail	0.00	5.29	8.47	Pass	0.00	2.35	8.47	Pass	0.00	1.32	8.47	Pass
2.00	2.46	2.77	0.00	11.80	8.47	Fail	0.00	6.64	8.47	Pass	0.00	2.95	8.47	Pass	0.00	1.66	8.47	Pass
2.50	2.96	3.33	0.00	14.20	8.47	Fail	0.00	7.99	8.47	Pass	0.00	3.55	8.47	Pass	0.00	2.00	8.47	Pass
3.00	3.46	3.89	0.00	16.60	8.47	Fail	0.00	9.34	8.47	Fail	0.00	4.15	8.47	Pass	0.00	2.33	8.47	Pass
3.50	3.96	4.45	0.00	19.00	8.47	Fail	0.00	10.69	8.47	Fail	0.00	4.75	8.47	Pass	0.00	2.67	8.47	Pass
4.00	4.46	5.01	0.00	21.40	8.47	Fail	0.00	12.04	8.47	Fail	0.00	5.35	8.47	Pass	0.00	3.01	8.47	Pass
4.50	4.96	5.58	0.00	23.79	8.47	Fail	0.00	13.38	8.47	Fail	0.00	5.95	8.47	Pass	0.00	3.35	8.47	Pass
5.00	5.46	6.14	0.00	26.19	8.47	Fail	0.00	14.73	8.47	Fail	0.00	6.55	8.47	Pass	0.00	3.68	8.47	Pass
5.50	5.96	6.70	0.00	28.59	8.47	Fail	0.00	16.08	8.47	Fail	0.00	7.15	8.47	Pass	0.00	4.02	8.47	Pass
6.00	6.46	7.26	0.00	30.99	8.47	Fail	0.00	17.43	8.47	Fail	0.00	7.75	8.47	Pass	0.00	4.36	8.47	Pass
6.50	6.96	7.83	0.00	33.39	8.47	Fail	0.00	18.78	8.47	Fail	0.00	8.35	8.47	Pass	0.00	4.70	8.47	Pass
7.00	7.46	8.39	0.00	35.79	8.47	Fail	0.00	20.13	8.47	Fail	0.00	8.95	8.47	Fail	0.00	5.03	8.47	Pass
7.50	7.96	8.95	0.00	38.19	8.47	Fail	0.00	21.48	8.47	Fail	0.00	9.55	8.47	Fail	0.00	5.37	8.47	Pass
8.00	8.46	9.51	0.00	40.58	8.47	Fail	0.00	22.83	8.47	Fail	0.00	10.15	8.47	Fail	0.00	5.71	8.47	Pass
8.50	8.95	10.07	0.00	42.98	8.47	Fail	0.00	24.18	8.47	Fail	0.00	10.75	8.47	Fail	0.00	6.04	8.47	Pass

Recommendation:

QCEC recommend to use 250*100mm SPF Grade No.1 Timber for the first 2.5 meters and change to double 250*100 SPF Grade No.1 Timber for depth deeper than 2.5 meters.

Appendix I

Rigid Gravity Retaining Wall Calculations

Massive Rigid Retaining Wall Design



Note Design for the left hand side of the retaining wall only. The wall is designed to be 15 meters (14.42m) long. Specification refers to the "Design Criterias". The design height was used as 6 meters for the whole length.

Assumptions:

1 Natural backfill

2 Groundwater level is seasonal

3 Groundwater level is below the base of the gravity retaining wall

4 Wall friction = 0

5 Effective friciton angle ϕ' provided in the geotechnical report can be used as both critical state friction angle ϕ'_{cs} and peak friction angle ϕ'_p

6 $\theta'_{b}=2/3^{*}\theta'_{cs}$ (should be between $1/2^{*}\theta'_{cs}$ to $2/3^{*}\theta'_{cs}$)

Notes:

1 Using Rankine's Method

2 Factor of safety for translation equals to 1.5

3 Factor of safety for bearing capacity equals to 3

4 With wall friction, the factor of safety against translation is greater than without friction

Geotechnical Parameters for design:

Υ=		20.5	KN/m ³		Ybase=	20.	5 KN/m ³				
							36	Degree		36	Degree
ф'=		0.628	rad	36	Degree	φ'cs=	0.628	rad <mark>oʻ</mark> l)=	0.628	rad
Ka=		0.26									
Кр=		3.8									
Ko=		0.41									
Desig	n Criterias:										
	Design Length=15m										
q=		12	kPa								
a/b=		1.00		а	b	С					
				1		1 1.41	4				
T=		0.5	m	Unit Thickr	ו	1 m					
Ho=		4	m	b1=	1	.5 m	x1=	1.000 m	e	Э' _b =	0.419 rad
B=			m	b2=		.5 m	x2=	1.750 m	ſ	Min.(FS) _T =	1.5
Υc=		24	KN/m ³	A=		2 m ²	Za=	1.333333 m	ſ	Min.(FS) _B =	3
Calcu	lations:						Zb=	2 m			



1	Determine the laterial force			
Pasoil	= 1/2*Ka*Υ*Ho ²	=	42.640 KN	
Pasuro	:Ka*q*Ho	=	12.480 KN	
Pah=	Pasoil*b/c+Pasurcharge	=	42.631 KN	
Pav=	Pasoil*a/c	=	30.151 KN	
2	Determing the wall stability			
Consia	ler a unit lenth of wall			
W1=	1/2*b1*Ho*Yc	=	72.000 KN	
W2=	b2*Ho*Yc	=	48.000 KN	
W=	W1+W2	=	120.000 KN	
Mo=	W1*x1+W2*x2+Pav*B-(Pah-Pas	51 =	151.141 kNm	
Rz=	W+Pav	=	150.151 KN	
xbar=	Mo/Rz	=	1.007 m	
3	Base resistance			
T=	Rz*tan(θ' _b)	=	66.852 KN	
4	Factor of Safety for Translation			
(FS) _⊤ =	T/Pah	=	1.568	Safe against translation
5	Checking for rotational stability			
e=	B/2-xbar	=	0.007 m	
B/6=	B/6	=	0.333 m	Safe against rotation
6	Checking for bearing capacity			

Notes:

1 Since the resultant vertical force is located within the middle one-third, tension will not be developed in the soil.

2 The maximum stress occurs at A

3 The groundwater level is below B=2m from the base, so groundwater would have no effect on the bearing capacity.


σ _{max} = Rz/	/A*(1+6*e/B)	=	76.560 Kpa
H= Pal	h	=	42.631 KN
Vn= Rz		=	150.151 KN
ω= tar	n ^{⁻1} (H/Vn)	=	3.427 rad
4 The	e base of the wall can be take	n as a strip, s	surface foundation, that is B/L approaching 0, and Df=0.
B'= B-2	2e	=	1.987 m
B'/L'= B'/	/L'	=	0.000
n= (2+	+B'/L')/(1+B'/L')	=	2.000
i _r = (1-	-H/Vn)^(n+1)	=	0.367
N _Y = 0.1	1054*e^(9.6*¢' _p)	=	43.898

q _u =	0.5*Υ*Β'*Ν _Υ *i _Υ	=	328.252 KPa
(FS) _B =	q_u/σ_{max}	=	4.287518

Safe against bearing







Appendix J

Cost Estimate

STEEL - PRELIMINARY									
Wall Length	63	m	Drilling (Soil) Length	176	m				
# of Piles	22		Drilling (Rock) Length	44	m				
Lenth of Pile (avg)	10	m	Drilling - Soil Price	\$180.00	/m				
Total Pile Length	220	m	Drilling - Rock Price	\$550.00	/m				
Weight of Steel	110	kg/m	Drilling Cost-Soil:	\$31,680.00					
Total Weight of Steel	24200	kg	Drilling Cost-Rock:	\$24,200.00					
Steel Weight Price:	\$3.50	/kg	Tie-Back						
Total Steel Cost:	\$84,700.00		Length (un-grouted)	3.5	m				
			Length (grouted)	4.5	m				
Concrete (@ base)			Drilled Diameter	168	mm				
Diameter	550	mm	Bar Diameter	32	mm				
Height	2	m	# of Tie-Backs:	22	ea				
Volume/hole	0.475166	m3	Total Tie-Back Length	176	m				
# of holes	22		Drilling Price:	\$65.45	/m				
Total Volume	10.454	m3	Drilling Cost:	\$11,520.00					
Concrete Price	\$650.00	/m3	Weight of Tie-back (DYWIDAG)	6.40	kg/m				
Total Concrete Cost:	\$6,794.87		Total Weight:	1126.4	kg				
			TIE-BACK ROD PRICE:	\$3,942.40					
			Grout Volume	0.09975185	m3				
			Total Grout Volume	2.19454070	m3				
			Grout Price	\$400.00	/m3				
			Total Grout Price	\$877.82					

TIMBER-PRELIMINARY								
# Piles:	22							
Average Height:	7.1	m						
Timber Dimensions:								
Width	0.076	m						
Height	0.254	m						
Length	3.049	m						
Timber @ 1 Section	28							
TOTAL TIMBER:	589	ea						
Vol. Per 1 Timber	0.0590	m3						
Total Volume of Timber:	34.7693	m3						
Daily Output	2.120	m3/Day						
Timber Installed per Day	35.91	ea/day						
Days to Install Timber	16.4	days						
Labour Cost (2 labouer):	\$567.20	/day						
Labour Price:	\$9,302.44							
Material Cost:	\$451.20	/m3						
Material Price:	\$15,687.93							
TOTAL PRELIMINARY TIMBER PRICE:	\$24,990.37							

SOIL NAILING - PRELIMINARY							
Number of Nails	149	ea					
Nail Length	5.79	m					
Total Length	863.11	m					
Weight	6.40	kg/m					
Total Weight	5523.90	kg					
Material Price	\$3.50	/kg					
Total Nail Material Price	\$19,333.66						
Diameter	0.203252033	m					
Shotcrete Thickness	0.101626016	m					
Area for Mesh	332.2616	m2					
Shotcrete w/ Mesh	\$430.60	/m2					
Shotcrete w/ Mesh Cost:	\$143,071.84						
Grout Volume	0.187948746	m3					
Total Grout Volume	28.0043632	m3					
Grout Price	400	/m3					
Grout Cost:	\$11,201.75						
Drilled Diameter	200	mm					
Total Drilled Length	863.1097561	m					
Drilling Price (% of greater diam drilled)	\$65.45	/m					
Drilling Cost:	\$56,494.46						
Dist from Toronto to St. John's	3075	km					
price per distance (km)	\$1.26	/km					
Shipping Cost:	\$3,874.50						
Cost to pay a contractor to come from the m	nainland and do the project will increase the	e cost					
greatly							

EXCAVATION										
Excavation in Soil										
EXCAVATION (WHOLE CONSTRUCTION AREA)	2898.8	m2								
VOLUME EXCAVATED (avg height=7.5m)	21741.00	m3								
Excavation in Rock	Excavation in Rock									
VOLUME EXCAVATED (under concrete wall)	46.14	m3								
COSTS										
Price in Soil	\$15.70	/m3								
Cost-Soil	\$341,333.72									
Price in Rock (soil price x 2.5)	\$39.25	/m3								
Cost-Rock	\$1,811.15									

	DRILLING	G
Diameter :	550	mm
Pile #	Length in Soil (m)	Length in Rock (m)
1	6.56	4.000
2	6.56	3.500
3	7.35	4.000
4	8.24	4.250
5	8.24	3.500
6	8.52	3.500
7	8.52	3.000
8	8.52	3.250
9	8.52	3.500
10	8.1	3.500
11	7.6	3.250
Total (m)	86.73	39.25
Price (soil)	\$180.00	/m
Total Cost:	\$15,611.40	
Price (rock)	\$550.00	
Total Cost:	\$21,587.50	

				STEEL PILES				
Pile #	Height (m) Unit	Concrete @ embe	dment depth			Steel Casing	
	1	9.5 m						
	2	9.5 m	Diameter		550 r	nm	Rented	
	3	10.5 m	Height		3 r	n	# of Casings	11
	4	11.5 m	Volume/hole		0.712749 r	n3	Length	120.5 m
	5	11.5 m	# of holes		11		weight of casing	372 kg/m
	6	11.5 m	Total Volume		7.840 r	n3	Total Weight	44826 kg
	7	11.5 m	Concrete Price		650 /	′m3**	Material Price	\$3.50 /kg
	8	11.5 m		**price confirmed by client			Total Cost (New Material)	\$156,891.00
	9	11.5 m	Concrete Cost:		\$5,096.15		Rented Cost (10% New)	\$15,689.10
	10	11.5 m			-			
	11	10.5 m						
Total Length of Steel		120.5 m						
Weight of Steel		110 kg/m						
Total Weight:		13255 kg						
Material Price		\$3.50 /kg						
Material Cost:	\$	<mark>46,392.50</mark>						
*price confirmed by client								
**accounts for any shipping								

TIMBER

WALL HEIGHT	HEIGHT SECTIONS (m)	# of Sections	QTY	W	Н	L
9.5	2.5	6	59.04	0.10	0.25	3.05
0.5	6	6	283.4	0.10	0.25	3.05
7 5	2.5	2	19.68	0.10	0.25	3.05
7.5	5	2	78.72	0.10	0.25	3.05
6.5	2.5	2	19.68	0.10	0.25	3.05
0.5	4	2	62.98	0.10	0.25	3.05
	WALL HEIGHT 8.5 7.5 6.5	$ \begin{array}{c} 2.5 \\ \hline 8.5 \\ \hline 7.5 \\ \hline 5 \\ \hline 2 5 \\ 2 5 \\ \hline 2 5 \\ \hline 2 5 \\ 2 5 \\ \hline 2 5 \\ 2 5 \\ \hline 2 5 \\ \hline 2 5 \\ 2 5 \\ \hline 2 5 \\ 2 5 \\ \hline 2 5 \\ 2 5 \\ $	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$

Option 2: is to use 250*100mm for first 2.5 meters,

and use 2*250*100mm for depth greater than 2.5 meters.

		TOTAL TIMBER:	523.488 ea
		Total Volume of Timber:	41.21 m3
Volume of Each Timber	0.08	m3	
Daily Output	2.36	m3	
Timber Placed/Day	29.98	ea/day	
Days to Place All Timber	17.5	Days	
Labourer(2)	\$567.20	/Day	2 Labourers
Labour Cost:	\$9,903.92		
Materials:	\$451.20	/m3	
Material Cost:	\$18,593.10		
Tatal Timber Cast	620 407 04		
Total Timber Cost:	\$28,497.01		

Blocking	W		н	L
Dimensions (m)		0.051	0.102	2.4
Total Timber		523.488		
Blocking/Timber		4	ea	
Blocking Length (section w/ 1 timber)		420	mm	
Blocking Length (section w/ 2 timber)		220	mm	
Blocking Amount (1 timber section)		393.6		
Blocking Amount (2 timber section)		1700.35		
Total Length (1)		165.31	m	
Total Length (2)		374.08	m	
# of pieces of lumber:		221	рс	
Price of Lumber 2x4x8)		\$2.79	/pc	
Blocking Price:		\$617.01		

TIMBER + BLOCKING:

\$29,114.02

Tie-Back	
Length (un-grouted)	4.5 m
Length (grouted)	4.5 m
Drilled Diameter	168 mm
Bar Diameter	32 mm
# of Tie-Backs:	19 ea
Total Tie-Back Length	171 m
Drilling Price (**% of larger drilling cost)	\$65.45 /m
Drilling Cost	<mark>\$11,192.73</mark>
Weight of Tie-back (DYWIDAG)	6.40 kg/m
Total Weight:	1094.4 kg
Steel Price	\$3.50 /kg
TIE-BACK ROD PRICE:	<mark>\$3,830.40</mark>
Grout Volume	0.14137167 m3
TOTAL GROUT VOLUME	2.68606172 m3
Grout Price	\$400.00 /m3
Grout Cost:	<mark>\$1,074.42</mark>
Steel Beam Cut/Replace	
Steel Strip (100mmx12mm)	3 m
Amount of Steel Strip	10 ea
Total Length of Strip	30 m
Weight of Strip	94.2 kg/m2
Weight/Strip	0.11304
Total Strip Weight	4.3912 kg
Steel Price	\$3.50 /kg
Total Strip Cost:	\$15. 37
L - angle (L200x100x13) (to secure tie-back)	29.5 kg/m
Length of angles	155 mm
total weight of angles:	4.5725 KG
Steel Price	\$3.50 /kg
Total Strip Cost:	\$16.00

			RIGID GI	RAVITY WALL				
DESCRIPTION		UNIT		FORMWORK			TOTAL	UNIT
CONCRETE WALL				BACK AREA	1	60	60	m2
WALL LENGTH	15	m		SIDE AREA	2	5	10	m2
WALL HEIGHT	4	m		FRONT AREA	1	64.08	64.08	m2
TOP WIDTH	0.5	m						
BASE WIDTH	2	m		TOTAL FORMWORK AREA			134.08	m2
				say 3 labourers and 1 carp				
CONCRETE VOLUME	75	m3		and 2 days				
			confirmed					
Concrete Price:	650	/m3	by client	Days for Formwork	2.00			
Concrete Cost:	\$48,750.00			Labour Price	\$1,210.00	/day		
				Labour Cost	\$2,420.00			
WEEP HOLES	10	ea		Materials:	\$22.38	/m2		
DIAMETER	0.08	m		Material Cost	\$3,000.71			
0.5 < L < 2 M (say 1.5m length)	1.5	m		Total Formwork Cost:	\$5,420.71			
PVC PRICE-KENTS.CA	\$13.49	/pc						
4" diameter - 10' length		· ·						
say 2 pipes from one piece (plus one just								
in case?)	6.00							
PVC PRICE:	\$80.94			TOTAL CONCRETE WALL COST:		\$54,251.65		
Material Cost:	\$80.94							
Labour-Drill holes in formwork and place								
pipe - can be included with formwork price								

					RSMEANS	VALUES					
TII	MBER										
	LINE #	DESCRIPTION	UNIT	CREW	DAILY OUTPUT	LABOUR HOURS	BARE MATERIAL	BARE LABOUR	BARE EQUIPMENT	BARE TOTAL	TOTAL O&P
		Framing, heavy mill timber, beams, built from 100mm lumber, multiple									
0	61323100270	100mm x 250mm	m3	2 Carp	2.36	6.781	518.4	252.24		770.64	959.89
FC	RMWORK										
	LINE #	DESCRIPTION	UNIT	CREW	DAILY OUTPUT	LABOUR HOURS	BARE MATERIAL	BARE LABOUR	BARE EQUIPMENT	BARE TOTAL	TOTAL O&P
0	31113854900	Retaining Wall,battered, job-built plywood, over 2.4 to 4.8m high, 1 use	m2CA	C2	22.3	2.153	22.38	79.24	0	101.62	146.86
SC	DIL NAILING										
	LINE #	DESCRIPTION	UNIT	CREW	DAILY OUTPUT	LABOUR HOURS	BARE MATERIAL	BARE LABOUR	BARE EQUIPMENT	BARE TOTAL	TOTAL O&P
		Grouted soil nailing material delivery add \$1.14 to \$1.26 per truck km for	-	-							
	31323616006	0 shipping									
1	Crew Prices	Daily	1								
	1 Laborer	\$283.60)								
	1 Carpenter	359.2	!								

Appendix K

Construction Schedule

Duckworth Street Retaining Wall Construction Scehdule



Project Length Start Mobilization Soldier Pile Insta				Finish		1 Mar '13		14 Apr '1		28 A			12 May '1		26 M				un '13
Start Mobilization		2 days	Mon 01/04/13	Tue 11/06/13	F	T	S W	S	T M	F	T S	W	S	T M	F	T S	W	S	
Mobilization		days		Mon 01/04/13		01/04												Ĩ	
		. day		Mon 01/04/13															
		6 days	Tue 02/04/13																
Drill Boreholes		1 days	Tue 02/04/13			Č – – –													
Install Piles/St		days	Tue 16/04/13																
Pour Embeddi	ng Concrete 4	days	Tue 16/04/13	Fri 19/04/13															
Excavate Soil &	& Bedrock 1	4 days	Thu 18/04/13	Tue 07/05/13															
Install Lagging	1	4 days	Thu 18/04/13	Tue 07/05/13															
Tieback Installat	ion 1	2 days	Fri 10/05/13	Mon 27/05/13															
Drill Tieback H	oles 7	' days	Fri 10/05/13	Mon 20/05/13															
		•																	
Complete Perf Proof Tests	ormance and 3	days	Mon 20/05/13	Wed 22/05/13															
Lock-off and st	tress 3	days	Wed 22/05/13	Fri 24/05/13															
Place seconda	ry grout 2	days	Fri 24/05/13	Mon 27/05/13										(
Backfill and Com	pact Soil 2	days	Tue 28/05/13	Wed 29/05/13											Ľ	3		—	
Gravity Wall Inst	allation 3	6 days	Mon 22/04/13	Mon 10/06/13															
Excavation																			
											Ĩ								
•												Ċ							
														Ľ					
		•																	1
End	0) days	Tue 11/06/13	Tue 11/06/13															11/0
	Excavate Soil & Install Lagging Tieback Installat Drill Tieback H Install & Grout Complete Perf Proof Tests Lock-off and st Place seconda Backfill and Com Gravity Wall Inst Excavation Formwork Inst Pour/Place Co	Excavate Soil & Bedrock1Install Lagging1Tieback Installation1Drill Tieback Holes7Install & Grout Bar7Complete Performance and Proof Tests3Lock-off and stress3Place secondary grout2Backfill and Compact Soil3Excavation1Formwork Installation2Pour/Place Concrete Wall1Cure/Set Concrete1Demobilize1	Excavate Soil & Bedrock14 daysInstall Lagging14 daysTieback Installation12 daysDrill Tieback Holes7 daysInstall & Grout Bar7 daysComplete Performance and Proof Tests3 daysLock-off and stress3 daysPlace secondary grout2 daysBackfill and Compact Soil2 daysExcavation10 daysFormwork Installation2 daysPour/Place Concrete Wall10 daysCure/Set Concrete14 daysDemobilize1 day	Excavate Soil & Bedrock14 daysThu 18/04/13Install Lagging14 daysThu 18/04/13Tieback Installation12 daysFri 10/05/13Drill Tieback Holes7 daysFri 10/05/13Install & Grout Bar7 daysFri 10/05/13Complete Performance and Proof Tests3 daysMon 20/05/13Lock-off and stress3 daysWed 22/05/13Place secondary grout2 daysFri 24/05/13Backfill and Compact Soil2 daysTue 28/05/13Formwork Installation36 daysMon 22/04/13Formwork Installation2 daysMon 06/05/13Pour/Place Concrete Wall10 daysWed 08/05/13Cure/Set Concrete14 daysWed 22/05/13Demobilize1 dayTue 11/06/13	Excavate Soil & Bedrock 14 days Thu 18/04/13 Tue 07/05/13 Install Lagging 14 days Thu 18/04/13 Tue 07/05/13 Tieback Installation 12 days Fri 10/05/13 Mon 27/05/13 Drill Tieback Installation 12 days Fri 10/05/13 Mon 20/05/13 Install & Grout Bar 7 days Fri 10/05/13 Mon 20/05/13 Complete Performance and Proof Tests 3 days Mon 20/05/13 Wed 22/05/13 Lock-off and stress 3 days Wed 22/05/13 Fri 24/05/13 Place secondary grout 2 days Fri 24/05/13 Mon 27/05/13 Backfill and Compact Soil 2 days Tue 28/05/13 Wed 29/05/13 Excavation 10 days Mon 22/04/13 Fri 03/05/13 Formwork Installation 2 days Mon 06/05/13 Tue 07/05/13 Pour/Place Concrete Wall 10 days Wed 08/05/13 Tue 21/05/13 Pour/Set Concrete 14 days Wed 22/05/13 Mon 10/06/13 Demobilize 1 day Tue 11/06/13 Tue 11/06/13	Excavate Soil & Bedrock 14 days Thu 18/04/13 Tue 07/05/13 Install Lagging 14 days Thu 18/04/13 Tue 07/05/13 Tieback Installation 12 days Fri 10/05/13 Mon 27/05/13 Drill Tieback Installation 12 days Fri 10/05/13 Mon 20/05/13 Install & Grout Bar 7 days Fri 10/05/13 Mon 20/05/13 Complete Performance and Proof Tests 3 days Mon 20/05/13 Wed 22/05/13 Lock-off and stress 3 days Wed 22/05/13 Fri 24/05/13 Place secondary grout 2 days Fri 24/05/13 Mon 27/05/13 Backfill and Compact Soil 2 days Tue 28/05/13 Wed 29/05/13 Formwork Installation 36 days Mon 22/04/13 Mon 10/06/13 Excavation 10 days Mon 06/05/13 Tue 07/05/13 Pour/Place Concrete Wall 10 days Wed 22/05/13 Mon 10/06/13 Demobilize 14 days Wed 22/05/13 Tue 11/06/13	Excavate Soil & Bedrock14 daysThu 18/04/13Tue 07/05/13Install Lagging14 daysThu 18/04/13Tue 07/05/13Tieback Installation12 daysFri 10/05/13Mon 27/05/13Drill Tieback Holes7 daysFri 10/05/13Mon 20/05/13Install & Grout Bar7 daysFri 10/05/13Mon 20/05/13Complete Performance and Proof Tests3 daysMon 20/05/13Wed 22/05/13Lock-off and stress3 daysWed 22/05/13Fri 24/05/13Place secondary grout2 daysFri 24/05/13Mon 27/05/13Gravity Wall Installation36 daysMon 22/04/13Mon 10/06/13Excavation10 daysMon 22/04/13Fri 03/05/13Formwork Installation2 daysMon 06/05/13Tue 07/05/13Pour/Place Concrete Wall10 daysWed 08/05/13Tue 21/05/13Demobilize1 dayTue 11/06/13Tue 11/06/13	Excavate Soil & Bedrock14 daysThu 18/04/13Tue 07/05/13Install Lagging14 daysThu 18/04/13Tue 07/05/13Tieback Installation12 daysFri 10/05/13Mon 27/05/13Drill Tieback Holes7 daysFri 10/05/13Mon 20/05/13Install & Grout Bar7 daysFri 10/05/13Mon 20/05/13Complete Performance and Proof Tests3 daysMon 20/05/13Wed 22/05/13Lock-off and stress3 daysWed 22/05/13Fri 24/05/13Place secondary grout2 daysFri 24/05/13Mon 27/05/13Backfill and Compact Soil2 daysTue 28/05/13Wed 29/05/13Gravity Wall Installation36 daysMon 22/04/13Mon 10/06/13Excavation10 daysMon 22/04/13Tue 07/05/13Pour/Place Concrete Wall10 daysWed 08/05/13Tue 21/05/13Demobilize1 dayTue 11/06/13Tue 11/06/13	Excavate Soil & Bedrock14 daysThu 18/04/13Tue 07/05/13Install Lagging14 daysThu 18/04/13Tue 07/05/13Tieback Installation12 daysFri 10/05/13Mon 27/05/13Drill Tieback Holes7 daysFri 10/05/13Mon 20/05/13Install & Grout Bar7 daysFri 10/05/13Mon 20/05/13Complete Performance and Proof Tests3 daysMon 20/05/13Wed 22/05/13Lock-off and stress3 daysWed 22/05/13Fri 24/05/13Place secondary grout2 daysFri 24/05/13Mon 27/05/13Backfill and Compact Soil2 daysTue 28/05/13Wed 29/05/13Formwork Installation36 daysMon 22/04/13Mon 10/06/13Formwork Installation2 daysMon 06/05/13Tue 07/05/13Pour/Place Concrete14 daysWed 22/05/13Tue 21/05/13Demobilize1 dayTue 11/06/13Tue 11/06/13	Excavate Soil & Bedrock14 daysThu 18/04/13Tue 07/05/13Install Lagging14 daysThu 18/04/13Tue 07/05/13Tieback Installation12 daysFri 10/05/13Mon 27/05/13Drill Tieback Holes7 daysFri 10/05/13Mon 20/05/13Install & Grout Bar7 daysFri 10/05/13Mon 20/05/13Complete Performance and Proof Tests3 daysMon 20/05/13Wed 22/05/13Lock-off and stress3 daysWed 22/05/13Fri 24/05/13Place secondary grout2 daysFri 24/05/13Mon 27/05/13Backfill and Compact Soil2 daysTue 28/05/13Wed 29/05/13Formwork Installation36 daysMon 22/04/13Mon 10/06/13Excavation10 daysMon 06/05/13Tue 07/05/13Pour/Place Concrete Wall10 daysWed 22/05/13Tue 21/05/13Demobilize1 dayTue 11/06/13Tue 11/06/13	Excavate Soil & Bedrock14 daysThu 18/04/13Tue 07/05/13Install Lagging14 daysThu 18/04/13Tue 07/05/13Tieback Installation12 daysFri 10/05/13Mon 27/05/13Drill Tieback Holes7 daysFri 10/05/13Mon 20/05/13Install & Grout Bar7 daysFri 10/05/13Mon 20/05/13Complete Performance and Proof Tests3 daysMon 20/05/13Wed 22/05/13Lock-off and stress3 daysWed 22/05/13Fri 24/05/13Place secondary grout2 daysFri 24/05/13Mon 27/05/13Backfill and Compact Soil2 daysTue 28/05/13Wed 29/05/13Excavation10 daysMon 06/05/13Tue 07/05/13Formwork Installation2 daysMon 06/05/13Tue 07/05/13Pour/Place Concrete14 daysWed 22/05/13Mon 10/06/13Cure/Set Concrete14 daysWed 22/05/13Mon 10/06/13Demobilize1 dayTue 11/06/13Tue 11/06/13	Excavate Soil & Bedrock14 daysThu 18/04/13Tue 07/05/13Install Lagging14 daysThu 18/04/13Tue 07/05/13Tieback Installation12 daysFri 10/05/13Mon 27/05/13Drill Tieback Holes7 daysFri 10/05/13Mon 20/05/13Install & Grout Bar7 daysFri 10/05/13Mon 20/05/13Complete Performance and Proof Tests3 daysMon 20/05/13Wed 22/05/13Lock-off and stress3 daysWed 22/05/13Fri 24/05/13Place secondary grout2 daysFri 24/05/13Mon 27/05/13Backfill and Compact Soil2 daysTue 28/05/13Wed 29/05/13Formwork Installation36 daysMon 22/04/13Fri 03/05/13Formwork Installation2 daysMon 06/05/13Tue 07/05/13Pour/Place Concrete14 daysWed 22/05/13Tue 21/05/13Demobilize1 dayTue 11/06/13Tue 11/06/13	Excavate Soil & Bedrock 14 days Thu 18/04/13 Tue 07/05/13 Install Lagging 14 days Thu 18/04/13 Tue 07/05/13 Tieback Installation 12 days Fri 10/05/13 Mon 27/05/13 Drill Tieback Holes 7 days Fri 10/05/13 Mon 20/05/13 Install & Grout Bar 7 days Fri 10/05/13 Mon 20/05/13 Complete Performance and Proof Tests 3 days Mon 20/05/13 Wed 22/05/13 Lock-off and stress 3 days Wed 22/05/13 Fri 24/05/13 Place secondary grout 2 days Fri 24/05/13 Mon 27/05/13 Backfill and Compact Soil 2 days Tue 28/05/13 Wed 29/05/13 Excavation 10 days Mon 22/04/13 Fri 03/05/13 Formwork Installation 2 days Mon 06/05/13 Tue 07/05/13 Pour/Place Concrete 14 days Wed 22/05/13 Mon 10/06/13 Demobilize 1 day Tue 11/06/13 Tue 11/06/13	Excavate Soil & Bedrock 14 days Thu 18/04/13 Tue 07/05/13 Install Lagging 14 days Thu 18/04/13 Tue 07/05/13 Tieback Installation 12 days Fri 10/05/13 Mon 27/05/13 Drill Tieback Holes 7 days Fri 10/05/13 Mon 20/05/13 Install & Grout Bar 7 days Fri 10/05/13 Mon 20/05/13 Complete Performance and Proof Tests 3 days Mon 20/05/13 Wed 22/05/13 Lock-off and stress 3 days Wed 22/05/13 Fri 24/05/13 Place secondary grout 2 days Fri 24/05/13 Mon 27/05/13 Backfill and Compact Soil 2 days Fri 24/05/13 Wed 29/05/13 Formwork Installation 36 days Mon 22/04/13 Fri 03/05/13 Formwork Installation 2 days Mon 02/05/13 Tue 21/05/13 Pour/Place Concrete 14 days Wed 22/05/13 Mon 10/06/13 Demobilize 1 day Tue 11/06/13 Tue 11/06/13	Excavate Soil & Bedrock 14 days Thu 18/04/13 Tue 07/05/13 Install Lagging 14 days Thu 18/04/13 Tue 07/05/13 Tieback Installation 12 days Fri 10/05/13 Mon 27/05/13 Drill Tieback Holes 7 days Fri 10/05/13 Mon 20/05/13 Install & Grout Bar 7 days Fri 10/05/13 Mon 20/05/13 Complete Performance and Proof Tests 3 days Mon 20/05/13 Wed 22/05/13 Lock-off and stress 3 days Wed 22/05/13 Fri 24/05/13 Place secondary grout 2 days Fri 24/05/13 Mon 27/05/13 Gravity Wall Installation 36 days Mon 22/04/13 Mon 27/05/13 Formwork Installation 2 days Fri 24/05/13 Wed 29/05/13 Formwork Installation 2 days Mon 22/04/13 Mon 10/06/13 Excavation 10 days Mod 20/05/13 Tue 21/05/13 Pour/Place Concrete 14 days Wed 22/05/13 Mon 10/06/13 Demobilize 1 day Tue 11/06/13 Tue 11/06/13	Excavate Soil & Bedrock 14 days Thu 18/04/13 Tue 07/05/13 Install Lagging 14 days Thu 18/04/13 Tue 07/05/13 Tieback Installation 12 days Fri 10/05/13 Mon 27/05/13 Drill Tieback Holes 7 days Fri 10/05/13 Mon 20/05/13 Install & Grout Bar 7 days Fri 10/05/13 Mon 20/05/13 Complete Performance and 3 days Mon 20/05/13 Wed 22/05/13 Proof Tests 3 asys Mon 27/05/13 Lock-off and stress 3 days Wed 22/05/13 Fri 24/05/13 Place secondary grout 2 days Fri 24/05/13 Mon 27/05/13 Backfill and Compact Soil 2 days Tue 28/05/13 Wed 29/05/13 Formwork Installation 36 days Mon 22/04/13 Mon 10/06/13 Excavation 10 days Mon 22/05/13 Tue 21/05/13 Pour/Place Concrete 14 days Wed 82/05/13 Tue 21/05/13 Puenobilize 1 day Tue 11/06/13 Tue 11/06/13	Excavate Soil & Bedrock 14 days Thu 18/04/13 Tue 07/05/13 Install Lagging 14 days Thu 18/04/13 Tue 07/05/13 Tieback Installation 12 days Fri 10/05/13 Mon 22/05/13 Drill Tieback Holes 7 days Fri 10/05/13 Mon 20/05/13 Install & Grout Bar 7 days Fri 10/05/13 Mon 20/05/13 Complete Performance and Proof Tests 3 days Mon 22/05/13 Wed 22/05/13 Lock-off and stress 3 days Wed 22/05/13 Mon 27/05/13 Place secondary grout 2 days Fri 24/05/13 Mon 22/04/13 Backfill and Compact Soil 2 days Tue 28/05/13 Wed 29/05/13 Excavation 10 days Mon 22/04/13 Tue 07/05/13 Pour/Place Concrete Wall 10 days Wed 08/05/13 Tue 21/05/13 Pumobilize 1 day Tue 11/06/13 Tue 11/06/13 Tue 11/06/13	Excavate Soil & Bedrock14 daysThu 18/04/13Tue 07/05/13Install Lagging14 daysThu 18/04/13Tue 07/05/13Tieback Installation12 daysFri 10/05/13Mon 22/05/13Drill Tieback Holes7 daysFri 10/05/13Mon 20/05/13Install & Grout Bar7 daysFri 10/05/13Mon 20/05/13Complete Performance and Proof Tests3 daysMon 20/05/13Wed 22/05/13Lock-off and stress3 daysWed 22/05/13Fri 24/05/13Place secondary grout2 daysFri 24/05/13Won 22/04/13Place secondary grout2 daysTue 28/05/13Wed 29/05/13Backfill and Compact Soil2 daysMon 22/04/13Mon 10/06/13Excavation10 daysMon 06/05/13Tue 07/05/13Formwork Installation2 daysMon 06/05/13Tue 07/05/13Pour/Place Concrete Wall10 daysWed 88/05/13Tue 21/05/13Demobilize1 dayTue 11/06/13Tue 11/06/13	Excavate Soil & Bedrock 14 days Thu 18/04/13 Tue 07/05/13 Install Lagging 14 days Thu 18/04/13 Tue 07/05/13 Tieback Installation 12 days Fri 10/05/13 Mon 27/05/13 Drill Tieback Holes 7 days Fri 10/05/13 Mon 20/05/13 Complete Performance and Proof Tests 3 days Mon 20/05/13 Wed 22/05/13 Lock-off and stress 3 days Mon 20/05/13 Wed 22/05/13 Place secondary grout 2 days Fri 24/05/13 Wed 29/05/13 Backfill and Compact Soil 2 days Fri 24/05/13 Wed 29/05/13 Gravity Wall Installation 36 days Mon 20/05/13 Wed 29/05/13 Excavation 10 days Mon 20/05/13 Wed 29/05/13 Pour/Place Concrete Wall 10 days Wed 88/05/13 Tue 21/05/13 Pour/Place Concrete 14 days Wed 22/05/13 Mon 06/06/13 Demobilize 1 day Tue 11/06/13 Tue 11/06/13

QCEC Staff Contact Information

Chantel Nicolle

Phone: 709-691-4507 Email: <u>cjn518@mun.ca</u>

Erica Soucy

Phone: 709-631-2176 Email: <u>esoucy@mun.ca</u>

Qiong Zhang

Phone: 709-763-5998 Email: <u>q.zhang@mun.ca</u>

Chenel Waight

Phone: 709-749-2780 Email: <u>cwaight@mun.ca</u>



Quality Civil Engineering

S.J. Carew Building St. John's, NL A1B 3X5